PROJECT REFERENCE NO.	SHEET NO.
W-5601N	3

REVISIONS

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

ITEM	SECT	QUANTITY	UNIT	ITEM DESCRIPTION
1	800	1	LS	MOBILIZATION
2	801	1	LS	CONSTRUCTION SURVEYING
3	226	1	LS	GRADING
4	226	200	CY	UNDERCUT EXCAVATION
5	300	788	TON	FOUNDATION CONDITIONING MATERIAL,MINOR STRUCTURES
6	300	270	SY	FOUNDATION CONDITIONING GEOTEXTILE
7	310	418	LF	15" RC PIPE CULVERTS,CLASS IV
8	310	314	LF	18" RC PIPE CULVERTS,CLASS IV
9	310	56	LF	24" RC PIPE CULVERTS,CLASS IV
10	340	98	LF	PIPE REMOVAL
11	520	400	TON	AGGREGATE BASE COURSE
12	545	200	TON	INCIDENTAL STONE BASE
13	610	860	TON	ASPHALT CONCRETE BASE COURSE,TYPE B25.0B
14	610	850	TON	ASPHALT CONCRETE INTERMEDIATE COURSE,TYPE I19.0B
15	610	675	TON	ASPHALT CONCRETE SURFACE COURSE,TYPE S9.5B
16	620	120	TON	ASPHALT BINDER FOR PLANT MIX
17	840	10	EA	MASONRY DRAINAGE STRUCTURES
18	840	1	EA	MANHOLE COVER AND FRAME,STD. 840.54
19	840	7	EA	FRAME WITH GRATE AND HOOD,STD. 840.03,TYPE E
20	840	2	EA	FRAME WITH GRATE AND HOOD,STD. 840.03,TYPE G
21	846	50	LF	2'-6" CONCRETE GUTTER
22	846	325	LF	1'-6" CONCRETE CURB & GUTTER
23	846	1,100	LF	2'-6" CONCRETE CURB & GUTTER
24	SP	1	EA	MODIFIED CONCRETE FLUME
25	852	460	SY	5" MONOLITHIC ISLANDS (SURFACE MOUNTED)
26	SP	500	SY	6" CONCRETE TRUCK APRON
27	876	10	TON	RIP RAP,CLASS I
28	876	10	TON	RIP RAP,CLASS B
29	876	400	SY	GEOTEXTILE FOR DRAINAGE
30	1105	1	LS	TEMPORARY TRAFFIC CONTROL
31	SP	224	SF	WORK ZONE ADVANCE/ GENERAL WARNING SIGNING
32	1205	2450	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4",120 MILS)
33	1205	70	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12",120 MILS)
34	1205	20	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTERS (120 MILS)
35	1205	8	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
36	1205	20	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (120 MILS)
37	1605	1700	LF	TEMPORARY SILT FENCE
38	1610	5	TON	STONE FOR EROSION CONTROL, CLASS B
39	1610	15	TON	SEDIMENT CONTROL STONE
40	1615	1	ACRE	TEMPORARY MULCHING
41	1620	50	LB	SEED FOR TEMPORARY SEEDING
42	1620	0.2	TON	FERTILIZER FOR TEMPORARY SEEDING
43	1631	700	SY	MATTING FOR EROSION CONTROL
44	1632	380	LF	1/4" HARDWARE CLOTH
45	SP	180	LF	WATTLE
46	SP	5	LB	POLYACRYLAMIDE (PAM)
47	1660	1	ACRE	SEEDING AND MULCHING
48	1661	50	LB	SEED FOR REPAIR SEEDING
49	1661	0.2	TON	FERTILIZER FOR REPAIR SEEDING
50	SP	4	EA	RESPONSE FOR EROSION CONTROL

28-MAY-2015 15:54
C:\APTCS\SCRATCH\IVYMILLS\IVYMILLS_ddc2_psh_3.dgn
$$$$USERNAME$$$$