



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY
GOVERNOR

ANTHONY J. TATA
SECRETARY

June 17, 2014

CONTRACT: DB00189
TIP NUMBER: K-5101
WBS ELEMENT: 42229.3.FS1
COUNTY: Craven
ROUTE: US 70
DESCRIPTION: Rest Area Renovation
ADDENDUM NUMBER 2

TO: Prospective Bidders

Please note the following revision to the contract proposal for the above-referenced project.

The following corrections, clarifications, or supplemental information is to be incorporated into the Contractor(s) bid to perform the Work:

CHANGES TO DRAWINGS:

1. None.

CLARIFICATIONS:

1. Horizontal blocking is required at exterior wall sheathing at 48" o.c. per note 5.6 on drawing S4.1.
2. In reference to drawings A15/A2.1, G15/A2.1, A15/A2.2, and G15/A2.2 at exterior fiber-cement walls, 1"x2" battens to be applied and match fiber-cement siding specification 074646.
3. Drawing S1.2 – Referenced Section detail 5/S4.1 does not exist. Change all references for this detail to 4/S4.1.
4. Drawing S4.1, Note 5.7 – The note calls for 19/32 sheathing for the roof. Architectural plan note 061600E2 calls for 3/4" T&G plywood. Provide 3/4" sheathing. 2x10 blocking is required at the rafters.
5. Drawing S1.1 – Shear walls are indicated. See note 13/S1.1.
6. Drawing 15/S2.1 – This detail applies at all shear wall ends. See note 13/S1.1.

CHANGES TO SPECIFICATIONS

1. Section No. 074646 dated 1-10-2014:
 - a. Modify paragraph 1.2.A: remove phrase "and soffit".
 - b. Delete paragraph 1.5.C.2 in its entirety.
 - c. Modify paragraph 1.8.A 1: remove "and soffit".
 - d. Modify paragraph 1.9.A 1: remove "and soffit".
 - e. Delete paragraph 2.3 in its entirety.
2. Section No. 074113 dated 1-10-2014:
 - a. Modify paragraph 2.2.B.2.a: replace "Nominal Thickness: 0.38 inch." with "Nominal Thickness: 0.038 inch."

MAILING ADDRESS:
DIVISION TWO - OPERATIONS
P.O. BOX 1587
GREENVILLE, NC 27835

TELEPHONE: (252) 439-2800
FAX: (252) 830-3341
WEBSITE: WWW.NCDOT.GOV

LOCATION:
1704 N GREENE ST
GREENVILLE, NC

- b. Add paragraph 2.7: "METAL SOFFIT PANELS"
- c. Add paragraph 2.7.A: "General: Provide factory-formed metal soffit panels designed to be installed by lapping and interconnecting side edges of adjacent panels and mechanically attaching through panel to supports using concealed fasteners and factory-applied sealant in side laps. Include accessories required for weathertight installation."
- d. Add paragraph 2.7.B: "Flush-Profile Metal Soffit Panels: Solid panels formed with vertical panel edges and flat pan between panel edges; with flush joint between panels."
- e. Add paragraph 2.7.B.1: "Manufacturers: Same as roofing panels."
- f. Add paragraph 2.7.B.2: "Material: Same material, finish, and color as metal roof panels."

Sincerely,



Sarah Lentine
Division Contract Officer

Attachment

cc: Mr. Ed Eatmon, PE
Mr. Bill Kincannon, PE
Ms. Betty Caldwell, PE