



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

JAMES H. TROGDON, III
SECRETARY

June 22, 2019

CONTRACT: DB00453
WBS ELEMENT: 17BP.2.R.88
COUNTY: BEAUFORT
ROUTE: SR 1742
DESCRIPTION: REPLACEMENT OF BEAUFORT COUNTY BRIDGE 135

NOTICE TO PROSPECTIVE BIDDERS
ADDENDUM 1

TO: PROSPECTIVE BIDDERS

Please note the following revisions to the proposal.

- Revised line item #77 to 3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS. An attached Itemized Proposal sheet is attached
- A revised electronic file has been uploaded to bid express named DB00453.001

Please make sure to sign the addendum page in the proposal to acknowledge this addendum.

Sincerely,

DocuSigned by:
Mary Voelker Moore
714C11DCCEBC4C6...

Mary Voelker Moore, PE
Division Contract Engineer

cc: Mr. Michael Aman, PE
Mr. Rhett Gerrald, PE
Mr. Jeff Cabaniss, PE
Ms. Claudia Wainwright

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION 2
PROJECT DEVELOPMENT GROUP
GREENVILLE, NC 27834

Telephone: (252) 439-2828
Customer Service: 1-877-368-4968

Website: www.ncdot.gov

Location:
1037 W.H. SMITH BLVD.
GREENVILLE, NC 27834

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	TYPE II MODIFIED APPROACH FILL, STATION ***** 14+84.50	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	300 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	10 TON		
0009	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	20 SY		
0010	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	44 LF		
0011	1330000000-E	607	INCIDENTAL MILLING	231 SY		
0012	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	210 TON		
0013	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	240 TON		
0014	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	30 TON		
0015	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0016	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	200 SY		
0017	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	34 CY		
0018	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2070000000-N	815	SUBDRAIN PIPE OUTLET	1		EA
0020	2077000000-E	815	6" OUTLET PIPE	6		LF
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2		EA
0022	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2		EA
0023	2556000000-E	846	SHOULDER BERM GUTTER	125		LF
0024	2612000000-E	848	6" CONCRETE DRIVEWAY	20		SY
0025	3030000000-E	862	STEEL BEAM GUARDRAIL	120		LF
0026	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5		EA
0027	3215000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE III	4		EA
0028	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	4		EA
0029	3649000000-E	876	RIP RAP, CLASS B	2		TON
0030	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	200		SY
0031	5326000000-E	1510	10" WATER LINE	157		LF
0032	5326200000-E	1510	12" WATER LINE	289		LF
0033	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	1,010		LB
0034	5552000000-E	1515	10" VALVE	2		EA
0035	5649000000-N	1515	RECONNECT WATER METER	1		EA
0036	5802000000-E	1530	ABANDON 10" UTILITY PIPE	442		LF
0037	5872600000-E	1550	DIRECTIONAL DRILLING OF *** 12"	289		LF
0038	6000000000-E	1605	TEMPORARY SILT FENCE	1,050		LF

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	65 TON		
0040	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	15 TON		
0041	6012000000-E	1610	SEDIMENT CONTROL STONE	15 TON		
0042	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0043	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0044	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1 TON		
0045	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0046	6029000000-E	SP	SAFETY FENCE	400 LF		
0047	6030000000-E	1630	SILT EXCAVATION	20 CY		
0048	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,400 SY		
0049	6037000000-E	SP	COIR FIBER MAT	100 SY		
0050	6042000000-E	1632	1/4" HARDWARE CLOTH	50 LF		
0051	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	80 SY		
0052	6071012000-E	SP	COIR FIBER WATTLE	150 LF		
0053	6071014000-E	SP	COIR FIBER WATTLE BARRIER	220 LF		
0054	6071020000-E	SP	POLYACRYLAMIDE (PAM)	10 LB		
0055	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0056	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0057	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0058	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0059	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0060	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
0061	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0062	6123000000-E	1670	REFORESTATION	0.1 ACR		
0063	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** 14+84.50	Lump Sum	L.S.	
0064	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0065	8112730000-N	450	PDA TESTING	1 EA		
0066	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** 14+84.50	Lump Sum	L.S.	
0067	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	43.6 CY		
0068	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** 14+84.50	Lump Sum	L.S.	
0069	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	5,202 LB		
0070	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES HP 12X53	14 EA		
0071	8364000000-E	450	HP12X53 STEEL PILES	1,015 LF		
0072	8393000000-N	450	PILE REDRIVES	8 EA		
0073	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	140.3 LF		
0074	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	170 TON		
0075	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	180 SY		
0076	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0077	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	770 LF		

1351/June21/Q16495.5/D364931776000/E77 Total Amount Of Bid For Entire Project :
