STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

SECT	QUANTITY	UNIT	ITEM DESCRIPTION
800	1	LS	MOBILIZATION
801	1	LS	CONSTRUCTION SURVEYING
226	1	LS	GRADING
226	100	CY	UNDERCUT EXCAVATION
300	10	TON	FOUNDATION CONDITIONING MATERIAL,MINNOR STRUCTURES
300	30	SY	FOUNDATION CONDITIONING GEOTEXTILE
310	32	LF	12" RC PIPE CULVERTS,CLASS III
310	48	LF	15" RC PIPE CULVERTS,CLASS III
610	2700	TON	ASPHALT CONCRETE BASE COURSE,TYPE B25.0B
610	1500	TON	ASPHALT CONCRETE INTERMEDIATE COURSE,TYPE I19.0B
610	750	TON	ASPHALT CONCRETE SURFACE COURSE,TYPE S9.5B
620	240	TON	ASPHALT BINDER FOR PLANT MIX,GRADE PG64-22
840	17	EA	FRAMES WTH TWO GRATES,STD.840.22
SP	17	EA	CONVERT EXISTING DI TO (OFFSET DROP INLET)
840	3	EA	MASONRY DRAINAGE STRUCTURES
840	2	EA	FRAME WITH GRATE,STD.840J6
840	3	CY	PIPE COLLARS
1105	1	LS	TEMPORARY TRAFFIC CONTROL
1205	8450	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4",90 MILS)
1205	3900	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4",120 MILS)
1205	42	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOLS (90 MILS)
1610	20	TON	SEDIMENT CONTROL STONE
1620	300	LB	SEED FOR TEMPORARY SEEDING
1620	1.5	TON	FERTILIZER FOR TEMPORARY SEEDING
SP	4	EA	RESPONSE FOR EROSION CONTROL
1632	800	LF	1/4" HARDWARE CLOTH
1661	50	LB	SEED FOR REPAIR SEEDING
1661	.2	TON	FERTILIZER FOR REPAIR SEEDING
1660	6	ACRE	SEEDING AND MULCHING
SP	800	LF	WATTLE
SP	25	LB	POLYACRYLAMIDE (PAM)

8/17/99
REVISIONS
05-JUN-2015 08:27
C:\pwworking\DOT\NC 11 Median Turn Lanes\W5202K_psh3.dgn
$$$$USERNAME$$$$