DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

CROSS-SECTION SUMMARY

IN CUBIC YARDS

LOCATION (-L-)	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBANKMENT
15+00.00	1		2
15+50.00	4		11
16+00.00	8		19
16+50.00	11		25
17+00.00	9		30
17+50.00	6		53
17+55.00	0		7
18+00.00	7		42
18+50.00	9		11
22+00.00	0		0
22+50.00	4		1
23+00.00	11		6
23+50.00	14		17
24+00.00	9		31
24+50.00	8		39
25+00.00	6		55
25+13.00	1		19
25+50.00	4		36
28+50.00	0		0
29+00.00	4		22
29+50.00	5		24
30+00.00	4		31
30+50.00	5		39
31+00.00	4		59
31+17.00	1		29
31+50.00	4		42
32+00.00	12		18
32+17.71	3		0

LOCATION (-L-)	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBANKMENT
33+00.00	0		0
33+20.00	1		12
33+50.00	2		32
34+00.00	5		44
34+50.00	6		35
35+00.00	5		33
35+50.00	6		29
36+00.00	7		23
36+50.00	7		16
36+97.85	2		6
42+50.00	0		0
42+69.00	2		18
43+00.00	5		25
43+50.00	14		21
44+00.00	15		14
44+50.00	12		13
45+00.00	9		13
45+50.00	7		14
46+00.00	4		22
46+06.49	0		2
69+00.00	0		0
69+50.00	4		10
70+00.00	6		20
70+50.00	7		24
71+00.00	7		40
71+50.00	10		33
72+00.00	11		20
72+50.00	9		29
72+75.00	4		16

LOCATION (-L-)	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBANKMENT
86+00.00	0		0
86+11.00	1		12
86+50.00	5		39
87+00.00	7		42
87+50.00	6		43
88+00.00	5		35
88+50.00	5		31
88+81.00	2		21
89+00.00	1		11
89+50.00	3		16
89+51.69	0		0
91+00.00	0		0
91+50.00	5		5
92+00.00	8		13
92+50.00	9		19
93+00.00	9		23
93+50.00	9		27
94+00.00	8		30
94+26.00	3		20
94+50.00	3		15
94+87.52	3		6

LOCATION (-L-)	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBANKMENT
95+94.00	0		0
96+00.00	1		4
96+50.00	9		32
97+00.00	12		25
97+50.00	11		25
98+00.00	11		24
98+31.51	7		15
98+50.00	4		9
99+00.00	9		26
99+50.00	8		29
99+56.04	1		4
99+72.00	2		11
100+00.00	5		17
100+50.00	10		28
101+00.00	10		31
101+44.00	10		35
101+50.00	1		5
102+00.00	8		26
102+31.51	2		3
119+50.00	0		0
120+00.00	14		39
120+50.00	16		33
121+00.00	15		33
121+50.00	16		29
122+00.00	20		20
122+50.00	18		11
123+00.00	10		6
123+04.83	0		0

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT.

NOTE:
APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, BORROW EXCAVATION, FINE GRADING, CLEARING AND GRUBBING AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING."

Rev. 3/6/01
05-JUN-2015 08:30
C:\PROJECTS\TOPRN\NC 11 Median Turn Lanes\W5202K_X1A.dgn
$$$$USERNAME$$$$