PROJECT NO.	SHEET NO.	TOTAL NO.
49017	4	5

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	0 TO 1.75" MILLING SY	BASE COURSE, B25.0B TONS	INTERMEDIATE COURSE, I19.0B TONS	SURFACE COURSE, S9.5B TONS	ASPHALT BINDER FOR PLANT MIX TONS	ADJ. OF METER OR VALVE BOX EA	TEMPORARY SILT FENCE LF	COIR FIBER WATTLE LF	SEED & MULCHING AC
49017	Carteret	1	SR 1300	FROM 500' NORTH OF US 70 TO SR 1163	1	2	2WU	NO	NO	2.431	24.5	300	4.86	30,940	1,815	5,423	3,720	563	5	850	340	1.18
TOTAL FOR MAP NO. 1										**2.431**		**300**	**4.86**	**30,940**	**1,815**	**5,423**	**3,720**	**563**	**5**	**850**	**340**	**1.18**
TOTAL FOR PROJ NO. 49017										**2.431**		**300**	**4.86**	**30,940**	**1,815**	**5,423**	**3,720**	**563**	**5**	**850**	**340**	**1.18**
GRAND TOTAL										**2.431**		**300**	**4.86**	**30,940**	**1,815**	**5,423**	**3,720**	**563**	**5**	**850**	**340**	**1.18**