PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.02.13.20072.1	3	4

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	ASPHALT SURFACE TREATMENT, DOUBLE SEAL SY	EMULSION FOR ASPHALT SURFACE TREATMENT GAL
2016CPT.02.13.20072.1	Beaufort	1	SR 1717	FROM NC 99 TO END OF MAINT.	1	2	2WU	NO	NO	1.29	20	15,200	7,600
TOTAL FOR MAP NO. 1										**1.29**		**15,200**	**7,600**
2016CPT.02.13.20072.1	Beaufort	2	SR 1718	FROM US 264 TO NC 99	1	2	2WU	NO	NO	5.73	20	67,700	33,850
TOTAL FOR MAP NO. 2										**5.73**		**67,700**	**33,850**
2016CPT.02.13.20072.1	Beaufort	3	SR 1722	FROM SR 1719 TO SR 1718	1	2	2WU	NO	NO	3.68	19	41,100	20,550
TOTAL FOR MAP NO. 3										**3.68**		**41,100**	**20,550**
2016CPT.02.13.20072.1	Beaufort	4	SR 1731	FROM SR 1722 TO DEAD END	1	2	2WU	NO	NO	1.97	20	23,200	11,600
TOTAL FOR MAP NO. 4										**1.97**		**23,200**	**11,600**
2016CPT.02.13.20072.1	Beaufort	5	SR 1732	FROM SR 1718 TO DEAD END	1	2	2WU	NO	NO	6.14	19	70,100	35,050
TOTAL FOR MAP NO. 5										**6.14**		**70,100**	**35,050**
2016CPT.02.13.20072.1	Beaufort	6	SR 1745	FROM NC 92 TO SR 1746	1	2	2WU	NO	NO	1.13	20	13,400	6,700
TOTAL FOR MAP NO. 6										**1.13**		**13,400**	**6,700**
2016CPT.02.13.20072.1	Beaufort	7	SR 1746	FROM NC 92 TO SR 1750	1	2	2WU	NO	NO	0.85	18	9,000	4,500
TOTAL FOR MAP NO. 7										**0.85**		**9,000**	**4,500**
2016CPT.02.13.20072.1	Beaufort	8	SR 1747	FROM NC 99 TO SR 1722	1	2	2WU	NO	NO	1.17	20	13,800	6,900
TOTAL FOR MAP NO. 8										**1.17**		**13,800**	**6,900**
TOTAL FOR PROJ NO. 2016CPT.02.13.20072.1										**21.96**		**253,500**	**126,750**
GRAND TOTAL										**21.96**		**253,500**	**126,750**