



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY  
GOVERNOR

ANTHONY J. TATA  
SECRETARY

August 29, 2013

CONTRACT: DB00142  
WBS ELEMENT: 2C.007118, 2C.007119  
COUNTY: Beaufort  
ROUTE: SR 1306 (Fifteenth St.)  
DESCRIPTION: Mill and Resurface  
**ADDENDUM NUMBER 1**

TO: Prospective Bidders

Please note the following revision to the contract proposal for the above-referenced project.

- Replace Page 26 with the revised version attached, addressing the adjustment of manholes, meter boxes, and valve boxes.

If you should have any questions concerning this addendum, please call me at (252) 439-2807.

Sincerely,

A handwritten signature in cursive script that reads "Bullard".

Aaron Bullard, PE  
Division Contract Officer

Attachment

cc: Mr. Ed Eatmon, PE  
Mr. Bill Kincannon, PE

**FINAL SURFACE TESTING NOT REQUIRED:**

(5-18-04) (Rev. 5-15-12)

610

SP6 R45

Final surface testing is not required on this project.

**PAVING INTERSECTIONS:**

(7-1-95) (Rev. 8-21-12)

610

SP6 R67AR

Surface all unpaved intersections back from the edge of the pavement on the main line of the project at least 50 feet. The pavement placed in the intersection shall be of the same material and thickness placed on the main line of the project.

Resurface all paved intersections back to the ends of the radii, or as directed by the Engineer.

The base on the unpaved intersections will be placed and prepared for surfacing by State Forces.

Widen the pavement on curves as directed by the Engineer.

**ADJUSTMENT OF MANHOLES, METER BOXES, AND VALVE BOXES:**

Any required adjustments to manholes, meter boxes, or valve boxes will be performed by the Contractor using Department-furnished rings. There will be no additional compensation for this work as it shall be considered incidental to the asphalt paving operations.

**MATERIALS:**

(2-21-12) (Rev. 5-21-13)

1000, 1005, 1050, 1074, 1078, 1080, 1081, 1087, 1092

SP10 R01

Revise the *2012 Standard Specifications* as follows:

**Page 10-1, Article 1000-1, DESCRIPTION, line 14, add the following:**

Use materials which do not produce a mottled appearance through rusting or other staining of the finished concrete surface.