STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

SECT	QUANTITY	UNIT	ITEM DESCRIPTION
800	1	LS	MOBILIZATION
225	1	LS	GRADING
545	100	TON	INCIDENTAL STONE BASE
SP	2.9	SMI	SHOULDER RECONSTRUCTION
607	22394	SY	1.5" MILLING ASPHALT PAVEMENT
610	1533	TON	ASPHALT CONCRETE BASE COURSE,TYPE B25.0B
610	893	TON	ASPHALT CONCRETE INTERMEDIATE COURSE,TYPE I19.0B
610	3138	TON	ASPHALT CONCRETE SURFACE COURSE,TYPE S9.5B
620	299	TON	ASPHALT BINDER FOR PLANT MIX,GRADE PG64-22
848	240	SY	6" CONCRETE DRIVEWAYS
1105	1	LS	TEMPORARY TRAFFIC CONTROL
SP	152.72	SF	WORK ZONE ADVANCE/GENERAL WARNING SIGNING
1205	15893	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6",90 MILS)
1205	11246	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4",120 MILS)
1205	40	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6",120 MILS)
1205	60	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12",90 MILS)
1205	200	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24",120 MILS)
1205	8	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
1605	1100	LF	TEMPORARY SILT FENCE
SP	20	LF	WATTLE
1660	3.5	ACRE	SEEDING AND MULCHING
1661	50	LB	SEED FOR REPAIR SEEDING
1661	.2	TON	FERTILIZER FOR REPAIR SEEDING
SP	5	EA	RESPONSE FOR EROSION CONTROL

REVISIONS

8/17/99

17-NOV-2014 10:07
C:\WINDOWS\TEMP\TS\NC33_Redmond_US264_Widening\nc33_psh3.dgn
$$$$USERNAME$$$$