PROJECT NO.	SHEET NO.	TOTAL NO.
	1	2
NC 41		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	1½" MILLING SY	SURFACE COURSE, S9.5B TONS	ASPHALT BINDER FOR PLANT MIX TONS	2'-6" CURB & GUTTER LF	WHEELCHAIR RAMPS EA	ADJ. OF MANHOLES EA	ADJ. OF METER OR VALVE BOX EA
NC 41	Jones	1	NC 41	MILL AND RESURFACE FROM JONES BRIDGE 29 TO BEGINNING OF CURB AND GUTTER	1	2	2WU	NO	NO	0.041	28	674	59	4			1	
TOTAL FOR MAP NO. 1										**0.041**		**674**	**59**	**4**			**1**	
NC 41	Jones	2	NC 41	MILL AND RESURFACE FROM BEGINNING OF CURB AND GUTTER TO CROSSING OF NC 41 AND WEBER ST.	1	2	2WU	NO	NO	0.09	28	1,478	121	7			3	1
TOTAL FOR MAP NO. 2										**0.09**		**1,478**	**121**	**7**			**3**	**1**
NC 41	Jones	3	NC 41	MILL 10' ALONG GUTTER LINE EACH SIDE AND RESURFACE FROM CROSSING OF NC 41 AND WEBER ST. TO END OF CURB AND GUTTER	2	2	MU	NO	NO	0.575	45	6,747	1,279	77	120	14	3	2
TOTAL FOR MAP NO. 3										**0.575**		**6,747**	**1,279**	**77**	**120**	**14**	**3**	**2**
NC 41	Jones	4	NC 41	MILL AND RESURFACE FROM END OF CURB AND GUTTER TO 600' W OF SR 1368	1	2	MU	NO	NO	0.421	41	10,127	879	53			4	2
TOTAL FOR MAP NO. 4										**0.421**		**10,127**	**879**	**53**			**4**	**2**
NC 41	Jones	5	NC 41	PAVE EXISTING TRENTON YARD WITH 1.75" OF SURFACE	3	2		NO	NO	0.077	128		1,131	68				
TOTAL FOR MAP NO. 5										**0.077**			**1,131**	**68**				
TOTAL FOR PROJ NO. NC 41										**1.204**		**19,026**	**3,469**	**209**	**120**	**14**	**11**	**5**
GRAND TOTAL										**1.204**		**19,026**	**3,469**	**209**	**120**	**14**	**11**	**5**