STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

ITEM	SECT	QUANTITY	UNIT	ITEM DESCRIPTION
1	800	1	LS	MOBILIZATION
2	801	1	LS	CONSTRUCTION SURVEYING
3	SP	1	LS	GRADING
4	300	20	TON	FOUNDATION CONDITIONING MATERIAL,MINOR STRUCTURES
5	300	40	SY	FOUNDATION CONDITIONING GEOTEXTILE
6	310	120	LF	15" RC PIPE CULVERTS,CLASS IV
7	340	70	LF	PIPE REMOVAL
8	607	4,330	SY	MILLING ASPHALT PAVEMENT,1.5" DEPTH
9	610	1520	TON	ASPHALT CONCRETE BASE COURSE B25.0B
10	610	830	TON	ASPHALT CONCRETE INTERMEDIATE COURSE,TYPE I19.0B
11	610	1560	TON	ASPHALT CONCRETE SURFACE COURSE,TYPE S9.5B
12	620	205	TON	ASPHALT BINDER FOR PLANT MIX
13	1605	700	LF	TEMPORARY SILT FENCE
14	1615	1	ACRE	TEMPORARY MULCHING
15	1620	50	LB	SEED FOR TEMPORARY SEEDING
16	1620	0.2	TON	FERTILIZER FOR TEMPORARY SEEDING
17	SP	120	LF	WATTLE
18	SP	5	LB	POLYACRYLAMIDE (PAM)
19	1660	1	ACRE	SEEDING AND MULCHING
20	1661	50	LB	SEED FOR REPAIR SEEDING
21	1661	0.2	TON	FERTILIZER FOR REPAIR SEEDING
22	SP	3	EA	RESPONSE FOR EROSION CONTROL
23	1205	29	EA	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)
24	1205	7,847	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4",120 MILS)
25	1205	6,630	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4",90 MILS)
26	1205	275	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12",90 MILS)
27	1205	70	LF	THERMOPLASTIC PAVEMENT MARKING LINES (24",120 MILS)
28	1205	8	EA	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)

REVISIONS

8/17/99

10-NOV-2014 12:55
C:\WINDOWS\TEMP\ADTR\HILLFARM\HILLFARM_ddc2_pth3.dgn
$$$$USERNAME$$$$