DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

CROSS-SECTION SUMMARY

IN CUBIC YARDS

LOCATION (-L-)	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBANKMENT
12+50.00	0		0
13+00.00	14		0
13+50.00	14		0
14+00.00	16		1
14+50.00	14		4
15+00.00	20		9
15+50.00	26		8
16+00.00	31		5
16+50.00	33		6
17+00.00	25		10
17+50.00	18		17
18+00.00	37		10
18+50.00	43		1
19+00.00	26		1
20+50.00	0		0
21+00.00	17		4
21+50.00	28		4
22+00.00	33		5
22+50.00	31		9
23+00.00	26		7
23+50.00	22		5
24+00.00	17		6
24+50.00	14		7
25+00.00	12		7
25+50.00	21		11
26+00.00	32		17
26+50.00	35		19
27+00.00	39		20
27+50.00	45		17
28+00.00	48		11
28+50.00	48		11
29+00.00	43		17

LOCATION (-L-)	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBANKMENT
29+50.00	34		23
30+00.00	29		25
30+50.00	31		24
31+00.00	35		24
31+50.00	33		26
32+00.00	51		18
32+50.00	73		12
33+00.00	73		13
33+50.00	70		12
34+00.00	62		12
34+50.00	57		11
35+00.00	57		8
35+50.00	52		9
36+00.00	45		11
36+50.00	37		11
37+00.00	27		13
37+50.00	25		17
38+00.00	33		9
38+50.00	21		0
39+00.00	2		4
39+50.00	3		7
40+00.00	3		6
40+50.00	4		4
41+00.00	4		2
41+50.00	4		3
42+00.00	8		10
42+50.00	10		20
43+00.00	7		18
43+50.00	6		9
44+00.00	3		8

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT.

NOTE:

APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, BORROW EXCAVATION, FINE GRADING, CLEARING AND GRUBBING AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR "GRADING."

Rev. 3/6/01
07-NOV-2014 10:18
C:\PROJECTS\ENDIR\HILLFARM\HILLFARM_DDC2_x1a.dgn
$$$$USERNAME$$$$