



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

JAMES H. TROGDON, III  
SECRETARY

November 20, 2017

CONTRACT: DB00356  
WBS ELEMENT: 17BP.2.R.74  
COUNTY: Lenoir  
ROUTE: SR 1905  
DESCRIPTION: Replacement of Bridge 23 in Lenoir County

**ADDENDUM 1**

TO: PROSPECTIVE BIDDERS

Please note the following revision to the proposal.

- Revision of the Line Item 3 from Item Number 0029000000-N Reinforced Bridge Approach Fill, Station to Item Number 0030000000-N Bridge Approach Fill – Sub Regional Tier.
- A revised electronic file has been uploaded to bid express and the bid letting website named “DB00356.001”.

**Please make sure to sign the addendum page in the proposal to acknowledge this addendum.**

Sincerely,

DocuSigned by:

A handwritten signature in black ink that reads "Mary Voelker Moore".

714G14DCCEBC4CG  
Mary Voelker Moore, P.E.  
Division Contract Engineer

cc: Mr. Aaron Bullard, PE  
Mr. Hon Yeung, PE  
Mr. William Kincannon, PE  
Mr. B.E. Eatmon, PE  
Ms. Claudia Wainwright

Mailing Address:  
NC DEPARTMENT OF TRANSPORTATION  
DIVISION 2  
PROJECT DEVELOPMENT GROUP  
PO BOX 1587  
GREENVILLE, NC 27835-1587

Telephone: (252) 439-2800  
Customer Service: 1-877-368-4968

Website: www.ncdot.gov

Location:  
1037 W.H. SMITH BLVD  
GREENVILLE, NC 27835

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (-L-STA.14+22)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	5 TON		
0007	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	15 SY		
0008	0335200000-E	305	15" DRAINAGE PIPE	12 LF		
0009	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	28 LF		
0010	1330000000-E	607	INCIDENTAL MILLING	260 SY		
0011	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	300 TON		
0012	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	320 TON		
0013	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	35 TON		
0014	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0015	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0016	2556000000-E	846	SHOULDER BERM GUTTER	40 LF		
0017	3030000000-E	862	STEEL BM GUARDRAIL	237.5 LF		
0018	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0020	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0021	3649000000-E	876	RIP RAP, CLASS B	2 TON		
0022	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	7 SY		
0023	6000000000-E	1605	TEMPORARY SILT FENCE	1,255 LF		
0024	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	20 TON		
0025	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	20 TON		
0026	6012000000-E	1610	SEDIMENT CONTROL STONE	20 TON		
0027	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0028	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0029	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0030	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0031	6029000000-E	SP	SAFETY FENCE	400 LF		
0032	6036000000-E	1631	MATTING FOR EROSION CONTROL	210 SY		
0033	6037000000-E	SP	COIR FIBER MAT	100 SY		
0034	6042000000-E	1632	1/4" HARDWARE CLOTH	25 LF		
0035	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	150 SY		
0036	6071012000-E	SP	COIR FIBER WATTLE	60 LF		
0037	6071013000-E	SP	WATTLE BARRIER	150 LF		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6071014000-E	SP	COIR FIBER WATTLE BARRIER	40 LF		
0039	6071020000-E	SP	POLYACRYLAMIDE (PAM)	10 LB		
0040	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0041	6087000000-E	1660	MOWING	0.5 ACR		
0042	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0043	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0044	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0045	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25 TON		
0046	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0047	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
0048	6123000000-E	1670	REFORESTATION	0.1 ACR		
0049	6132000000-N	SP	GENERIC EROSION CONTROL ITEM CONCRETE WASHOUT STRUCTURE	2 EA		
0050	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** 14+26.91	Lump Sum	L.S.	
0051	8112730000-N	450	PDA TESTING	1 EA		
0052	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** 14+26.91	Lump Sum	L.S.	
0053	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	39.1 CY		
0054	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** 14+26.91	Lump Sum	L.S.	
0055	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,366 LB		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	8328200000-E	SP	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES HP12X53	14 EA		
0057	8328400000-E	SP	PILE DRIVING EQUIPMENT SETUP FOR *** GALVANIZED STEEL PILES HP14X73	8 EA		
0058	8364000000-E	450	HP12X53 STEEL PILES	910 LF		
0059	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	600 LF		
0060	8393000000-N	450	PILE REDRIVES	12 EA		
0061	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	200.5 LF		
0062	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	330 TON		
0063	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	370 SY		
0064	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0065	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,100 LF		
0066	8860000000-N	SP	GENERIC STRUCTURE ITEM ASBESTOS ASSESMENT	Lump Sum	L.S.	

0921/Nov20/Q14126.7/D340957989000/E66

Total Amount Of Bid For Entire Project :