

SUMMARY OF QUANTITIES

COUNTY	WBS ELEMENT.	MAP NO.	ROUTE	TERMINI	DESCRIPTION	PROJECT LENGTH	WIDTH	TYPICAL SECTION
PENDER	3CR.20711.154	1	SR 1102	NC 210 to Bladen County Line	RESURFACE WITH 1" SF 9.5 A	2.50	18	1
PENDER	3CR.20711.154	2	SR 1104	NC 210 TO SR 1103	RESURFACE WITH 1.5" S 9.5 B	0.80	18	2
PENDER	3CR.20711.154	3	SR 1128	NC 53 TO US 421	WIDEN 2' EACH SIDE WITH 4" B 25.0 B AND RESURFACE 22' WITH 1 1/2" S 9.5 B	4.05	18-22	3
PENDER	3CR.20711.154	4	SR 1201	BLADEN COUNTY LINE TO SR 1206	1" OVERLAYS AS MARKED WITH SF 9.5 A	4.60	20	4
PENDER	3CR.20711.154	5	SR 1212	SR 1211 TO US 421	1" OVERLAYS AS MARKED WITH SF 9.5 A	1.32	18	4
PENDER	3CR.20711.154	6	SR 1215	SR 1211 TO SR 1217	1" OVERLAYS AS MARKED WITH SF 9.5 A	0.80	18	4
PENDER	3CR.20711.154	7	SR 1216	SR 1128 TO US 421	RESURFACE WITH 1" SF 9.5 A	1.40	18	1
PENDER	3CR.20711.154	8	SR 1217	SR 1209 TO US 421	1" OVERLAYS AS MARKED WITH SF 9.5 A	1.55	18	4
PENDER	3CR.20711.154	9	SR 1336	SR 1332 TO SR 1120	1" OVERLAYS AS MARKED WITH SF 9.5 A	4.53	18	4
PENDER	3CR.20711.154	10	SR 1569	US 17 TO CASTLE BAY(PRIVATE SUBDIVISION)	MILL PATCH WITH 1 1/2" S 9.5 B	2.00	20-22	5
PENDER	3C.071088	11	SR 1401	SR 1402 TO SR1400	CONDITION EXISTING BASE AND PAVE WITH 1 1/2" S 9.5 B	1.75	20	6
PENDER	36249.3294	12	DRUM AVENUE (CITY STREET)	OCEAN BLVD. TO CAROLINA BLVD.	MAT WITH NO. 6 STONE AND RESURFACE WITH 1 1/2" SF 9.5 A	0.11	20	7
PENDER	36249.3294	13	BAEWICK AVENUE (CITY STREET)	ANDERSON BLVD.(NC 50) TO BRIDGES STREET	RESURFACE WITH 1 1/2" SF 9.5 A	0.07	20	8
PENDER	36249.3294	14	CANADY AVENUE (CITY STREET)	ANDERSON BLVD.(NC 50) TO DEAD END	RESURFACE WITH 1 1/2" SF 9.5 A	0.14	16	8
TOTALS						25.62		

MAP NO.	MOBILIZATION (%)	CONDITION EXISTING BASE (MSY)	INCIDENTAL STONE BASE (TONS)	MILLING 1 1/2" DEPTH (SQ YDS)	ACBC TYPE B25.0 B (TONS)	ACSC TYPE S 9.5 B (TONS)	ACSC TYPE SF 9.5A (RESURFACING & OVERLAYS) (TONS)	ASPHALT BINDER FOR PLANT MIX (TONS)
1	0.0976						1,525	102.2
2	0.0312		20			745		45.0
3	0.1581		150	2,960	2,850	4,700		407.0
4	0.1795		50				650	44.0
5	0.0515						240	18.0
6	0.0312						60	4.0
7	0.0546						855	57.0
8	0.0605						600	40.0
9	0.1768						700	47.0
10	0.0781							
11	0.0683	21.503	50			1,800		108.0
12	0.0043		25				140	9.5
13	0.0027		10				70	4.7
14	0.0055		10				115	7.7
TOTALS	1.0000	21.503	315	2,960	2,850	7,245	4,955	894

MAP NO.	MILL PATCH S 9.5 B (TONS)	WORK ZONE ADVANCE / GENERAL WARNING SIGNING (SF)	TEMPORARY TRAFFIC CONTROL (LS)	PERMANENT RAISED PAVEMENT MARKERS (EACH)	SILT FENCE (LF)			
1		250	0.1143					
2		90	0.0503	53				
3		440	0.4552	267	500			
4		490	0.0492					
5		130	0.0201					
6		90	0.0045					
7		140	0.0638					
8		160	0.0447					
9		490	0.0526					
10	180	260	0.0000					
11		186	0.1208	116				
12		48	0.0106					
13		48	0.0053					
14		48	0.0086					
TOTALS	180	2,870	1.0000	436	500			