

SUMMARY OF QUANTITIES

COUNTY	WBS ELEMENT.	MAP NO.	ROUTE	TERMINI	DESCRIPTION	PROJECT LENGTH	WIDTH	TYPICAL SECTION
PENDER	3CR.20711.142	1	SR 1114	SR 1113 to NC 210	FROM SR 1113 TO NC 210 WIDEN 2' EACH SIDE & CAP WIDENING PLUS 1" OVERLAYS TO BE MARKED	2.73	18	1
PENDER	3CR.20711.142	2	SR 1565	SR 1563 TO SR 1675	WIDEN FOR 2' PAVED SHOULDERS, MAT WITH NO.6 STONE AND RESURFACE WITH 1.5" S 9.5 B	1.20	20-24	2
PENDER	3CR.20711.142	3	SR 1582	US 17 TO SR 1603	WIDEN FOR 2' PAVED SHOULDERS, MAT WITH NO.78M STONE AND RESURFACE WITH 1.5" S 9.5 B	1.50	18	2
TOTALS						5.43		
MAP NO.	MOBILIZATION (%)	INCIDENTAL STONE BASE (TONS)	ACBC TYPE B25.0 B (TONS)	ACSC TYPE S 9.5 B (TONS)	ACSC TYPE SF 9.5A (OVERLAYS) (TONS)	ASPHALT BINDER FOR PLANT MIX (TONS)	PERMANENT RAISED PAVEMENT MARKERS (EA)	TEMPORARY SILT FENCE (LF)
1	0.5028	50	1575	580.00	171	116		200
2	0.2210	150	370	1,690.00		118	80	200
3	0.2762	50	845	1,800.00		145	99	200
TOTALS	1.0000	250	2,790	4,070	171	379.0	179	600
MAP NO.	COIR FIBER WATTLES (LF)	PAM (LB)						
1	120	1						
2	120	1						
3	120	1						
TOTALS	360	3.00						