GENERAL NOTES:

2012 SPECIFICATIONS
EFFECTIVE: 01-17-12
REVISED: 07/30/12

SIDE ROADS:

THE CONTRACTOR WILL BE REQUIRED TO DO ALL NECESSARY WORK TO PROVIDE SUITABLE CONNECTIONS WITH ALL ROADS, STREETS, AND DRIVES ENTERING THIS PROJECT. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PARTICULAR ITEMS INVOLVED.

2012 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated January, 2012 are applicable to this project and by reference hereby are considered a part of these plans:

DIVISION 6 - ASPHALT BASES AND PAVEMENTS
654.01 Pavement Repairs

DIVISION 11 - TRAFFIC CONTROL
1101.01 Work Zone Advance Warning Signs for Facilities 55 MPH
1101.02 Temporary Lane Closures
1101.04 Temporary Shoulder closures
1101.11 Traffic Control Design Tables
1110.01 Stationary Work Zone Signs
1110.02 Portable Work Zone Signs
1130.01 Drum
1145.01 Barricades
1165.01 Work Vehicle Lighting Systems and TMA Delineation
1180.01 Skinny Drums

UTILITIES:

UTILITY OWNERS ON THIS PROJECT ARE-
POWER-JONES ONSLOW-BENNIE MELTON-910.577.6375
PHONE-CENTURY LINK-ANTHONY MELILI-910.577.9359
CABLE TV-TIME WARNER-JOHN ROBERT-910.619.0192
WATER & SEWAGE-ONWASO-KAREN FERGASON-910.937.7546

INDEX OF SHEETS

SHEET NUMBER	SHEET
1	TITLE SHEET, ALIGNMENT AND SHEET LAYOUT
1-A	INDEX OF SHEETS, GENERAL NOTES AND LIST OF STANDARD DRAWINGS
1-B	CONVENTIONAL SYMBOLS
2 THRU 2-B	PROJECT DETAILS

8/17/99
14-JAN-2016 17:21
C:\HAYCODONE\ONSLOW\W-5106_41870.1.1_Sand Ridge Rd.Stripng\ROADWAY\Proj\PLAN SHEETS\W-5106_41870.3.FD1_SAND RIDGE RD STRIPING_PSH 1A.dgn
$$$$USERNAME$$$$