

PROJECT	FEDERAL PROJECT NUMBER	FED ITEM	CONT SEC	WORK TYPE	LOCATION
45349.1.22	BRZ-1306(24)				Duplin County - SR 1306(Beautancus Road ZONE: ROUTE: SR 1306

BREAKDOWN ID 001

WORK ITEM DESCRIPTION	CATG	SEQUENCE	ITEM	QUANTITY	UNIT
MOBILIZATION	0001	0001	0000100000-N	1.00	LS
CONSTRUCTION SURVEYING	0001	0002	0000400000-N	1.00	LS
REINFORCED BRIDGE APPROACH FILL, STATION ***** -L- STA 12+50	0001	0003	0029000000-N	1.00	LS
GRADING	0001	0004	0043000000-N	1.00	LS
FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES 31	0001	0005	0318000000-E	10.00	TON
FOUNDATION CONDITIONING GEOTEXTILE	0001	0006	0320000000-E	20.00	SY
15" RC PIPE CULVERTS, CLASS IV	0001	0007	0448200000-E	36.00	LF
ASPHALT CONC BASE COURSE, TYPE B25.0B	0001	0008	1489000000-E	420.00	TON
ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	0001	0009	1525000000-E	290.00	TON
ASPHALT BINDER FOR PLANT MIX	0001	0010	1575000000-E	40.00	TON
MASONRY DRAINAGE STRUCTURES	0001	0011	2286000000-N	2.00	EA
FRAME WITH TWO GRATES, STD 840.29	0001	0012	2367000000-N	2.00	EA
SHOULDER BERM GUTTER	0001	0013	2556000000-E	44.00	LF
STEEL BM GUARDRAIL	0001	0014	3030000000-E	25.00	LF
ADDITIONAL GUARDRAIL POSTS	0001	0015	3150000000-N	5.00	EA
GUARDRAIL ANCHOR UNITS, TYPE III	0001	0016	3215000000-N	4.00	EA
GUARDRAIL ANCHOR UNITS, TYPE 350	0001	0017	3270000000-N	4.00	EA
RIP RAP, CLASS B	0001	0018	3649000000-E	1.00	TON
GEOTEXTILE FOR DRAINAGE	0001	0019	3656000000-E	5.00	SY
WORK ZONE SIGNS (STATIONARY)	0001	0020	4400000000-E	424.00	SF
WORK ZONE SIGNS (BARRICADE MOUNTED)	0001	0021	4410000000-E	63.00	SF
BARRICADES (TYPE III)	0001	0022	4445000000-E	64.00	LF
PAINT PAVEMENT MARKING LINES (4")	0001	0023	4810000000-E	5,040.00	LF
PERMANENT RAISED PAVEMENT MARKERS	0001	0024	4900000000-N	8.00	EA
10" WATER LINE	0001	0025	5326000000-E	104.00	LF
12" WATER LINE	0001	0026	5326200000-E	287.00	LF
10" VALVE	0001	0027	5552000000-E	2.00	EA
ABANDON 10" UTILITY PIPE	0001	0028	5802000000-E	384.00	LF
TRENCHLESS INSTALLATION OF 12"IN SOIL	0001	0029	5871700000-E	144.00	LF
TRENCHLESS INSTALLATION OF 12"NOT IN SOIL	0001	0030	5871710000-E	143.00	LF

PROJECT	FEDERAL PROJECT NUMBER	FED ITEM	CONT SEC	WORK TYPE	LOCATION
45349.1.22	BRZ-1306(24)				Duplin County - SR 1306(Beautancus Road ZONE: ROUTE:SR 1306

BREAKDOWN ID 001

WORK ITEM DESCRIPTION	CATG	SEQUENCE	ITEM	QUANTITY	UNIT
TEMPORARY SILT FENCE	0001	0031	6000000000-E	1,275.00	LF
STONE FOR EROSION CONTROL, CLASS B	0001	0032	6009000000-E	5.00	TON
SEDIMENT CONTROL STONE	0001	0033	6012000000-E	15.00	TON
TEMPORARY MULCHING	0001	0034	6015000000-E	0.50	ACR
SEED FOR TEMPORARY SEEDING	0001	0035	6018000000-E	50.00	LB
FERTILIZER FOR TEMPORARY SEED-ING	0001	0036	6021000000-E	0.25	TON
SAFETY FENCE	0001	0037	6029000000-E	300.00	LF
SILT EXCAVATION	0001	0038	6030000000-E	10.00	CY
MATTING FOR EROSION CONTROL	0001	0039	6036000000-E	70.00	SY
1/4" HARDWARE CLOTH	0001	0040	6042000000-E	50.00	LF
FLOATING TURBIDITY CURTAIN	0001	0041	6048000000-E	50.00	SY
COIR FIBER WATTLE	0001	0042	6071012000-E	60.00	LF
SEEDING & MULCHING	0001	0043	6084000000-E	0.50	ACR
SEED FOR REPAIR SEEDING	0001	0044	6090000000-E	50.00	LB
FERTILIZER FOR REPAIR SEEDING	0001	0045	6093000000-E	0.25	TON
SEED FOR SUPPLEMENTAL SEEDING	0001	0046	6096000000-E	50.00	LB
FERTILIZER TOPDRESSING	0001	0047	6108000000-E	0.50	TON
RESPONSE FOR EROSION CONTROL	0001	0048	6117000000-N	13.00	EA
REMOVAL OF EXISTING STRUCTURE AT STATION ***** -L- STA 12+50	0001	0049	8035000000-N	1.00	LS
PDA TESTING	0001	0050	8112730000-N	1.00	EA
UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** -L- STA 12+50	0001	0051	8121000000-N	1.00	LS
CLASS A CONCRETE (BRIDGE)	0001	0052	8182000000-E	36.10	CY
BRIDGE APPROACH SLABS, STATION***** -L- STA 12+50	0001	0053	8210000000-N	1.00	LS
REINFORCING STEEL (BRIDGE)	0001	0054	8217000000-E	5,913.00	LB
HP12X53 STEEL PILES	0001	0055	8364000000-E	500.00	LF
HP14X73 GALVANIZED STEEL PILES	0001	0056	8384200000-E	420.00	LF
STEEL PILE POINTS	0001	0057	8391000000-N	7.00	EA
PILE REDRIVES	0001	0058	8393000000-N	10.00	EA
VERTICAL CONCRETE BARRIER RAIL	0001	0059	8505000000-E	160.50	LF
RIP RAP CLASS II (2'-0" THICK)	0001	0060	8608000000-E	109.00	TON

PROJECT 45349.1.22	FEDERAL PROJECT NUMBER BRZ-1306(24)	FED ITEM	CONT SEC	WORK TYPE	LOCATION Duplin County - SR 1306(Beautancus Road ZONE: ROUTE:SR 1306
-----------------------	--	----------	----------	-----------	--

BREAKDOWN ID 001

WORK ITEM DESCRIPTION	CATG	SEQUENCE	ITEM	QUANTITY	UNIT
GEOTEXTILE FOR DRAINAGE	0001	0061	8622000000-E	121.00	SY
ELASTOMERIC BEARINGS	0001	0062	8657000000-N	1.00	LS
3'-0" X 1'-9" PRESTRESSED CONCCORED SLABS	0001	0063	8762000000-E	800.00	LF