

49303.3.24

TIP NO HS-2003W
FED AID NO 0017199

0.153 MILES

DIRECTIONAL LEFT TURN AT US 17 & RED BUG ROAD
US 17 FROM SR 1136 (RED BUG RD.) TO SR 1345 (ROYAL OAK RD.) NORTH OF SHALLOTTE

BARNHILL CONTRACTING CO
ROCKY MOUNT, NC

ROADWAY ITEMS

0001	0000100000-N	800	MOBILIZATION	Lump Sum			120,250.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum			22,085.00
0003	0043000000-N	226	GRADING	Lump Sum			264,000.00
0004	0318000000-E	300	FND CONDIT MATL MINOR STRS	60	TON	77.00	4,620.00
0005	0320000000-E	300	FND CONDIT GEOTEXTILE	170	SY	3.25	552.50
0006	0366000000-E	310	15" RC PIPE CULV III	488	LF	95.00	46,360.00
0007	1111000000-E	SP	CLASS IV AGGREGATE STABILIZATION	10	TON	255.00	2,550.00
0008	1297000000-E	607	MILL ASP PVMT ***** DTH (3)	260	SY	40.00	10,400.00
0009	1491000000-E	610	ASP CONC BASE CRS B25.0C	440	TON	135.00	59,400.00
0010	1503000000-E	610	ASP CONC INTR CRS I19.0C	430	TON	130.00	55,900.00
0011	1519000000-E	610	ASP CONC SURF CRS S9.5B	310	TON	210.00	65,100.00
0012	1575000000-E	620	ASP FOR PLANT MIX	65	TON	725.00	47,125.00
0013	2286000000-N	840	MASNRY DRAINAGE STRUCT	5	EA	4,775.00	23,875.00
0014	2308000000-E	840	MASNRY DRAINAGE STRUCT	0.4	LF	7,050.00	2,820.00
0015	2364000000-N	840	FRAME W/2GRTS 840.16 STD	2	EA	1,570.00	3,140.00
0016	2365000000-N	840	FRAME W/2GRTS 840.22 STD	2	EA	1,560.00	3,120.00
0017	2396000000-N	840	FRAME W/COVER STD 840.54	1	EA	1,690.00	1,690.00
0018	2451000000-N	852	CONC TRANS SECT FOR DROP INLET	2	EA	2,315.00	4,630.00
0019	2647000000-E	852	5" MONO CONC ISLANDS (SURF MTD)	340	SY	94.00	31,960.00
0020	2815000000-N	858	ADJ DROP INLETS	1	EA	7,750.00	7,750.00
0021	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	190	SY	3.25	617.50
0022	4072000000-E	903	SUPPORT, 3-LB STL U-CHAN	650	LF	6.05	3,932.50
0023	4102000000-N	904	SIGN ERECTION, TYPE E	35	EA	295.50	10,342.50
0024	4108000000-N	904	SIGN ERECTION, TYPE F	4	EA	410.00	1,640.00
0025	4116100000-N	904	SIGN ERECT, RELOC ** GRD MTD (TYPE D)	1	EA	410.00	410.00
0026	4155000000-N	907	DISPOSE SIGN SYST U-CHAN	31	EA	10.00	310.00
0027	4405000000-E	1110	WORK ZONE SIGNS (PORT)	432	SF	15.00	6,480.00
0028	4410000000-E	1110	WORK ZONE SIGNS (BARR)	20	SF	10.50	210.00
0029	4415000000-N	1115	FLASHING ARROW BOARD	6	EA	2,540.00	15,240.00
0030	4420000000-N	1120	PORTABLE CHANGE MSG SIGN	2	EA	8,910.00	17,820.00
0031	4424000000-N	SP	WZ PRESENCE LIGHTING	22	EA	2,160.00	47,520.00
0032	4430000000-N	1130	DRUMS	200	EA	60.00	12,000.00
0033	4434000000-N	SP	SEQ FLASH WARN LIGHTS	26	EA	222.00	5,772.00
0034	4445000000-E	1145	BARRICADES (TYPE III)	360	LF	21.50	7,740.00
0035	4480000000-N	1165	TMA	2	EA	18,145.00	36,290.00
0036	4510000000-N	1190	LAW ENFORCEMENT	8	HR	70.00	560.00
0037	4685000000-E	1205	THERMO PVT MKG LINES 4"90	5,428	LF	2.00	10,856.00
0038	4695000000-E	1205	THERMO PVT MKG LINES 8"90 MILS	1,540	LF	3.00	4,620.00
0039	4700000000-E	1205	12"WIDE THERMO 90 MILS	667	LF	3.50	2,334.50
0040	4709000000-E	1205	24"WIDE THERMO 90 MILS (24" THERMO)	130	LF	15.00	1,950.00

49303.3.24

TIP NO HS-2003W
FED AID NO 0017199

0.153 MILES

DIRECTIONAL LEFT TURN AT US 17 & RED BUG ROAD
US 17 FROM SR 1136 (RED BUG RD.) TO SR 1345 (ROYAL OAK RD.) NORTH OF SHALLOTTE

BARNHILL CONTRACTING CO
ROCKY MOUNT, NC

0041	4725000000-E	1205	THERMO PVT SYMBOL 90MILS	7	EA	150.00	1,050.00
0042	4810000000-E	1205	PAINT PVMT MARKINGS 4"	1,854	LF	2.00	3,708.00
0043	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM (LF) LONGITUDINAL CHANNELIZING CURB SYSTEM	275	LF	89.00	24,475.00
0044	4900000000-N	1251	PERM RAISED PVMT MARKERS	22	EA	10.00	220.00
0045	4905100000-N	SP	NON-CAST IRON SNOWPLB PVMT MRKER (NON CAST IRON)	118	EA	75.00	8,850.00
0046	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum			64,345.00
0047	6000000000-E	1605	TEMPORARY SILT FENCE	100	LF	11.00	1,100.00
0048	6006000000-E	1610	EROS CONTRL STONE CL A	165	TON	229.00	37,785.00
0049	6009000000-E	1610	EROS CONTRL STONE CL B	10	TON	240.00	2,400.00
0050	6012000000-E	1610	SEDIMENT CONTROL STONE	125	TON	170.00	21,250.00
0051	6015000000-E	1615	TEMPORARY MULCHING	2.5	ACR	1,450.00	3,625.00
0052	6018000000-E	1620	SEED FOR TEMP SEEDING	200	LB	2.10	420.00
0053	6021000000-E	1620	FERT FOR TEMP SEEDING	1	TON	1,775.00	1,775.00
0054	6029000000-E	SP	SAFETY FENCE	200	LF	10.00	2,000.00
0055	6030000000-E	1630	SILT EXCAVATION	110	CY	95.00	10,450.00
0056	6036000000-E	1631	MATTING FOR EROS CONTROL	1,700	SY	3.00	5,100.00
0057	6042000000-E	1632	1/4" HARDWARE CLOTH	105	LF	4.50	472.50
0058	6071012000-E	SP	COIR FIBER WATTLE	170	LF	16.00	2,720.00
0059	6071020000-E	SP	POLYACRYLAMIDE (PAM)	25	LB	20.00	500.00
0060	6084000000-E	1660	SEEDING AND MULCHING	3	ACR	4,000.00	12,000.00
0061	6087000000-E	1660	MOWING	1.5	ACR	750.00	1,125.00
0062	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	22.50	1,125.00
0063	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	1,650.00	412.50
0064	6096000000-E	1662	SEED FOR SUPP SEEDING	75	LB	16.25	1,218.75
0065	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75	TON	1,775.00	3,106.25
0066	6114500000-N	1667	SPECIALIZED HAND MOWING	5	MHR	90.00	450.00
0067	6114800000-N	SP	MANUAL LITTER REMOVAL	2	MHR	211.00	422.00
0068	6114900000-E	SP	LITTER DISPOSAL	1	TON	350.00	350.00
0069	6117000000-N	SP	RESPONSE FOR EROS CONTROL	8	EA	95.00	760.00
0070	6117500000-N	SP	CONC WASHOUT STRUCTURE	2	EA	2,000.00	4,000.00
0071	7060000000-E	1705	SIGNAL CABLE	900	LF	4.00	3,600.00
0072	7120000000-E	1705	VEHICLE SIGNAL HD (12", 3 SECT)	5	EA	1,250.00	6,250.00
0073	7132000000-E	1705	VEHICLE SIGNAL HD (12", 4 SECT)	1	EA	1,400.00	1,400.00
0074	7288000000-E	1715	PAVED TRENCH (*****) (2, 2')	55	LF	35.00	1,925.00
0075	7300000000-E	1715	UNPAVED TRENCH (*****) (2, 2')	505	LF	14.00	7,070.00
0076	7301000000-E	1715	DIRECT DRILL (*****) (2, 2')	205	LF	35.00	7,175.00
0077	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	6	EA	675.00	4,050.00
0078	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	540	LF	9.25	4,995.00

49303.3.24

TIP NO HS-2003W
FED AID NO 0017199

0.153 MILES

DIRECTIONAL LEFT TURN AT US 17 & RED BUG ROAD
US 17 FROM SR 1136 (RED BUG RD.) TO SR 1345 (ROYAL OAK RD.) NORTH OF SHALLOTTE

BARNHILL CONTRACTING CO
ROCKY MOUNT, NC


0079	7456000000-E	1726	LEAD-IN CABLE(***** (14-2)	1,375	LF	2.00	2,750.00
0080	7575142000-N	1736	900MHZ SPECTRUM RADIO	2	EA	4,210.00	8,420.00
0081	7588000000-N	SP	SGNL MAST ARM WITH METAL POLE	1	EA	35,250.00	35,250.00
0082	7613000000-N	SP	SOIL TEST	1	EA	4,500.00	4,500.00
0083	7614100000-E	SP	DRILLED PIER FOUND	13	CY	2,000.00	26,000.00
0084	7631000000-N	SP	MAST ARM W/ MTL POLE DES	1	EA	200.00	200.00
0085	7636000000-N	1745	SIGN FOR SIGNALS	2	EA	350.00	700.00
0086	7642200000-N	1743	TYPE II PED W/ FOUNDATION	4	EA	4,200.00	16,800.00
0087	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1	EA	2,000.00	2,000.00
0088	7696000000-N	1751	CONTLRS WITH CBNT (***** (TYPE 2070E, BASE MOUNTED)	1	EA	22,000.00	22,000.00
0089	7708000000-N	1751	DETECTOR CARD (***** (TYPE 2070E)	3	EA	250.00	750.00
0090	7980000000-N	SP	GENERIC SIGNAL ITEM (EA) ETHERNET EDGE SWITCH	2	EA	3,500.00	7,000.00

CONTRACT TOTAL	TOTAL	1,344,022.50
ROADWAY ITEMS	SUB-TOTAL	1,344,022.50

BIDDERS IN ORDER

CONTRACT TOTAL

BARNHILL CONTRACTING CO	1	1,344,022.50
-------------------------	---	--------------

DocuSigned by:

 02B404268BC84C2...

03/16/2023