



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

BEVERLY EAVES PERDUE  
GOVERNOR

EUGENE A. CONTI, JR.  
SECRETARY

March 22, 2012

To: Prospective Bidders

From: Lloyd G. Royall, Jr  
Division Proposal Engineer

A handwritten signature in black ink, appearing to be "LR", enclosed in a hand-drawn oval.

WBS Element: 34608.2.4

Subject: Addendum #1 is for the correction to the Bid Form.

The Subject contract proposal contains the following addendum:

1. Replacement of the Sign Erection section.

**Change No. 1:**

**SIGN ERECTION: Will now read in the description, Direct payment for the Disposal of Signs, Type A (Ground Mounted & Overhead) will be made per erecting the signs on the project as stated on the Bid Form page.**

To have a properly submitted proposal, the contractor shall sign and date this addendum and attach it to the back of the existing contract. This addendum has been sent out by mail and posted on the Division 3 Web Page.

LGR/lgr

## SIGN ERECTION

Sign erection will be made in accordance with Section 904 of the Standard Specifications as modified herein.

The Department will furnish all new signs for this project in accordance with Section 901 of the Standard Specifications. The Contractor will be responsible for picking up Type A signs from the Department of Transportation facility in Castle Hayne, NC. Direct payment for items associated with "Department Furnished Signs" will not be covered under this contract and will be considered incidental to the sign erection.

Existing signs will be removed and disposed of in accordance with Section 907 of the Standard Specifications. **Direct payment for the Disposal of Signs, Type A (Ground Mounted & Overhead) will be made per erecting the signs on the project as stated on the Bid Form page.**

Existing lighting heads and conduit will be removed in accordance with Section 907 as modified herein. Conduit should be removed back to the elbow fitting (LB) and the fitting shall be plugged after removal of the conduit. Seal the ends of the disconnected conduit by methods approved by the Engineer. Rigid conduit removed under this contract shall be disposed of by the Contractor. Catwalk should be removed at all locations unless it is equipped with a camera or otherwise approved by the engineer. **Contractor is responsible for disposal of catwalk, signage & lighting.**

*Received by* \_\_\_\_\_ *Date* \_\_\_\_\_