

<u>COUNTY</u>	<u>BRIDGE</u>	<u>ROUTE</u>	<u>ROADWAY</u>	<u>SKEW</u>	<u># JOINTS</u>
---------------	---------------	--------------	----------------	-------------	-----------------

Duplin	430	I-40	39.75	73	4
Duplin	435	I-40	48.2	97	4
Duplin	436	I-40	47.9	90	4
Duplin	437	I-40	48.0	59	5
Duplin	438	I-40	48.0	59	5
Duplin	37	SR 1154	29.9	90	2
Duplin	69	SR1915	24	90	3
Duplin	101	SR 1004	30	120	2
Duplin	408	SR 1105	27.0	90	3
Duplin	457	NC 24	37.6	90	2
Duplin	458	NC 24	37.7	90	2
Sampson	396	SR 1845	26.4	86	5
Sampson	397	NC 55	56.0	76	5
Sampson	398	US 13	40.0	86	5
Sampson	169	SR 1620	24.0	90	2
Sampson	273	SR 1800	24.0	90	3
Sampson	348	SR 1703	24.0	90	1
Sampson	135	SR 1002	30.2	90	1
Sampson	167	SR1446	24.0	90	3
Sampson	19	NC 242	40	120	2
Sampson	85	SR 1214	24.0	90	2

<b>RECOMMEDED REPAIR</b>		<b><u>Total Length</u></b>
Ecrete/Foam seals		159.00
Ecrete/Foam seals		193.00
Ecrete/Foam seals		191.67
Ecrete/Foam seals		240.00
Ecrete/Foam seals		240.00
Ecrete/Foam Seals		59.80
Plug Joints		72.00
Ecrete/Foam Seals		60.00
Plug Joints		81.00
Ecrete/Foam seals		75.20
Ecrete/Foam seals		75.40
Ecrete/Foam Seals		132.08
Ecrete/Foam Seals		280.00
Ecrete/Foam Seals		200.00
Silicon		47.92
Silicon		72.00
Silicon		24.00
Plug Joints		30.17
Plug Joints		71.88
Ecrete/Foam Seals		80.00
ecrete/silicon		47.92

Total:	2433.03
--------	---------