

SUMMARY OF QUANTITIES

COUNTY	WBS ELEMENT.	MAP NO.	ROUTE	TERMINI	DESCRIPTION	PROJECT LENGTH	WIDTH	TYPICAL SECTION
Onslow	3CR.20671.146	1	SR 1203	NC 53 to SR 1204	Full Depth Patch, Leveling Overlays	3.18	18	1,2 & 3
Onslow	3CR.20671.146	2	SR 1203	SR 1204 to SR 1207	Full Depth Patch, Leveling & Overlays	1.69	18	1,2 & 3
Onslow	3CR.20671.146	3	SR 1205	SR 1206 to SR 1209	Leveling & Overlays	2.41	18	2 & 3
Onslow	3CR.20671.146	4	SR 1231	SR 1238 TO SR 1229	Mill Patch S 9.5 B	1.07	18	5
Onslow	3CR.20671.146	5	SR 1239	SR 1238 to NC 24	Mill Patch S 9.5 B	1.13	18	5
Onslow	3CR.20671.146	6	SR 1331	US 17 to EOS	Mill Patch I 19.0 B	8.4	20	6
Onslow	3CR.20671.146	7	SR 1428	SR 1425 To SR 2610	Mill Patch I 19.0 B	1.5	20	6
Onslow	3CR.20671.146	8	SR 1817	NC 24 to SR 1819	Mill Patch & Resurface 1 1/2" SF 9.5 A	0.16	20	7 & 8
Onslow	3CR.20671.146	9	SR 1817	SR 1819 to SR 1823	Mill Patch & Resurface 1 1/2" SF 9.5 A	0.21	18	7 & 8
Onslow	3CR.20671.146	10	SR 1818	SR 1821 to SR 1817	Mill Patch & Resurface 1 1/2" SF 9.5 A	0.14	20	7 & 8
Onslow	3CR.20671.146	11	SR 1819	SR 1817 to SR 1821	Mill Patch & Resurface 1 1/2" SF 9.5 A	0.11	20	7 & 8
Onslow	3CR.20671.146	12	SR 1820	SR 1823 to SR 1817	Mill Patch & Resurface 1 1/2" SF 9.5 A	0.11	20	7 & 8
Onslow	3CR.20671.146	13	SR 1821	SR 1820 to NC 24	Mill Patch & Resurface 1 1/2" SF 9.5 A	0.18	20	7 & 8
Onslow	3CR.20671.146	14	SR 1822	SR 1821 to Dead End	Mill Patch & Resurface 1 1/2" SF 9.5 A	0.11	20	7 & 8
Onslow	3CR.20671.146	15	SR 1823	SR 1817 to SR 1822	Mill Patch & Resurface 1 1/2" SF 9.5 A	0.17	20	7 & 8
Onslow	3CR.20671.146	16	SR 1824	SR 1823 to Dead End	Mill Patch & Resurface 1 1/2" SF 9.5 A	0.06	20	7 & 8
Onslow	3CR.20671.146	17	SR 1274	SR 1243 to Cul - De -Sac	Mill 2" Place 2.5" S19.0 B & Resurface 0.75" S4.75 A	0.21	20	9 & 10
Onslow	3CR.20671.146	18	SR 1107	NC 53 to SR 11.5	Mill Patch I 19.0 B	3.76	20	6
TOTALS						24.6		

MAP NO.	MOBILIZATION (LS)	INCIDENTAL STONE BASE (TONS)	MILLING ASPHALT PAVEMENT 2" DEPTH (SY)	ACIC TYPE 19.0 B (TONS)	ACSC TYPE SF 9.5 A (LEVELING COURSE) (TONS)	ACSC TYPE S4.75 A (TONS)	ASPHALT BINDER FOR PLANT MIX (TONS)	
1	0.129	50			45	14	2	
2	0.069	10			5	1	0.5	
3	0.098	50			400	240	42	
4	0.043							
5	0.046							
6	0.341							
7	0.061							
8	0.007	15			130		9	
9	0.009	15			190		13	
10	0.006	15			140		10	
11	0.004	15			115		7	
12	0.004	15			105		7	
13	0.007	15			180		12	
14	0.004	15			140		9	
15	0.007	15			185		13	
16	0.002	15			65		4	
17	0.009		2607	300		100	26	
18	0.154							
TOTALS	1.000	245	2607	300	1,700	255	100	155

MAP NO.	PATCHING EXISTING PAVEMENT (MILL) (TONS) S 9.5B	PATCHING EXISTING PAVEMENT (MILL) (TONS) 19.0 B	PATCHING EXISTING PAVEMENT (FULL DEPTH) (TONS)
1			66
2			9
3			
4	185		
5	140		
6		165	
7		205	
8	25		
9	55		
10	50		
11	50		
12	10		
13	75		
14	25		
15	25		
16	5		
17			
18		300	
TOTALS	645	670	75