



May 26, 2021

To: Prospective Bidders

From: Al Edgerton
Project Manager, SEPI, Inc.

TIP Designation: U-5534S (FA # STPDA-0332(062))

WBS Element:44096.3.20

Subject: Addendum Number 1

Installation of Approximately 1,100 Linear Feet of Sidewalk Along the East Side of Coral Drive, Between Causeway Drive and 4th Street.

The Subject contract proposal contains the following addendum:

1. On page G-1, under "Contract Time And Liquidated Damages", replace "Five Hundred Dollars (\$500.00)" with Six Hundred Dollars (\$600.00).
2. On page G-1, under "INTERMEDIATE CONTRACT TIME NUMBER [ICT number] AND LIQUIDATED DAMAGES" and "DAY AND TIME RESTRICTIONS", replace "Monday through Friday from 6:00 AM to 8:00 AM" and Monday through Friday from 2:00 PM to 3:00 PM with the following.
 - For the entirety of the contract, no work between the hours of 6:00 PM and 8:00 AM.
 - For the entirety of the contract, no work on Sunday's.
 - Between August 23, 2021 and September 10, 2021, or project completion date, no lane closures Monday through Friday between the hours of 2:00 PM to 3:00 PM.
3. Include the following special provision for:
PERMANENT VEGETATION ESTABLISHMENT:
Establish a permanent stand of the vegetation mixture shown in the contract. During the period between initial vegetation planting and final project acceptance, perform all work necessary to establish permanent vegetation on all erodible areas within the project limits, as well as, in borrow and waste pits. This work shall include erosion control device maintenance and installation, repair seeding and mulching, supplemental seeding and mulching, specialize hand



mowing, and fertilizer topdressing, as directed. All work shall be performed in accordance with the applicable section of the *2018 Standard Specifications*. All work required for initial vegetation planting shall be performed as a part of the work necessary for the completion and acceptance of the Intermediate Contract Time (ICT). Between the time of ICT and Final Project acceptance, or otherwise referred to as the vegetation establishment period, the Town of Wrightsville Beach, or their representative, will be responsible for preparing the National Pollutant Discharge Elimination System (NPDES) inspection records.

Once the Engineer has determined that the permanent vegetation establishment requirement has been achieved at an 80% vegetation density (the amount of established vegetation per given area to stabilize the soil) and no erodible areas exist within the project limits, the Contractor will be notified to remove the remaining erosion control devices that are no longer needed. The Contractor will be responsible for and shall correct any areas disturbed by operations performed in permanent vegetation establishment and the removal of temporary erosion control measures, whether occurring prior to or after placing traffic on the project.

Payment for *Response for Erosion Control, Seeding and Mulching, Repair Seeding, Supplemental Seeding, Specialize Hand Mowing, Fertilizer Topdressing and Stone for Erosion Control* will be made at contract unit prices for the affected items. Work required that is not represented by contract line items will be paid in accordance with Articles 104-7 or 104-3 of the *2018 Standard Specifications*. No additional compensation will be made for maintenance and removal of temporary erosion control items.

4. The minutes and sign in sheet for the May 14, 2021 pre-bid meeting are attached and includes answers to questions asked through May 25, 2021.

Addendum must be signed and dated.

You MUST sign as your acknowledgement that you did in fact receive this addendum. Failure to do so shall cause the bid to be considered irregular and shall be grounds for rejection of the bid.

Signature: _____

Date: _____