

44647.3.1

Jun 15, 2023

DC00439

TIP NO U-5914

0.373 MILES

FED AID NO STATE FUNDED

U-5914_NC 133 WIDENING AT SR 1554 (OLD RIVER RD.)

NC 133 FROM SR 1551 (BLACKWELL RD.) TO SR 1554 (OLD RIVER RD.)

CHATHAM CIVIL CONTRACTING
LLC
PITTSBORO, NC

ROADWAY ITEMS

0001	0000100000-N	800	MOBILIZATION	Lump Sum			240,559.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum			60,500.00
0003	0000930000-E	SP	GENERIC MISCELLANEOUS ITEM (LF) SAFETY RAIL	625	LF	112.35	70,218.75
0004	0000960000-E	SP	GENERIC MISCELLANEOUS ITEM (SY) GEOTEXTILE FOR EMBANKMENT STABILIZATION	1,100	SY	4.00	4,400.00
0005	0008000000-E	200	SUPP CLEARING & GRUBBING	1	ACR	0.01	0.01
0006	0043000000-N	226	GRADING	Lump Sum			1,027,492.00
0007	0057000000-E	226	UNDERCUT EXCAVATION	600	CY	32.00	19,200.00
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	1,300	CY	106.00	137,800.00
0009	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	1,400	SY	3.00	4,200.00
0010	0199000000-E	SP	TEMPORARY SHORING	810	SF	225.00	182,250.00
0011	0318000000-E	300	FND CONDIT MATL MINOR STRS	98	TON	82.00	8,036.00
0012	0320000000-E	300	FND CONDIT GEOTEXTILE	739	SY	3.00	2,217.00
0013	0354000000-E	310	**** RC PIPE CULV **** (15", V)	132	LF	148.50	19,602.00
0014	0354000000-E	310	**** RC PIPE CULV **** (54", IV)	48	LF	1,428.00	68,544.00
0015	0354000000-E	310	**** RC PIPE CULV **** (66", IV)	100	LF	1,885.00	188,500.00
0016	0448000000-E	310	**** RCP CULV CLASS IV (15")	296	LF	144.00	42,624.00
0017	0995000000-E	340	PIPE REMOVAL	63	LF	34.50	2,173.50
0018	1099500000-E	505	SHALLOW UNDERCUT	100	CY	41.00	4,100.00
0019	1099700000-E	505	CLASS IV SUBGRD STABILIZATION	190	TON	54.25	10,307.50
0020	1121000000-E	520	AGGREGATE BASE COURSE	90	TON	59.00	5,310.00
0021	1275000000-E	600	PRIME COAT	650	GAL	12.85	8,352.50
0022	1330000000-E	607	INCIDENTAL MILLING	670	SY	19.50	13,065.00
0023	1491000000-E	610	ASP CONC BASE CRS B25.0C	1,390	TON	227.00	315,530.00
0024	1503000000-E	610	ASP CONC INTR CRS I19.0C	710	TON	280.00	198,800.00
0025	1519000000-E	610	ASP CONC SURF CRS S9.5B	1,650	TON	258.00	425,700.00
0026	1575000000-E	620	ASP FOR PLANT MIX	200	TON	1,096.50	219,300.00
0027	2044000000-E	815	6" PERF SUBDRN PIPE	500	LF	12.60	6,300.00
0028	2190000000-N	828	TEMP STL PLT COVER FOR MDS	1	EA	11,500.00	11,500.00
0029	2220000000-E	838	REINFORCED ENDWALLS	15.7	CY	3,496.50	54,895.05
0030	2286000000-N	840	MASNRY DRAINAGE STRUCT	9	EA	9,911.00	89,199.00
0031	2308000000-E	840	MASNRY DRAINAGE STRUCT	8	LF	0.01	0.08
0032	2374000000-N	840	FRAME-GRT-HD 840.03 ** (E)	1	EA	750.00	750.00
0033	2374000000-N	840	FRAME-GRT-HD 840.03 ** (F)	6	EA	784.00	4,704.00
0034	2374000000-N	840	FRAME-GRT-HD 840.03 ** (G)	1	EA	784.00	784.00

44647.3.1

TIP NO U-5914

0.373 MILES

FED AID NO STATE FUNDED

U-5914_NC 133 WIDENING AT SR 1554 (OLD RIVER RD.)

NC 133 FROM SR 1551 (BLACKWELL RD.) TO SR 1554 (OLD RIVER RD.)

CHATHAM CIVIL CONTRACTING
LLC
PITTSBORO, NC

0035	2396000000-N	840	FRAME W/COVER STD 840.54	1	EA	495.00	495.00
0036	2549000000-E	846	2'-6" CONC CURB & GUTTER	1,480	LF	41.00	60,680.00
0037	2591000000-E	848	4" CONCRETE SIDEWALK	100	SY	95.50	9,550.00
0038	2605000000-N	848	CONCRETE CURB RAMPS	1	EA	3,500.00	3,500.00
0039	3030000000-E	862	STL BEAM GUARDRAIL	425	LF	32.00	13,600.00
0040	3150000000-N	862	ADDIT GUARDRAIL POSTS	5	EA	11.75	58.75
0041	3287000000-N	SP	GR END TYPE TL-3	4	EA	3,531.00	14,124.00
0042	3360000000-E	863	REMOVE EXISTING GUARDRAIL	258	LF	1.00	258.00
0043	3628000000-E	876	RIP RAP, CLASS I	78	TON	93.00	7,254.00
0044	3649000000-E	876	RIP RAP, CLASS B	4	TON	91.00	364.00
0045	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,285	SY	3.00	3,855.00
0046	4025000000-E	901	CONTR FURN, TYPE ***SIGN (TYPE F)	29	SF	21.70	629.30
0047	4072000000-E	903	SUPPORT, 3-LB STL U-CHAN	120	LF	7.15	858.00
0048	4102000000-N	904	SIGN ERECTION, TYPE E	6	EA	400.75	2,404.50
0049	4116100000-N	904	SIGN ERECT, RELOC ** GRD MTD (TYPE D)	4	EA	452.80	1,811.20
0050	4116100000-N	904	SIGN ERECT, RELOC ** GRD MTD (TYPE E)	11	EA	400.75	4,408.25
0051	4192000000-N	907	DISPOSE SUPPORT, U-CHAN	14	EA	1.15	16.10
0052	4400000000-E	1110	WORK ZONE SIGNS (STAT)	218	SF	13.75	2,997.50
0053	4405000000-E	1110	WORK ZONE SIGNS (PORT)	192	SF	11.00	2,112.00
0054	4410000000-E	1110	WORK ZONE SIGNS (BARR)	65	SF	11.15	724.75
0055	4420000000-N	1120	PORTABLE CHANGE MSG SIGN	2	EA	14,885.00	29,770.00
0056	4424000000-N	SP	WZ PRESENCE LIGHTING	6	EA	3,724.00	22,344.00
0057	4430000000-N	1130	DRUMS	85	EA	53.00	4,505.00
0058	4435000000-N	1135	CONES	20	EA	24.00	480.00
0059	4445000000-E	1145	BARRICADES (TYPE III)	132	LF	27.00	3,564.00
0060	4455000000-N	1150	FLAGGER	30	DAY	1,924.00	57,720.00
0061	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4	EA	10,887.00	43,548.00
0062	4470000000-N	1160	REM & RES CRASH CUSHION	2	EA	973.00	1,946.00
0063	4485000000-E	1170	PORT CONC BARRIER	590	LF	101.00	59,590.00
0064	4500000000-E	1170	REM & RES PORT CONC BARRIER	510	LF	9.50	4,845.00
0065	4510000000-N	1190	LAW ENFORCEMENT	40	HR	107.00	4,280.00
0066	4516000000-N	1180	SKINNY DRUM	20	EA	38.75	775.00
0067	4650000000-N	1251	TEMP RAISED PVMT MRKS	53	EA	10.70	567.10
0068	4685000000-E	1205	THERMO PVT MKG LINES 4"90	4,978	LF	1.90	9,458.20
0069	4688000000-E	1205	THERMO PVT MKG LINES,6"90 MILS	5,125	LF	2.10	10,762.50
0070	4695000000-E	1205	THERMO PVT MKG LINES 8"90 MILS	416	LF	3.20	1,331.20
0071	4700000000-E	1205	12"WIDE THERMO 90 MILS	195	LF	4.30	838.50
0072	4709000000-E	1205	24"WIDE THERMO 90 MILS	468	LF	17.10	8,002.80
0073	4725000000-E	1205	THERMO PVT SYMBOL 90MILS	22	EA	208.65	4,590.30

44647.3.1

Jun 15, 2023

DC00439

TIP NO U-5914

0.373 MILES

FED AID NO STATE FUNDED

U-5914_NC 133 WIDENING AT SR 1554 (OLD RIVER RD.)

NC 133 FROM SR 1551 (BLACKWELL RD.) TO SR 1554 (OLD RIVER RD.)

CHATHAM CIVIL CONTRACTING
LLC
PITTSBORO, NC

0074	4810000000-E	1205	PAINT PVMT MARKINGS 4"	14,462	LF	1.10	15,908.20
0075	4820000000-E	1205	PAINT PVMT MARKINGS 8"	18	LF	2.15	38.70
0076	4835000000-E	1205	PAINT PVT MKG LINES 24"	53	LF	5.35	283.55
0077	4850000000-E	1205	LINE REMOVAL 4" WIDE	7,268	LF	1.10	7,994.80
0078	4900000000-N	1251	PERM RAISED PVMT MARKERS	72	EA	10.70	770.40
0079	4905100000-N	SP	NON-CAST IRON SNOWPLB PVMT MRKER	17	EA	267.50	4,547.50
0080	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum			25,000.00
0081	5325600000-E	1510	6" WATER LINE	445	LF	113.50	50,507.50
0082	5325800000-E	1510	8" WATER LINE	222	LF	147.00	32,634.00
0083	5329000000-E	1510	DI H2O PIPE FITTINGS	1,070	LB	20.00	21,400.00
0084	5536000000-E	1515	2" VALVE	1	EA	2,470.00	2,470.00
0085	5540000000-E	1515	6" VALVE	3	EA	3,284.00	9,852.00
0086	5546000000-E	1515	8" VALVE	3	EA	4,011.00	12,033.00
0087	5666000000-N	1515	FIRE HYDRANT	1	EA	7,468.00	7,468.00
0088	5672000000-N	1515	RELOCATE FIRE HYDRANT	1	EA	4,857.00	4,857.00
0089	5673000000-E	1515	FIRE HYDRANT LEG	24	LF	197.25	4,734.00
0090	5691300000-E	1520	8" SANITARY GRAVITY SEWER	20	LF	400.00	8,000.00
0091	5709000000-E	1520	*** FORCE MAIN SEWER (3")	449	LF	65.00	29,185.00
0092	5709100000-E	1520	2" FORCE MAIN SEWER	52	LF	136.75	7,111.00
0093	5769000000-E	1520	DI SEWER PIPE FITTINGS	92	LB	141.00	12,972.00
0094	5798000000-E	1530	ABANDON *** UTILITY PIPE (2")	430	LF	4.55	1,956.50
0095	5800000000-E	1530	ABANDON 6" UTILITY PIPE	465	LF	15.10	7,021.50
0096	5801000000-E	1530	ABANDON 8" UTILITY PIPE	215	LF	30.00	6,450.00
0097	5872600000-E	1550	DIRECT DRILL *** (3")	449	LF	34.25	15,378.25
0098	5872600000-E	1550	DIRECT DRILL *** (6")	385	LF	78.00	30,030.00
0099	6000000000-E	1605	TEMPORARY SILT FENCE	6,655	LF	4.25	28,283.75
0100	6006000000-E	1610	EROS CONTRL STONE CL A	150	TON	68.00	10,200.00
0101	6009000000-E	1610	EROS CONTRL STONE CL B	125	TON	83.00	10,375.00
0102	6012000000-E	1610	SEDIMENT CONTROL STONE	385	TON	65.00	25,025.00
0103	6015000000-E	1615	TEMPORARY MULCHING	5.5	ACR	1,070.00	5,885.00
0104	6018000000-E	1620	SEED FOR TEMP SEEDING	400	LB	7.50	3,000.00
0105	6021000000-E	1620	FERT FOR TEMP SEEDING	2	TON	1,284.00	2,568.00
0106	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	1.00	200.00
0107	6029000000-E	SP	SAFETY FENCE	440	LF	3.20	1,408.00
0108	6030000000-E	1630	SILT EXCAVATION	150	CY	25.40	3,810.00
0109	6036000000-E	1631	MATTING FOR EROS CONTROL	2,600	SY	3.00	7,800.00
0110	6037000000-E	SP	COIR FIBER MAT	100	SY	5.00	500.00
0111	6042000000-E	1632	1/4" HARDWARE CLOTH	615	LF	4.15	2,552.25

44647.3.1

Jun 15, 2023

DC00439

TIP NO U-5914

0.373 MILES

FED AID NO STATE FUNDED

U-5914_NC 133 WIDENING AT SR 1554 (OLD RIVER RD.)

NC 133 FROM SR 1551 (BLACKWELL RD.) TO SR 1554 (OLD RIVER RD.)

CHATHAM CIVIL CONTRACTING
LLC
PITTSBORO, NC

0112	6045000000-E	SP	*** TEMPORARY PIPE (36")	115	LF	278.50	32,027.50
0113	6048000000-E	SP	FLOAT TURBIDITY CURTAIN	70	SY	33.75	2,362.50
0114	6070000000-N	1639	SPECIAL STILLING BASINS	10	EA	400.00	4,000.00
0115	6071012000-E	SP	COIR FIBER WATTLE	170	LF	11.00	1,870.00
0116	6071020000-E	SP	POLYACRYLAMIDE (PAM)	55	LB	13.50	742.50
0117	6071030000-E	1640	COIR FIBER BAFFLE	25	LF	5.00	125.00
0118	6084000000-E	1660	SEEDING AND MULCHING	6	ACR	2,889.00	17,334.00
0119	6087000000-E	1660	MOWING	6	ACR	1.00	6.00
0120	6090000000-E	1661	SEED FOR REPAIR SEEDING	100	LB	7.50	750.00
0121	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	1,284.00	321.00
0122	6096000000-E	1662	SEED FOR SUPP SEEDING	150	LB	7.50	1,125.00
0123	6108000000-E	1665	FERTILIZER TOPDRESSING	4.25	TON	1,284.00	5,457.00
0124	6111000000-E	SP	IMPERVIOUS DIKE	210	LF	35.15	7,381.50
0125	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	38.00	380.00
0126	6117000000-N	SP	RESPONSE FOR EROS CONTROL	25	EA	1.00	25.00
0127	6117500000-N	SP	CONC WASHOUT STRUCTURE	4	EA	1,025.00	4,100.00
0128	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (EA) FABRIC INSERT INLET PROTECTION DEVICE	8	EA	76.00	608.00
0129	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (EA) FABRIC INSERT PROTECTION DEVICE CLEANOUT	24	EA	152.00	3,648.00
0130	7048500000-E	1705	16" PEDEST SIG HEAD 1 SEC W/CD	2	EA	963.00	1,926.00
0131	7060000000-E	1705	SIGNAL CABLE	1,460	LF	3.20	4,672.00
0132	7120000000-E	1705	VEHICLE SIGNAL HD (12", 3 SECT)	7	EA	1,016.50	7,115.50
0133	7132000000-E	1705	VEHICLE SIGNAL HD (12", 4 SECT)	1	EA	1,284.00	1,284.00
0134	7264000000-E	1710	MESSENGER CABLE (3/8")	250	LF	3.20	800.00
0135	7300000000-E	1715	UNPAVED TRENCH (*****) (1 CONDUIT, 2")	170	LF	12.85	2,184.50
0136	7300000000-E	1715	UNPAVED TRENCH (*****) (2 CONDUITS, 2")	15	LF	17.15	257.25
0137	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	4	EA	615.25	2,461.00
0138	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	920	LF	7.50	6,900.00
0139	7456000000-E	1726	LEAD-IN CABLE(*****) (14-2)	2,200	LF	2.15	4,730.00
0140	7481000000-N	SP	SITE SURVEY	1	EA	1,926.00	1,926.00
0141	7481220000-N	SP	CAMERA W/ INT LOOP EMUL PROCESS	1	EA	13,080.75	13,080.75
0142	7481260000-N	SP	EXT LOOP EMULATOR PROCESS UNIT	1	EA	7,409.75	7,409.75
0143	7576000000-N	SP	METAL STRAIN SIGNAL POLE	1	EA	18,111.00	18,111.00
0144	7613000000-N	SP	SOIL TEST	1	EA	5,294.00	5,294.00
0145	7614100000-E	SP	DRILLED PIER FOUND	8	CY	5,142.00	41,136.00
0146	7636000000-N	1745	SIGN FOR SIGNALS	5	EA	374.50	1,872.50
0147	7642200000-N	1743	TYPE II PED W/ FOUNDATION	2	EA	3,905.50	7,811.00

44647.3.1

Jun 15, 2023

DC00439

TIP NO U-5914

0.373 MILES

FED AID NO STATE FUNDED

U-5914_NC 133 WIDENING AT SR 1554 (OLD RIVER RD.)

NC 133 FROM SR 1551 (BLACKWELL RD.) TO SR 1554 (OLD RIVER RD.)

CHATHAM CIVIL CONTRACTING
LLC
PITTSBORO, NC


0148	7708000000-N	1751	DETECTOR CARD (***** (TYPE 2070L)	1	EA	267.50	267.50
0149	7960000000-N	SP	METAL POLE FOUND REMVL	1	EA	3,745.00	3,745.00
0150	7972000000-N	SP	METAL POLE REMOVAL	1	EA	1,605.00	1,605.00
CULVERT ITEMS							
0151	8126000000-N	414	CULV EXCAV @ ***** (STA. 14+10.00 -Y1-)	Lump Sum			97,141.00
0152	8133000000-E	414	FND CONDIR MAT, BOX CULV	63.5	TON	80.00	5,080.00
0153	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	75.2	CY	2,843.95	213,865.04
0154	8245000000-E	425	REINF STEEL (CULVERT)	12,514	LB	1.00	12,514.00

CONTRACT TOTAL	TOTAL	4,811,193.03
ROADWAY ITEMS	SUB-TOTAL	4,482,592.99
CULVERT ITEMS	SUB-TOTAL	328,600.04

BIDDERS IN ORDER

CONTRACT TOTAL

CHATHAM CIVIL CONTRACTING LLC	1	4,811,193.03
-------------------------------	---	--------------

DocuSigned by:

 02B404268BC84C2...