PROJECT REFERENCE NO.	SHEET NO.
SS-4903BR	SIGN-4

APPROVED: 2017.05.03 10:31:22 -04'00'

DATE:

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 034343 ENGINEER MATTHEW THIGPEN

(401) **QUANTITY REQ'D 8**

36" X 36"
W11-2

YELLOW/GREEN REFLECTIVE SHEETING

ONE "U" POST PER SIGN

(402) QUANTITY REQ'D 4

36" X 36" X 36"
R1-2

ONE "U" POST PER SIGN

(403) QUANTITY REQ'D 4

30" X 30"
W2-6

ONE "U" POST PER SIGN

(404) QUANTITY REQ'D 1

18" X 18"
OM1-3

MOUNT BELOW SIGN 407
IN X INSTALLATIONS

(405) QUANTITY REQ'D 8

24" X 12"
W16-7PL

YELLOW/GREEN REFLECTIVE SHEETING

MOUNT BELOW SIGN 401
IN 8 INSTALLATIONS

(406) QUANTITY REQ'D 2

24" X 30"
R4-7

ONE "U" POST PER SIGN

(407) QUANTITY REQ'D 2



30" X 30"
W12-1

ONE "U" POST PER SIGN

(408) QUANTITY REQ'D 4

30" X 24"
R6-4

ONE "U" POST PER SIGN

(501)



1 - 24" X 12"
1 - 24" X 24"
2 - 24" X 12"
2 - 24" X 24"
2 - 21" X 15"

TWO "U" POST PER SIGN

(502)



2 - 24" X 12"
2 - 24" X 24"
2 - 21" X 15"

TWO "U" POST PER SIGN

(503)

1 - 24" X 12"
1 - 24" X 24"
1 - 21" X 15"

ONE "U" POST PER SIGN

(504)

1 - 24" X 12"
1 - 24" X 24"
1 - 21" X 15"

ONE "U" POST PER SIGN

(505)

2 - 21" X 15"

THREE "U" POST PER SIGN

(506)

1 - 24" X 12"
1 - 24" X 24"
1 - 21" X 15"

ONE "U" POST PER SIGN

(507)



1 - 24" X 12"
1 - 24" X 24"
3 - 24" X 12"
3 - 24" X 24"
3 - 21" X 15"

TWO STEEL BEAM BREAK-AWAY SUPPORTS

TYPE "E" & "F" SIGNS

5/3/2017
10:50:07
Raleigh\38286.04 NCDOT SS-4903BR\NCDOT\Traffic\Signing\CADD\Signing Layout Plans\Engseed.dgn
Usertthigpen