12/05/11

PROJ. REFERENCE NO.	SHEET NO.
SS-4903BR	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, and removal of existing asphalt pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+50.00	0	0	11+00.00	0	0
12+00.00	6	20	11+50.00	6	4
12+50.00	5	25	12+00.00	5	7
13+00.00	5	24	12+50.00	5	7
13+50.00	5	21	13+00.00	5	8
14+00.00	5	47	13+50.00	12	10
14+50.00	7	64	14+00.00	30	12

Station Rab	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station Y2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00	0	0	10+50.00	0	0
10+50.00	6	149	11+00.00	17	43
11+00.00	7	121	11+50.00	36	12
11+50.00	13	124	12+00.00	30	15
12+00.00	13	145	12+50.00	3	26
12+50.00	1	197	13+00.00	3	28
13+00.00	0	320	13+50.00	2	33
13+50.00	0	292	14+00.00	2	38
			14+50.00	4	40

Station Y	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+50.00	0	0
11+00.00	8	4
11+50.00	3	6
12+00.00	2	9
12+50.00	3	5
13+00.00	4	6
13+50.00	4	11
14+00.00	5	12

INDEX OF SHEETS

LINE	STATIONS	SHEETS
-L-	11+50.00 TO 14+50.00	X-1 THRU X-2
-RAB-	10+00.00 TO 13+50.00	X-3 THRU X-6
-Y-	10+50.00 TO 14+50.00	X-7 THRU X-8
-Y1-	11+00.00 TO 14+00.00	X-9 THRU X-10
-Y2-	10+50.00 TO 15+00.00	X-11 THRU X-13