PROJECT REFERENCE NO.	SHEET NO.
U-5719	X-1B

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified Excavation, Shoulder Borrow, Fine Grading, Removal of Existing Asphalt Pavement, and Clearing and Grubbing will be paid for at the contract lump sum price for "Grading."

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
16+08.00	0	0	13+50.00	0	0												
16+50.00	13	4	14+00.00	22	8												
17+00.00	46	12	14+50.00	51	16												
17+50.00	49	24	15+00.00	47	24												
18+00.00	16	25	15+50.00	31	20												
18+50.00	4	16	16+00.00	57	8												
19+00.00	4	12	16+50.00	137	1												
19+50.00	0	0	17+00.00	253	3												
20+00.00	44	183	17+50.00	400	3												
20+50.00	37	112	18+00.00	580	0												
21+00.00	37	49	18+50.00	499	0												
21+50.00	41	50	19+00.00	287	0												
22+00.00	43	37	19+50.00	260	0												
22+50.00	43	19	20+00.00	253	0												
23+00.00	46	28	20+50.00	211	2												
23+25.00	27	18	21+00.00	189	5												
23+50.00	30	14	21+50.00	187	9												
24+00.00	54	36	22+00.00	118	61												
24+50.00	50	47	22+50.00	75	246												
25+00.00	41	26															
25+40.00	18	2															

8/17/99
23-MAR-2017 07:24
S:\U5719\Rdy\XSC\U-5719_RDY_XPL_1B.dgn
pb0059742 AT * PS\KM72