DocuSign Envelope ID: 09A4C58C-F42E-4A26-BA77-2E841E3B2533

PROJECT REFERENCE NO.	SHEET NO.
U-5719	SIGN-1

APPROVED: DocuSigned by: Jason M. Pickens 20CE483822FA4DB...

DATE: 3/29/2017

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 37950 ENGINEER JASON M. PICKENS

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

SIGNING PLAN
ONSLOW COUNTY

LOCATION: SR 1396 (RIDGE ROAD) AT US 258 AND BLUE CREEK ROAD

T.I.P.: U-5719

CONTRACT: DC00142

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
903.10	GROUND MOUNTED SIGN SUPPORTS
904.10	ORIENTATION OF GROUND MOUNTED SIGNS
904.50	MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS

GENERAL NOTES

. SIGNS FURNISHED BY CONTRACTOR

. IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER.

. WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER

. WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.

. THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.

INDEX

SHEET NO.	DESCRIPTION
SIGN-1	TITLE SHEET
SIGN-2	EXISTING SIGNS
SIGN-3	EXISTING AND PROPOSED SIGNS

SUMMARY OF QUANTITIES

ITEM NO. DESC. NO.	ITEM NO. SECT. NO.	ITEM DESCRIPTION	QUANTITY	UNIT
4025000000	901	CONTRACTOR FURNISHED, TYPE E SIGN	30.5	S.F.
4072000000	903	SUPPORTS, 3 LB STEEL U-CHANNEL	192	L.F.
4102000000	904	SIGN ERECTION, TYPE E	8	EA.
4116100000	904	SIGN ERECTION, RELOCATE SIGN TYPE D	1	EA.
4116100000	904	SIGN ERECTION, RELOCATE SIGN TYPE E	7	EA.
4155000000	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	5	EA.
4192000000	907	DISPOSAL OF SUPPORT, U-CHANNEL	8	EA.

PROJECT NOTES

1 DISPOSAL OF SIGN SYSTEM, U-CHANNEL

2 DISPOSAL OF SUPPORT, U-CHANNEL

3 RELOCATE SIGN, TYPE D

4 RELOCATE SIGN, TYPE E

401 QUANTITY REQ'D 2



30" X 30"
W3-3

ONE "U" POST PER SIGN

402 QUANTITY REQ'D 3

18" X 24"
W1-2L

ONE "U" POST PER SIGN

403 QUANTITY REQ'D 3

18" X 24"
W1-2R

ONE "U" POST PER SIGN

PLAN PREPARED FOR: NCDOT SIGNING AND DELINEATION UNIT

DAVID L. WILVER, PE	SIGNING & DELINEATION PROJECT ENGINEER
J. MATTHEW PICKENS, PE	SIGNING & DELINEATION PROJECT DESIGN ENGINEER

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

PLANS PREPARED BY:
PARSONS
800 CENTERVIEW DR., SUITE 217
RALEIGH, NORTH CAROLINA 27603
N.C. LICENSE NO: F-0246
FOR NORTH CAROLINA DEPT. OF TRANSPORTATION

29-MAR-2017 07:33
J:\U-5719\Traffic\Signing\CADD\Signing Layout Plans\U-5719_SGN_TSH_01.dgn
$$$$USERNAME$$$$