DocuSign Envelope ID: 09A4C58C-F42E-4A26-BA77-2E841E3B2533

5/14/99

T.I.P.: U-5719

PROJECT REFERENCE NO.	SHEET NO.
U-5719	PMP-1

NORTH CAROLINA PROFESSIONAL SEAL 37950 ENGINEER JASON M. ENGLAND 3/29/2017

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING PLAN

ONSLOW COUNTY

LOCATION: IMPROVEMENTS TO SR 1396 AT US 258 AND BLUE CREEK ROAD

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - 2 LANE AND MULTILANE ROADWAYS
1205.04	PAVEMENT MARKINGS - INTERSECTIONS
1205.05	PAVEMENT MARKINGS - TURN LANES
1205.08	PAVEMENT MARKINGS - SYMBOL AND WORD MESSAGES
1205.09	PAVEMENT MARKINGS - PAINTED ISLANDS
1250.01	RAISED PAVEMENT MARKERS - INSTALLATION SPACING
1251.01	RAISED PAVEMENT MARKERS - TEMPORARY AND PERMANENT
1253.01	RAISED PAVEMENT MARKERS - SNOWPLOWABLE
1261.01	GUARDRAIL AND BARRIER DELINEATORS - INSTALLATION SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATORS - TYPES AND MOUNTING
1262.01	GUARDRAIL END DELINEATION
1264.01	OBJECT MARKINGS - TYPES
1264.02	OBJECT MARKINGS - INSTALLATION

FINAL PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAVEMENT MARKINGS
		THERMOPLASTIC (24", 120 MILS)
T2	WHITE STOPBAR	
		THERMOPLASTIC (8", 90 MILS)
TN	WHITE GORELINE	
		THERMOPLASTIC (4", 90 MILS)
TA	WHITE EDGELINE	
		THERMOPLASTIC (4", 120 MILS)
T8	2'-6'/SP WHITE MINISKIP	
TC	10' WHITE SKIP	
TD	3'-9'/SP WHITE MINISKIP	
TE	WHITE SOLID LANE LINE	
TF	10' YELLOW SKIP	
TH	YELLOW SINGLE CENTER	
TI	YELLOW DOUBLE CENTER LINE	
		THERMOPLASTIC SYMBOL (90 MILS)
UA	LEFT ARROW	
UB	RIGHT ARROW	
UC	STRAIGHT ARROW	
UD	COMBO. LEFT/STRAIGHT ARROW	
UE	COMBO. RIGHT/STRAIGHT ARROW	

INDEX

SHEET NO.	DESCRIPTION
PMP-01	PAVEMENT MARKING PLAN TITLE SHEET
PMP-02	FINAL PAVEMENT MARKING PLAN

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

A) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

ROAD TYPE	MARKING	MARKER
-L- (US 258)	THERMOPLASTIC	SNOWPLOWABLE
-Y- LINES	THERMOPLASTIC	PERMANENT RAISED

B) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.

C) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.

D) MARKERS SHALL BE INSTALLED ACCORDING TO THE NCDOT ROADWAY STANDARD DRAWING 1250.01.

PLANS PREPARED BY:

DAVID L. WILVER, P.E. PROJECT ENGINEER

J. MATTHEW PICKENS, P.E. PROJECT DESIGN ENGINEER

PLANS PREPARED BY :

PARSONS

NC LICENSE NO. F-0246

FOR DIVISION OF HIGHWAYS

29-MAR-2017 07:37
J:\U-5719\Traffic\PMP\U-5719_PMP_01.dgn
$$$$USERNAME$$$$