


09/08/19

TIP PROJECT: R-4436CI

CONTRACT: 34625.2.67

2/22/2017
WLM_Rdy_psh-01.dgn
lisa.jamison





STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NEW HANOVER

LOCATION: US 74 RAMP AND McRAE ST, WILMINGTON

TYPE OF WORK: GRADING, STORM DRAINAGE, INFILTRATION BASIN, EROSION CONTROL,
AND SEEDING & MULCHING



DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

GRAPHIC SCALES

SCALE VARIES
SEE PLANS



LETTING DATE:
MAY 18, 2017

Prepared by
AECOM
AECOM TECHNICAL SERVICES OF NORTH CAROLINA
Licensure Number F-0342
1600 Perimeter Park Drive
Morrisville, North Carolina 27560
TELEPHONE: (919) 461-1100 FAX: (919) 461-1415

JASON SITES, PE
PROJECT ENGINEER


PROJECT DESIGN ENGINEER

HYDRAULICS ENGINEER

SIGNATURE: _____ P.E.

NCDOT CONTACT
BRIAN LIPSCOMB, P.E.
HIGHWAY STORMWATER PROGRAM

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA
HYDRAULICS UNIT
STORMWATER GROUP



PROJECT ENGINEER

8/17/99

INDEX OF SHEETS

SHEET NUMBER	SHEET DESCRIPTION
1	TITLE SHEET
1-A	INDEX OF SHEETS, GENERAL NOTES, AND LIST OF STANDARD DRAWINGS
1-B	CONVENTIONAL SYMBOLS
1-C	SURVEY CONTROL
2-A	BMP DETAILS 1 & PROFILE
2-B	BMP DETAILS 2
3B/3D	EARTHWORK, DRAINAGE & EROSION CONTROL SUMMARIES
4	PLAN SHEET
EC-1	EROSION CONTROL PLANS
TC-1	TRAFFIC CONTROL PLANS

CONSTRUCTION SEQUENCE NOTES

PROJECT REQUIRES A PRE-CONSTRUCTION CONFERENCE PRIOR TO INITIATING ANY EARTH DISTURBANCE ACTIVITIES.

1. INSTALL TEMPORARY SILT FENCE, ROCK PIPE INLET SEDIMENT TRAP AND GRAVEL CONSTRUCTION ENTRANCE AS SHOWN ON PLANS.
2. CONSTRUCT INFILTRATION BASIN, AND OTHER IMPROVEMENTS.
3. FOLLOW SEEDING/ MULCHING GUIDELINES ON THE PLANS TO STABILIZE ALL REMAINING DISTURBED SURFACES.
4. INSPECT ALL INLETS, PIPES, AND OUTLETS FOR SEDIMENT AND REMOVE SEDIMENT AS REQUIRED.
5. REMOVE ALL REMAINING TEMPORARY EROSION CONTROL MEASURES AFTER PERMANENT PERENNIAL VEGETATION IS ESTABLISHED.

EROSION CONTROL NOTES

1. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH NCDOT STANDARDS, SPECIFICATIONS, AND DETAILS, LATEST VERSION.
2. CONTRACTOR SHALL MAINTAIN ALL EROSION CONTROL MEASURES DURING THE LIFE OF THE PROJECT UNLESS OTHERWISE INDICATED ON THE PLANS OR DIRECTED BY NCDOT INSPECTOR.
3. CONTRACTOR SHALL CONSTRUCT DIVERSION DITCHES AS NECESSARY TO ENSURE THAT ALL SEDIMENT IS DIRECTED INTO EROSION CONTROL MEASURES.
4. CUT AND FILL SLOPES SHALL BE STABILIZED WITHIN 14 DAYS OF ANY PHASE OF GRADING. SLOPES 3:1 OR STEEPER SHALL BE STABILIZED WITHIN 7 DAYS.
5. PROVIDE TEMPORARY EROSION CONTROL MEASURES AS NECESSARY TO PREVENT SEDIMENT FROM MIGRATING INTO BASIN BOTTOM OR SODDED AREAS.
6. ALL STREETS ADJACENT TO THIS PROJECT SHALL REMAIN CLEAN AT ALL TIMES OR A WASH STATION MAY BE REQUIRED.
7. IF USED, SILT FENCE SHALL BE MAINTAINED ON THE SITE UNTIL ALL SITE WORK IS COMPLETED AND THE FINAL SITE INSPECTION IS COMPLETE.
8. RESEED OF PERMANENT GROUND COVER WILL BE ESTABLISHED IN 15 WORKING DAYS OR 30 CALENDAR DAYS, WHICH EVER IS SHORTER.
9. EROSION CONTROL MATTING SHALL BE STRAW MATTING. USE STD. DWG. 1631.01 FOR MATTING INSTALLATION.
10. PROVIDE GRAVEL CONSTRUCTION ENTRANCE PER 1607.01 AS NEEDED TO PREVENT TRACKING OFFSITE.

SURVEY

LOCATIONS AND ELEVATIONS SHOULD BE FIELD VERIFIED. CONSULT WITH ENGINEER IF SIGNIFICANT DEVIATIONS FROM THE PLAN ARE REQUIRED.

UTILITIES

THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATIONS AS TO THE LOCATION OF UTILITIES. EXISTING UTILITIES AND STRUCTURES (UNDERGROUND, SURFACE, OR OVERHEAD) ARE INDICATED ONLY TO THE THE EXTENT THAT SUCH INFORMATION WAS KNOWN, MADE AVAILABLE TO, OR DISCOVERED BY THE ENGINEER IN PREPARING THE DRAWINGS. THE LOCATIONS, CONFIGURATIONS, AND ELEVATIONS OF SUBSURFACE FACILITIES AND UTILITIES ARE APPROXIMATE, AND NOT ALL UTILITIES AND FACILITIES MAY BE INDICATED.

2012 ROADWAY ENGLISH STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" HIGHWAY DESIGN BRANCH – N.C. DEPARTMENT OF TRANSPORTATION – RALEIGH, N.C., JANUARY, 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED PART OF THESE PLANS.

STD.NO.	TITLE
DIVISION 2 – EARTHWORK	
200.02	METHOD OF CLEARING – METHOD 11
DIVISION 11 – WORK ZONE TRAFFIC CONTROL	
1101.01	DETAIL DRAWING FOR TWO-WAY UNDIVIDED WORK ZONE WARNING SIGNS
1101.02	TEMPORARY LANE CLOSURES – 2-LANE, 2-WAY ROADWAY – 1 LANE CLOSED
DIVISION 16 – EROSION CONTROL AND ROADSIDE DEVELOPMENT	
1605.01	TEMPORARY SILT FENCE
1607.01	GRAVEL CONSTRUCTION ENTRANCE
1635.02	ROCK PIPE INLET SEDIMENT TRAP TYPE B

GENERAL NOTES

GRADING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED OR FUTURE SURFACING AT GRADE POINTS SHOWN ON THE PLANS. GRADE LINES MAY BE ADJUSTED AT THEIR BEGINNING AND ENDING AND AT STRUCTURES AS DIRECTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD 11.

TRAFFIC CONTROL:

USE APPROPRIATE STANDARDS PER DIVISION 11 AS REQUIRED TO COMPLETE WORK. COORDINATE TRAFFIC CONTROL WITH THE DIVISION.

SEEDBED PREPARATION

1. PREPARE AND SEED ONLY DISTURBED AREAS. DO NOT SPREAD SEED ON AREAS TO RECEIVE SOD. SEE SHEET 2-A FOR 3-D GEOTEXTILE & SOD INSTALLATION.
2. CHISEL COMPACTED AREAS AND SPREAD TOPSOIL 3 INCHES DEEP OVER ADVERSE SOIL CONDITIONS IF AVAILABLE.
3. RIP THE ENTIRE AREA TO 6 INCHES DEPTH.
4. REMOVE ALL LOOSE ROCK, ROOTS AND OTHER OBSTRUCTIONS LEAVING SURFACES REASONABLY SMOOTH AND UNIFORM.
5. APPLY AGRICULTURAL LIME, FERTILIZER, AND SUPERPHOSPHATE UNIFORMLY AND MIX WITH SOIL (SEE BELOW*).
6. CONTINUE TILLAGE UNTIL A WELL-PULVERIZED, FIRM, REASONABLY UNIFORM SEEDBED IS PREPARED 4 TO 6 INCHES DEEP.
7. SEED A FRESHLY PREPARED SEEDBED AND COVER SEED LIGHTLY WITH SEEDING EQUIPMENT OR CULTIPACK AFTER SEEDING.
8. MULCH IMMEDIATELY AFTER SEEDING AND ANCHOR MULCH.
9. INSPECT ALL SEEDED AREAS AND MAKE ALL NECESSARY REPAIRS OR RESEEDINGS WITHIN THE PLANTING SEASON, IF POSSIBLE. IF STAND SHOULD BE OVER 70% DAMAGED, REESTABLISH FOLLOWING ORIGINAL LIME, FERTILIZER AND SEEDING RATES.
10. CONSULT CONSERVATION INSPECTOR ON MAINTENANCE TREATMENT AND FERTILIZATION AFTER PERMANENT COVER IS ESTABLISHED.


*APPLY: AGRICULTURAL LIMESTONE – 2 TONS/ACRE (34 TONS/ACRE ON CLAY SOILS)
FERTILIZER – 1,000 LBS/ACRE – 10-10-10
SUPERPHOSPHATE – 500 LBS/ACRE – 20%
MULCH – 2 TONS/ACRE – SMALL GRAIN STRAW
ANCHOR – ASPHALT EMULSION @ 300 GAL. ACRE

MAINTENANCE PLAN

1. ALL EROSION AND SEDIMENTATION CONTROL PRACTICES WILL BE CHECKED FOR STABILITY AND OPERATION FOLLOWING EVERY RUNOFF-PRODUCING RAINFALL BUT IN NO CASE LESS THAN ONCE A WEEK. ANY NEEDED REPAIRS WILL BE MADE IMMEDIATELY TO MAINTAIN ALL PRACTICES AS DESIGNED.
2. SEDIMENT WILL BE REMOVED FROM BEHIND THE SILT FENCE WHEN IT BECOMES ABOUT 6-INCHES DEEP AT THE FENCE. THE SILT FENCE WILL BE REPAIRED AS NECESSARY TO MAINTAIN A BARRIER.
3. INLET PROTECTION DEVICES SHALL BE INSPECTED AFTER EVERY RAINFALL EVENT. DAMAGED SILT FENCE SHALL BE REPLACED AND GRAVEL SHALL BE CLEANED OR REPLACED WHEN INLET NO LONGER DRAINS PROPERLY.

PROJECT REFERENCE NO.	SHEET NO.
R-4436C1	1-A

HYDRAULICS
ENGINEER



2/22/2017

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

CONVENTIONAL PLAN SHEET SYMBOLS

PROJECT REFERENCE NO.	SHEET NO.
R-4436CI	I-B

BOUNDARIES AND PROPERTY:

State Line	
County Line	
Township Line	
City Line	
Reservation Line	
Property Line	
Existing Iron Pin	
Computed Property Corner	
Property Monument	
Parcel/Sequence Number	
Existing Fence Line	
Proposed Woven Wire Fence	
Proposed Chain Link Fence	
Proposed Barbed Wire Fence	
Existing Wetland Boundary	
Proposed Wetland Boundary	
Existing Endangered Animal Boundary	
Existing Endangered Plant Boundary	
Existing Historic Property Boundary	
Known Contamination Area: Soil	
Potential Contamination Area: Soil	
Known Contamination Area: Water	
Potential Contamination Area: Water	
Contaminated Site: Known or Potential	

BUILDINGS AND OTHER CULTURE:

Gas Pump Vent or U/G Tank Cap	
Sign	
Well	
Small Mine	
Foundation	
Area Outline	
Cemetery	
Building	
School	
Church	
Dam	

HYDROLOGY:

Stream or Body of Water	
Hydro, Pool or Reservoir	
Jurisdictional Stream	
Buffer Zone 1	
Buffer Zone 2	
Flow Arrow	
Disappearing Stream	
Spring	
Wetland	
Proposed Lateral, Tail, Head Ditch	
False Sump	

RAILROADS:

Standard Gauge	
RR Signal Milepost	
Switch	
RR Abandoned	
RR Dismantled	

RIGHT OF WAY & PROJECT CONTROL:

Secondary Horiz and Vert Control Point	
Primary Horiz Control Point	
Primary Horiz and Vert Control Point	
Exist Permanent Easment Pin and Cap	
New Permanent Easement Pin and Cap	
Vertical Benchmark	
Existing Right of Way Marker	
Existing Right of Way Line	
New Right of Way Line	
New Right of Way Line with Pin and Cap	
New Right of Way Line with Concrete or Granite R/W Marker	
New Control of Access Line with Concrete C/A Marker	
Existing Control of Access	
New Control of Access	
Existing Easement Line	
New Temporary Construction Easement	
New Temporary Drainage Easement	
New Permanent Drainage Easement	
New Permanent Drainage /Utility Easement	
New Permanent Utility Easement	
New Temporary Utility Easement	
New Aerial Utility Easement	

ROADS AND RELATED FEATURES:

Existing Edge of Pavement	
Existing Curb	
Proposed Slope Stakes Cut	
Proposed Slope Stakes Fill	
Proposed Curb Ramp	
Existing Metal Guardrail	
Proposed Guardrail	
Existing Cable Guiderail	
Proposed Cable Guiderail	
Equality Symbol	
Pavement Removal	

VEGETATION:

Single Tree	
Single Shrub	

*S.U.E. = Subsurface Utility Engineering

Hedge	
Woods Line	
Orchard	
Vineyard	

EXISTING STRUCTURES:

MAJOR:	
Bridge, Tunnel or Box Culvert	
Bridge Wing Wall, Head Wall and End Wall	
MINOR:	
Head and End Wall	
Pipe Culvert	
Footbridge	
Drainage Box: Catch Basin, DI or JB	
Paved Ditch Gutter	
Storm Sewer Manhole	
Storm Sewer	

UTILITIES:

POWER:	
Existing Power Pole	
Proposed Power Pole	
Existing Joint Use Pole	
Proposed Joint Use Pole	
Power Manhole	
Power Line Tower	
Power Transformer	
U/G Power Cable Hand Hole	
H-Frame Pole	
U/G Power Line LOS B (S.U.E.*)	
U/G Power Line LOS C (S.U.E.*)	
U/G Power Line LOS D (S.U.E.*)	

TELEPHONE:

Existing Telephone Pole	
Proposed Telephone Pole	
Telephone Manhole	
Telephone Pedestal	
Telephone Cell Tower	
U/G Telephone Cable Hand Hole	
U/G Telephone Cable LOS B (S.U.E.*)	
U/G Telephone Cable LOS C (S.U.E.*)	
U/G Telephone Cable LOS D (S.U.E.*)	
U/G Telephone Conduit LOS B (S.U.E.*)	
U/G Telephone Conduit LOS C (S.U.E.*)	
U/G Telephone Conduit LOS D (S.U.E.*)	
U/G Fiber Optics Cable LOS B (S.U.E.*)	
U/G Fiber Optics Cable LOS C (S.U.E.*)	
U/G Fiber Optics Cable LOS D (S.U.E.*)	

WATER:

Water Manhole	
Water Meter	
Water Valve	
Water Hydrant	
U/G Water Line LOS B (S.U.E.*)	
U/G Water Line LOS C (S.U.E.*)	
U/G Water Line LOS D (S.U.E.*)	
Above Ground Water Line	

TV:

TV Pedestal	
TV Tower	
U/G TV Cable Hand Hole	
U/G TV Cable LOS B (S.U.E.*)	
U/G TV Cable LOS C (S.U.E.*)	
U/G TV Cable LOS D (S.U.E.*)	
U/G Fiber Optic Cable LOS B (S.U.E.*)	
U/G Fiber Optic Cable LOS C (S.U.E.*)	
U/G Fiber Optic Cable LOS D (S.U.E.*)	

GAS:

Gas Valve	
Gas Meter	
U/G Gas Line LOS B (S.U.E.*)	
U/G Gas Line LOS C (S.U.E.*)	
U/G Gas Line LOS D (S.U.E.*)	
Above Ground Gas Line	

SANITARY SEWER:

Sanitary Sewer Manhole	
Sanitary Sewer Cleanout	
U/G Sanitary Sewer Line	
Above Ground Sanitary Sewer	
SS Forced Main Line LOS B (S.U.E.*)	
SS Forced Main Line LOS C (S.U.E.*)	
SS Forced Main Line LOS D (S.U.E.*)	

MISCELLANEOUS:

Utility Pole	
Utility Pole with Base	
Utility Located Object	
Utility Traffic Signal Box	
Utility Unknown U/G Line LOS B (S.U.E.*)	
U/G Tank; Water, Gas, Oil	
Underground Storage Tank, Approx. Loc.	
A/G Tank; Water, Gas, Oil	
Geoenvironmental Boring	
U/G Test Hole LOS A (S.U.E.*)	
Abandoned According to Utility Records	AATUR
End of Information	E.O.I.

8/17/99

REVISIONS


2/20/2017
WTC/Edw.esh-01C.dgn
USA, London

SURVEY CONTROL

GPS-1

NAD 83/2011

PROJECT REFERENCE NO.		SHEET NO.
R-4436C1		I-C
RW SHEET NO.		
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	
	<div><div>SEAL</div><div>035946</div><div>ENGINEER</div><div>JASON S. STEB</div><div>2/22/2017</div></div>	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED		



GPS-2

EXISTING CONDITIONS SURVEY

SITE COORDINATE CONTROL AND EXISTING CONDITIONS FOR PROJECT ARE FROM A TOPOGRAPHIC SURVEY PERFORMED IN NOVEMBER 2016 BY: AECOM

DATUM DESCRIPTION

THE LOCALIZED COORDINATE SYSTEM DEVELOPED FOR THIS PROJECT IS BASED ON THE STATE PLANE COORDINATES ESTABLISHED BY OTHERS FOR MONUMENT "GPS-1" WITH NAD 83/NSRS 2007 STATE PLANE GRID COORDINATES OF NORTHING: 185820.322(ft) EASTING: 2320759.531(ft) ELEVATION: 15.51(ft) THE AVERAGE COMBINED GRID FACTOR USED ON THIS PROJECT (GROUND TO GRID) IS: 0.999778365 THE N.C. LAMBERT GRID BEARING AND LOCALIZED HORIZONTAL GROUND DISTANCE FROM "GPS-1" TO -L- STATION IS


ALL LINEAR DIMENSIONS ARE LOCALIZED HORIZONTAL DISTANCES VERTICAL DATUM USED IS NAVD 88

POINT	NORTHING	EASTING	ELEVATION	DESCRIPTION
1	185820.322	2320759.531	15.51	GPS-1
2	185269.921	2320752.31	18.16	GPS-2


8/17/99

REVISIONS


2/20/2017
WTC Edw.esh-02A.dgn
USA, London

PROJECT REFERENCE NO.		SHEET NO.
R-4436C1		2-A
RW SHEET NO.		
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	
		
2/22/2017		
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED		

BMP DETAILS 1 & PROFILE




- NOTE:
1. PLACE ZOYSIA SOD ON BASIN BOTTOMS, BERMS, AND SIDE SLOPES.
 2. SEE SPECIAL PROVISIONS FOR 3-D GEOTEXTILE. ANCHOR ON SIDE SLOPES PER MANUFACTURE'S INSTRUCTIONS.
 3. 3-D GEOTEXTILE & SOD INSTALLATION METHOD
 - a. LOOSEN SURFACE SOIL (TILL)
 - b. LAY 3-D GEOTEXTILE SO THAT LOOSENEED SOIL FILLS UNDERSIDE VOIDS
 - c. FEATHER SOIL ON TOP OF 3-D GEOTEXTILE TO FILL TOP VOIDS
 - d. ANCHOR PER MANUFACTURER'S RECOMONDATIONS.
 - e. LAY SOD & WATER PER STD. SPECIFICATION 1664 UNLESS OTHERWISE NOTED ON THESE PLANS. DO NOT APPLY LIME OR FERTILIZER.
 4. MAINTAIN EXISTING INFILTRATION RATE. NO HEAVY CONSTRUCTION EQUIPMENT PERMITTED ON BASIN BOTTOM. CONTACT ENGINEER IF CLAYEY SOILS ARE ENCOUNTERED DURING CONSTRUCTION.
 5. CONTRACTOR SHALL CONDUCT HYDRAULIC CONDUCTIVITY TESTS AT 2 LOCATIONS IN THE BASIN BOTTOM PRIOR TO INSTALLATION OF GEOTEXTILE AND SOD. RESULTS SHALL BE REPORTED TO THE ENGINEER PRIOR TO INSTALLATION OF GEOTEXTILE AND SOD.



3-D GEOTEXTILE & SOD INSTALLATION
N.T.S.

TYPICAL SECTION – INFILTRATION BASIN
N.T.S.




SECTION A-A – INFILTRATION BASIN
N.T.S.

8/17/99

REVISIONS

2/20/2017
WTC Edw.esh-02B.dgn
USA, Landon

BMP DETAILS 2




- NOTES:
1. PROVIDE WATER TIGHT CONNECTIONS USING WATERSTOP OR COMPRESSION GASKET APPROVED BY ENGINEER ON ALL OUTLET STRUCTURE PENETRATIONS.
 2. SEE DETAIL SHEET 2-A FOR INFILTRATION BASIN TYPICAL SECTION
 3. EXCAVATE AROUND EXISTING 15" RCP TO ACCOMMODATE BOX. SET BOX ON TOP OF EXISTING 15" RCP AND PROVIDE WATER TIGHT SEAL.
 4. GROUT BOTTOM TO OUTLET PIPE INVERT ELEVATON (12.3).

INFILTRATION BASIN OUTLET STRUCTURE DETAIL

N.T.S.

BASIN REF.	TOP BOX EL.	BOTTOM EL.	OUTLET PIPE INVERT	BOX INVERT
1	14.25	13.0	12.3	12.0



INFILTRATION BASIN FOREBAY

N.T.S.

- NOTE:
1. EXTEND RIP RAP MIN 3' INTO BASIN BOTTOM. SEE PLAN VIEW SHEET 4 FOR EXTENT OF RIP RAP.
 2. ELEVATIONS INDICATE TOP OF RIPRAP.

BASIN REF.	TOP TRANSITION BERM	BERM LENGTH	BOTTOM EL.	BASE LENGTH	LINING
1	14	5.0	11	2.0	CLASS B RIPRAP


PROJECT REFERENCE NO. <i>R-4436C1</i>		SHEET NO. <i>2-B</i>
RW SHEET NO.		
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	
	<div><div>SEAL</div><div>035946</div><div>ENGINEER</div><div>JASON S. STES</div><div>2/22/2017</div></div>	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED		

8/17/99

REVISIONS

2/20/2017
WTC/Edw.esh-03.dgn
USA, Landon

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJECT REFERENCE NO.		SHEET NO.	
R-4436C1		3B / 3D	
RW SHEET NO.			
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
			
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED			

SUMMARY OF EARTHWORK
(for Stormwater BMP's)

ITEM DESCRIPTION	UNIT	QUANTITY
		PROJECT TOTALS
UNCLASSIFIED EXCAVATION	CY	225
CLEARING AND GRUBBING	ACR	0.10
RIPRAP, CL. B	TON	90

DRAINAGE SUMMARY
(for Stormwater BMP's)

ITEM DESCRIPTION	UNIT	QUANTITY
		PROJECT TOTALS
GEOTEXTILE FOR DRAINAGE (TYPE 2, NON-WOVEN)	SY	150
OUTLET STRUCTURE BOX (840.14)	EA	1
FRAME WITH 2 GRATES, STD.840.16	EA	1
3-D GEOTEXTILE	SY	240
PIPE REMOVAL	LF	10

SUMMARY FOR EROSION CONTROL
(for Stormwater BMP's)


ITEM DESCRIPTION	UNIT	QUANTITY
		PROJECT TOTALS
SEDIMENT CONTROL STONE NO. 57	TON	12
TEMP. SILT FENCE	LF	35
SEEDING & MULCHING	ACR	0.1
SODDING	SY	350
WATER	MG	12
EROSION CONTROL STONE CL. A	TON	25

8/17/99

REVISIONS


2/20/2017
WTC Edw.esh-04.dgn
USA, Landon

PLAN VIEW



NOTES:

1. SEE SHEETS 2-A AND 2-B FOR DETAILS.
2. SOD WILL BE PLACED ON BASIN BOTTOM AND SIDES UNLESS OTHERWISE NOTED.
3. ALL VEGETATION SHALL BE CUT BACK TO THE FENCELINE.



NAD 83/2011

PROJECT REFERENCE NO.		SHEET NO.
R-4436C1		4
RW SHEET NO.		
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED		

8/17/99

REVISIONS

2/20/2017
W:\Cadd\ash.ec-1.dgn
USA, J. J. J.

EROSION CONTROL PLAN

NAD 83/2011


PROJECT REFERENCE NO.
R-4436C1

SHEET NO.
EC-1


RW SHEET NO.

ROADWAY DESIGN ENGINEER

HYDRAULICS ENGINEER



DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED



NOTES: ANY DEVIATION FROM OPTIONS GIVEN WILL REQUIRE PRIOR APPROVAL BY ENGINEER.

ADDITIONAL EROSION CONTROL DEVICES MAY NEED TO BE INSTALLED AS DIRECTED BY THE ENGINEER.

THESE EROSION AND SEDIMENT CONTROL PLANS COMPLY WITH THE REGULATIONS SET FORTH BY THE NCG-010000 GENERAL CONSTRUCTION PERMIT EFFECTIVE AUGUST 3, 2011 ISSUED BY THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT AND NATURAL RESOURCES DIVISION OF WATER QUALITY.

EROSION AND SEDIMENT CONTROL MEASURES		
Std. #	Description	Symbol
1605.01	Temporary Silt Fence	
1607.01	Gravel Construction Entrance	
1635.02	Rock Pipe Inlet Sediment Trap Type-B	

SOIL STABILIZATION TIMEFRAMES

SITE DESCRIPTION	STABILIZATION TIME	TIMEFRAME EXCEPTIONS
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HOW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HOW ZONES.


SEEDING SCHEDULE SHOULDERS, SIDE DITCHES, SLOPES (MAX. 3:1)		
DATE	TYPE	PLANTING RATE
AUG 15-NOV 1	TALL FESCUE	300 LBS/ACRE
NOV 1-MAR 1	TALL FESCUE AND ABRUZZIRYE	300 LBS/ACRE
MAR 1-APR 15	TALL FESCUE	300 LBS/ACRE
APR 15-JUNE 20	HULLED COMMON BERMUDAGRASS	25 LBS/ACRE
JUNE 30-AUG 15	TALL FESCUE AND ***BROWNTOP MILLET ***OR SORGHUM-SUDAN HYBRIDS	35 LBS/ACRE
SLOPES (3:1 TO 2:1)		
DATE	TYPE	PLANTING RATE
MAR 1-JUN 1	SERICEA LESPEDEZA (SCARIFIED) AND	50 LBS/ACRE
MAR 1-APR 15	ADD TALL FESCUE	120 LBS/ACRE
MAR 1-JUNE 30	ADD WEEPING LOVEGRASS OR	10 LBS/ACRE
MAR 1-JUNE 30	ADD HULLED COMMON BERMUDAGRASS	25 LBS/ACRE
JUNE 1-SEP 1	***TALL FESCUE AND ***BROWNTOP MILLET ***OR SORGHUM-SUDAN HYBRIDS	120 LBS/ACRE 35 LBS/ACRE 30 LBS/ACRE
SEP 1-MAR 1	SERICEA LESPEDEZA (UNHULLED-UNSCARIFIED) AND TALL FESCUE	70 LBS/ACRE
NOV 1-MAR 1	ADD ABRUZZIRYE	120 LBS/ACRE
CONSULT EROSION CONTROL ENGINEER OR SOIL CONSERVATION SERVICE FOR ADDITIONAL INFORMATION CONCERNING OTHER ALTERNATIVES FOR VEGETATION OF DENUDED AREAS. THE ABOVE VEGETATION RATES ARE THOSE WHICH DO WELL UNDER LOCAL CONDITIONS; OTHER SEEDING RATES COMBINATIONS ARE POSSIBLE.		
***TEMPORARY-RESEED ACCORDING TO OPTIMUM SEASON FOR DESIRED PERMANENT VEGETATION. DO NOT ALLOW TEMPORARY COVER TO GROW OVER 12 INCHES IN HEIGHT BEFORE MOWING, OTHERWISE FESCUE MAY BE SHADED OUT.		

8/17/99

REVISIONS

2/20/2017
PSH-TC-1.dgn
JASON S. STILES
035946
2/22/2017

TRAFFIC CONTROL PLAN

PROJECT REFERENCE NO.		SHEET NO.	
R-443601		TC-1	
RW SHEET NO.			
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
			
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED			

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
HALEIGH, N.C.


1-12

DETAIL
DRAWING FOR TWO-WAY UNDIVIDED
WORK ZONE WARNING SIGNS

ENGLISH STANDARD DRAWING FOR

SHEET 3 OF 3
1101.01

TWO-WAY UNDIVIDED (L-LINES)



POSTED SPEED LIMIT (MPH)	RECOMMENDED MINIMUM SIGN SPACING (ft)
≤ 60	600'
65	1000'

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
HALEIGH, N.C.

1-12

DETAIL
DRAWING FOR TWO-WAY UNDIVIDED
WORK ZONE WARNING SIGNS

ENGLISH STANDARD DRAWING FOR

SHEET 3 OF 3
1101.01


STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
HALEIGH, N.C.

1-12

TEMPORARY LANE CLOSURES
2-LANE, 2-WAY ROADWAY-1 LANE CLOSED

ENGLISH STANDARD DRAWING FOR

SHEET 1 OF 15
1101.02



GENERAL NOTES FOR FLAGGER OPERATIONS

1- REFER TO STD. 1101.11 SHEET 4 FOR SIGN SPACING.

2- INSTALL LANE CLOSURES WITH THE TRAFFIC FLOW, BEGINNING WITH DEVICES ON THE UPSTREAM SIDE OF TRAFFIC.

3- REMOVE LANE CLOSURES AGAINST THE TRAFFIC FLOW, BEGINNING WITH DEVICES ON THE DOWNSTREAM SIDE OF TRAFFIC.

4- PLACE CONES THRU THE WORK AREA AT THE MAXIMUM SPACING EQUAL IN FEET TO 2 TIMES THE POSTED SPEED LIMIT.

5- EXTEND LANE CLOSURES AT THE BUFFER SPACE SUCH THAT STOPPING SIGHT DISTANCE IS PROVIDED TO THE FLAGGER (REFER TO STD. 1101.11 SHEET 2).

6- DO NOT STOP TRAFFIC IN ANY ONE DIRECTION FOR MORE THAN 5 MINUTES AT A TIME.

7- DRUMS OR SKINNY-DRUMS MAY BE USED IN LIEU OF CONES. REFER TO ROADWAY STANDARD DRAWING 1180.01 FOR SKINNY-DRUM REQUIREMENTS.

8- USE FLAGGERS TO CONTROL TRAFFIC AT INTERSECTIONS AFFECTED BY THE LANE CLOSURE. SUPPLEMENT FLAGGERS LOCATED AT INTERSECTIONS WITH FLAGGER AHEAD SIGNS (W20-7a) PLACED APPROXIMATELY 250 FT. IN ADVANCE OF THE FLAGGER. FOR SIGNALIZED INTERSECTIONS PLACE SIGNALS IN THE FLASH MODE AND RECOMMEND THE USE OF LAW ENFORCEMENT.

9- REFER TO 2009 MUTCD, CHAPTER 6, FOR FLAGGER CONTROL, REQUIREMENTS, AND PROCEDURES.

10- DO NOT EXCEED A 1 MILE LANE CLOSURE LENGTH UNLESS OTHERWISE SHOWN IN THE TMP OR AS DIRECTED BY THE ENGINEER.

GENERAL NOTES FOR PILOT CAR OPERATIONS

1- USE PILOT CARS WHEN DIRECTED BY THE ENGINEER.

2- IF ROADWAY WIDTH IS LESS THAN 22 FEET (EOP TO EOP), CONES MAY NOT BE REQUIRED ALONG WORK AREA, AND AT THE DISCRETION OF THE ENGINEER, CONES MAY BE OMITTED ALONG THE WORK AREA IF USING A PILOT CAR.


3- CONES ARE ALWAYS REQUIRED IN THE UPSTREAM AND DOWNSTREAM TAPERS.


4- MOUNT SIGN W20-4 "PILOT CAR FOLLOW ME" AT A CONSPICUOUS POSITION ON THE REAR OF THE PILOT VEHICLE.


5- DO NOT INSTALL MORE THAN ONE (1) MILE OF LANE CLOSURE, MEASURED FROM THE BEGINNING OF THE MERGE TAPER TO THE END OF THE LANE CLOSURE.


6- ADVISE RESIDENTS AND BUSINESSES WITHIN THE LANE CLOSURE LIMITS ABOUT METHODS OF SAFE EGRESS AND INGRESS FROM DRIVEWAYS DURING FLAGGING AND PILOT CAR OPERATIONS.

LEGEND

 FLAGGER

 CONE

 PORTABLE SIGN

 DIRECTION OF TRAFFIC FLOW

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
HALEIGH, N.C.

1-12

TEMPORARY LANE CLOSURES
2-LANE, 2-WAY ROADWAY-1 LANE CLOSED

ENGLISH STANDARD DRAWING FOR

SHEET 1 OF 15
1101.02