


TREE OR SHRUB PLANTING DETAIL

NOT TO SCALE




GROUNDCOVER OR PERENNIAL PLANTING DETAIL

NOT TO SCALE


SCARIFY TO A MINIMUM DEPTH OF

5" OR 2" DEEPER THAN CONTAINER




SHRUB BED PLANTING DETAIL

NOT TO SCALE



TREE STAKING DETAIL
FOR TREES 6'-10'
NOT TO SCALE



TREE GUYING DETAIL
FOR TREES 10' OR LARGER
NOT TO SCALE

NOT TO SCALE

NOTES:

- 1. PLANTS SHOULD BE PLANTED IN THEIR PERMANENT LOCATION IMMEDIATELY UPON DELIVERY OR SHOULD BE ADEQUATELY PROTECTED UNTIL PLANTED.
- 2. SOIL AROUND THE PLANT SHOULD BE TAMPED TO REMOVE AIR POCKETS, 3. PROVIDE MINIMUM 3" MULCH AROUND ALL PLANTINGS.
- 4. MULCH SHOULD NOT CONTAIN SUBSTANCES WHICH WOULD INHIBIT NORMAL DEVELOPMENT AND GROWTH OF PLANTS.
- 5. TREES WHICH HAVE HEAVY TOPS OR WHICH ARE OVER SIX FEET IN HEIGHT MUST BE STAKED, GUYED, OR ANCHORED TO PREVENT WINDS FROM LOOSENING THE ROOTS.
- 6. ALL PLANT ROOTS SHOULD BE SOAKED THOROUGHLY WITH WATER AT PLANTING TIME AND ONCE PER WEEK DURING THE FIRST GROWING SEASON (UNLESS SOAKING RAIN OCCURS.)
- 7. PRUNE AND REMOVE BROKEN OR DEAD LIMBS/BRANCHES FROM TREES AND SHRUBS AFTER PLANTING. RETAIN NATURAL SHAPE OF PLANT.
- 8. THE CENTRAL LEADER OF TREES SHALL NOT BE REMOVED. (SEE DETAIL.)

