



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

October 8th, 2020

To: Prospective Bidders

From: Jonathan W. Mitchell
Division Contracts and Proposals Engineer

DocuSigned by:
Jonathan W Mitchell
02B404268BC84C2...

Contract ID#: DC00278
WBS Element: 46305.3.65
FA #: STP-0337(002)
TIP #: ER-5600

Subject: Addendum #1: ROUNDABOUT LANDSCAPE ENHANCEMENT

The subject contract proposal contains the following addendum:

- 1- The landscaping plan set has been revised. The old plan set has been removed from the NCDOT Letting Website and the new plan set has been added.
- 2- This project has Federal funding therefore Federal regulations will apply such as certified payroll, wage rate interviews, etc. Certified payroll will be required even if no work is performed on the project.
- 3- For the line item Incidental Concrete Construction reference plan sheet L3 of the revised plan set.
- 4- Catch basins are located in the curb line. Erosion Control will be incidental to other contract line items.
- 5- Plant Bed Certification - Type 6, NCDA Nursery Certification is required for the contractor.
- 6- Geotextile Fabric is incidental to the decorative concrete pavers line item. Please reference the revised plan set sheet L3.
- 7- Replace page 21 of the proposal with the attached. The Contractor's License Requirements SP has been revised.
- 8- Contractor must contact Mr. Justin Whiteside, (910) 579-2864 with Town of Ocean Isle Beach to coordinate parking and storing of materials.

*****An Addendum has been added to Bid Express.**

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
5501 BARBADOS BOULEVARD
CASTLE HAYNE, NC 28429-5647

Telephone: (910) 341-2000
Fax: (910) 675-0143
Customer Service: 1-877-368-4968

Website: www.ncdot.gov

Location:
5501 BARBADOS BOULEVARD
CASTLE HAYNE, NC 28429-5647

PROJECT SPECIAL PROVISIONS

ROADWAY

NOTES TO CONTRACTOR

- The Contractor must cooperate with State forces working within the limits of this project as directed by the Engineer. The Department reserves the right to make, at any time during the progress of the work, such alterations in plans or the details of construction as may be found necessary or desirable by the Engineer to complete the project. The Contractor shall maintain access to driveways for all residents and property owners throughout the life of the project. The Contractor shall be responsible for maintaining the project as directed by Section 104-10 in the *2018 Standard Specifications*.
- Town of Ocean Isle Beach will be responsible for the irrigation. Coordination and scheduling with the town will be crucial so there are no conflicting operations during construction.
- Contractor shall supply references and samples to the Engineer prior to construction as referenced on page 31 of this proposal.
- Incidental concrete construction shall be installed according to the guidance in the plan set.
- Upon award contractor will be required to supply a project schedule of construction, as well as a list of sub-contractors and product suppliers to be used, and references and samples of work supplied for retaining wall upon award.
- All exposed (above ground) stone wall sides shall be textured.
- The licensed electrician is needed to pull service and establish the GFCI outlets necessary for the low voltage lights. The landscape contractor can do all associated work for the setting up of the low voltage lights (and make the connections). The contractor may also set/anchor the transformer and plug it in, if it is a plug-in transformer. Any direct powered (110/220) lights can be set by the contractor but connections must be made by a licensed electrician.

CONTRACTOR'S LICENSE REQUIREMENTS

A current North Carolina Landscape Contractor's License is required. A copy of the License shall be given to the Engineer prior to the beginning work. The successful bidder has fourteen (14) business days after notice of award of the contract, to provide the North Carolina Department of Transportation with a copy of the Landscaper Contractor's License **If these terms are not met within the allotted amount of time of fourteen (14) business days, the North Carolina Department of Transportation will have the right to reject the bid and select the next lowest responsible bidder or cancellation of this contact.**

EROSION CONTROL

The Contractor shall install erosion control measures as needed and as directed by the Engineer prior to any soil disturbance operation, including vegetation removal, plant bed preparation, ditch renovation and seeding and mulching, and maintain as needed for the life of the project. Failure on the part of the Contractor to perform the required erosion control measures shall be cause for the immediate suspension of work. All erosion control for this project shall be considered incidental and there will be no separate payment.

VEGETATION REMOVAL

The removal of existing vegetation within a proposed new or renovated plant bed or seedbed shall be part of the plant bed or seed bed preparation and there will be no separate payment for this work.