



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

J. ERIC BOYETTE  
SECRETARY

October 14, 2021

**To: Prospective Bidders**

**From: Jonathan W. Mitchell**  
**Division Contract Engineer**

DocuSigned by:  
*Jonathan W Mitchell*  
02B404268BC84C2...

**Contract ID: DC00316**  
**WBS#: 50138.3.113**  
**F.A. #: HSIP-0017(54)**  
**TIP#: W-5601DH**  
**COUNTY: NEW HANOVER**

**Subject: Addendum #2: W-5601DH Third & Dock Street Re-let**

The Subject contract proposal contains the following addendum:

1. A line item has been added for *Remove, Stockpile, and Replace Historic Marker* per Each. See the attached SP and revised Bid From.

**\*\*\*An Addendum has been added to Bid Express.**

*Mailing Address:*  
NC DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS  
5505 BARBADOS BOULEVARD  
CASTLE HAYNE, NC 28429-5647

*Telephone:* (910) 341-2001  
*Fax:* (910) 675-0143  
*Customer Service:* 1-877-368-4968

*Website:* [www.ncdot.gov](http://www.ncdot.gov)

*Location:*  
5505 BARBADOS BOULEVARD  
CASTLE HAYNE, NC 28429-5647

**REMOVE, STOCKPILE, AND REPLACE HISTORIC MARKER:**

**Description**

Before stockpiling, remove historic marker from support. The Department maintains ownership of all materials to be stockpiled. Transport and stockpile designated items to locations approved by the Engineer. Sort and stockpile all materials neatly in stacks or storage bins. Repair or replace materials damaged in removal or while in storage. Place historic marker back on its original support once construction is complete and approved by the Engineer. Repair or replace support if damaged during construction.

**Measurement and Payment**

*Remove, Stockpile, and Replace Historic Marker* will be measured and paid as the actual number of components acceptably removed, stockpiled, and replaced. Removal is incidental to stockpiling. Repair or replacement of any materials or areas within the project limits disturbed or damaged in performance of the work required under this section will be at no cost to the Department.

Payment will be made under:

**Pay Item**

Remove, Stockpile, and Replace Historic Marker

**Pay Unit**

Each

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000900000-N	SP	GENERIC MISCELLANEOUS ITEM PLANTING SOIL	Lump Sum	L.S.	
0004	0000920000-E	SP	GENERIC MISCELLANEOUS ITEM SETTING SAND FOR PAVERS	2.3 CY		
0005	0000960000-E	SP	GENERIC MISCELLANEOUS ITEM BRICK PAVERS FOR CURB RAMP LANDING AREAS	80 SY		
0006	0000960000-E	SP	GENERIC MISCELLANEOUS ITEM GEOTEXTILE FABRIC FOR PAVERS	80 SY		
0007	0000960000-E	SP	GENERIC MISCELLANEOUS ITEM StreetPrint XD CROSSWALKS (ASPHALT SURFACE)	130 SY		
0008	0000995000-E	SP	GENERIC MISCELLANEOUS ITEM AGGREGATE BASE COURSE FOR PAVE RS	20 TON		
0009	0043000000-N	226	GRADING	Lump Sum	L.S.	
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	10 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	30 SY		
0012	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (12")	12 LF		
0013	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	8 LF		
0014	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	40 LF		
0015	0986000000-E	SP	GENERIC PIPE ITEM 18" CIPP	75 LF		
0016	0995000000-E	340	PIPE REMOVAL	13 LF		
0017	1121000000-E	520	AGGREGATE BASE COURSE	43 TON		

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1.5")	2,730 SY		
0019	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	40 TON		
0020	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	20 TON		
0021	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	260 TON		
0022	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	20 TON		
0023	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	6 EA		
0024	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (TYPE E)	4 EA		
0025	2396000000-N	840	FRAME WITH COVER, STD 840.54	6 EA		
0026	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	380 LF		
0027	2591000000-E	848	4" CONCRETE SIDEWALK	10 SY		
0028	2605000000-N	848	CONCRETE CURB RAMPS	8 EA		
0029	2752000000-E	SP	GENERIC PAVING ITEM (GRANITE CURB)	325 LF		
0030	2830000000-N	858	ADJUSTMENT OF MANHOLES	2 EA		
0031	2893000000-N	859	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX WITH MANHOLE	2 EA		
0032	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	95 SY		
0033	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	121 LF		
0034	4102000000-N	904	SIGN ERECTION, TYPE E	10 EA		
0035	4108000000-N	904	SIGN ERECTION, TYPE F	2 EA		

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	5 EA		
0037	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	128 SF		
0038	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192 SF		
0039	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	64 SF		
0040	4415000000-N	1115	FLASHING ARROW BOARD	2 EA		
0041	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2 EA		
0042	4435000000-N	1135	CONES	100 EA		
0043	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0044	4455000000-N	1150	FLAGGER	120 DAY		
0045	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,329 LF		
0046	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	425 LF		
0047	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	19 EA		
0048	4891000000-E	1205	GENERIC PAVEMENT MARKING ITEM (24" 90 MILS)	22 LF		
0049	4895000000-N	SP	GENERIC PAVEMENT MARKING ITEM NON CAST IRON SNOWPLOWABLE PAVEMENT MARKER	25 EA		
0050	6000000000-E	1605	TEMPORARY SILT FENCE	100 LF		
0051	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	35 TON		
0052	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	5 TON		
0053	6012000000-E	1610	SEDIMENT CONTROL STONE	40 TON		

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6015000000-E	1615	TEMPORARY MULCHING	0.25	ACR	
0055	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0056	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0057	6029000000-E	SP	SAFETY FENCE	100	LF	
0058	6030000000-E	1630	SILT EXCAVATION	5	CY	
0059	6036000000-E	1631	MATTING FOR EROSION CONTROL	100	SY	
0060	6042000000-E	1632	1/4" HARDWARE CLOTH	200	LF	
0061	6084000000-E	1660	SEEDING & MULCHING	0.25	ACR	
0062	6087000000-E	1660	MOWING	0.1	ACR	
0063	6090000000-E	1661	SEED FOR REPAIR SEEDING	25	LB	
0064	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.1	TON	
0065	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	25	LB	
0066	6102000000-E	1664	SODDING GRASS SOD FOR MEDIAN	210	SY	
0067	6108000000-E	1665	FERTILIZER TOPDRESSING	0.1	TON	
0068	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
0069	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13	EA	
0070	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	1	EA	
0071	6132000000-N	SP	GENERIC EROSION CONTROL ITEM FABRIC INSERT INLET PROTECTION DEVICE	9	EA	
0072	6132000000-N	SP	GENERIC EROSION CONTROL ITEM FABRIC INSERT INLET PROTECTION DEVICE CLEANOUT	9	EA	

County : New Hanover

---

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	4360000000-N	SP	GENERIC SIGNING ITEM REMOVE, STOCKPILE, AND REPLACE HISTORIC MARKER	2 EA		

---

---

1306/Oct14/Q8025.35/D259014695000/E73

Total Amount Of Bid For Entire Project :

---