EFF. 01-17-2012
REV. 10-30-2012

2012 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated January, 2012 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO.	TITLE
DIVISION 11 - TRAFFIC CONTROL	
1101.01	Work Zone Advance Warning Signs for High Speed Facilities ≤ 55 MPH
1101.02	Temporary Lane Closures
1101.04	Temporary Shoulder closures
1101.11	Traffic Control Design Tables
1110.01	Stationary Work Zone Signs
1110.02	Portable Work Zone Signs
1130.01	Drum
1135.01	Cones
1165.01	Work Vehicle Lighting Systems and TMA Delineation
1180.01	Skinny Drums

GENERAL NOTES:

2012 SPECIFICATIONS
EFFECTIVE: 01-17-2012
REVISED: 07-30-2012

GRADING AND SURFACING OR RESURFACING AND WIDENING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. WHERE NO GRADE LINES ARE SHOWN, THE PROFILES SHOWN DENOTE THE TOP ELEVATION OF THE EXISTING PAVEMENT ALONG THE CENTER LINE OF SURVEY ON WHICH THE PROPOSED RESURFACING WILL BE PLACED. GRADE LINES MAY BE ADJUSTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

UTILITIES:

UTILITY OWNERS ON THIS PROJECT ARE:
POWER- DUKE ENERGY PROGRESS- SHEILA TALTON- 919.431.4722
PHONE- AT&T- CHRIS BENTZ- 910.619.5500
CABLE- TIME WARNER CABLE- ROBERT JOHN- 910.619.0192
WATER AND SEWAGE- CAPE FEAR PUBLIC UTILITY AUTHORITY- JIM TAYSON- 910.332.6738
GAS- PIEDMONT NATURAL GAS- ROSS WILCOX- 910.251.2808

ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS.

SUBSURFACE PLANS:

NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.

INDEX OF SHEETS

SHEET NUMBER	SHEET
1	TITLE SHEET AND ALIGNMENT
1-A	INDEX OF SHEETS, GENERAL NOTES AND LIST OF STANDARD DRAWINGS
1-B	CONVENTIONAL SYMBOLS
2A-1	PAVEMENT SCHEDULE, TYPICAL SECTIONS
2B-1	PATCHING DETAIL
2C-1 THRU 2C-3	ROADWAY DETAILS
2D-1 THRU 2D-2	SPECIAL DETAILS
PMP-1 THRU PMP-2	PAVEMENT MARKING & SIGNING PLANS
SIG.1.0 THRU SIG.1.2	SIGNAL PLANS

NORTH CAROLINA PROFESSIONAL SEAL 037439 ENGINEER DAVID B. LEONARD

David Leonard
DIVISION DESIGN ENGINEER
9/17/2015 | 10:36 AM PT

8/17/99
15-SEP-2015 12:00
S:\TPD\PROJECTS\W-52030_45333_FS15_IHB_PSH_1A.dgn
$$$$USERNAME$$$$
NEW HANOVER\Isabel Holmes Bridge Restriping on West Side of Bridge\ROADWAY\Proj\Plan_Sheets\W-52030_45333_FS15_IHB_PSH_1A.dgn