LOCATION SKETCH

INFORMATION ON THE LOCATION SKETCH SHALL BE CONSIDERED GENERAL INFORMATION ONLY.

NOTES:

EXISTING DIMENSIONS AND BRIDGE CONDITION ARE FROM BEST INFORMATION AVAILABLE. THE CONTRACTOR SHALL FIELD VERIFY THE INFORMATION SHOWN ON THE PLANS AND NOTIFY THE ENGINEER IF ACTUAL DIMENSIONS AND CONDITIONS DIFFER.

IT IS THE CONTRACTOR'S RESPONSIBILITY TO FOLLOW ALL STATE AND FEDERAL SAFETY REQUIREMENTS.

FOR UNDER STRUCTURE WORK PLATFORM, SEE SPECIAL PROVISIONS.

FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.

FOR MAINTENANCE OF WATER TRAFFIC, SEE SPECIAL PROVISIONS.

FOR WORK IN, OVER OR ADJACENT TO NAVIGABLE WATERS, SEE SPECIAL PROVISIONS.

FOR SECURING VESSELS, SEE SPECIAL PROVISIONS.

FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.

FOR COAST GUARD COORDINATION, SEE SPECIAL PROVISIONS.

FOR PARTIAL REPLACEMENT OF STEEL GRID DECK, SEE SPECIAL PROVISIONS.

FOR CONTROL OF TRAFFIC AND LIMITS OF PHASING OF CONSTRUCTION, SEE TRANSPORTATION MANAGEMENT PLANS.

ACCESS TO OPERATOR'S HOUSE SHALL BE MAINTAINED AT ALL TIMES DURING CONSTRUCTION.

WORK ON BRIDGE SHALL BE PERFORMED SO AS NOT TO ALLOW DEBRIS TO FALL BELOW. THE CONTRACTOR SHALL SUBMIT PLANS FOR CONSTRUCTION IN ACCORDANCE TO ARTICLE 402-2 OF THE STANDARD SPECIFICATIONS AND THE PROJECT SPECIAL PROVISIONS.

PRIOR TO BEGINNING WORK, CONTRACTOR SHALL SUBMIT FOR REVIEW AND APPROVAL A COMPLETE SEQUENCE OF TASKS FOR EACH OPERATION AFFECTING THE BRIDGE SURFACE AND/OR TRAFFIC.

ANY DAMAGE TO THE EXISTING STRUCTURE DURING CONTRACTOR'S OPERATIONS, SHALL BE REPAIRED AS DIRECTED BY THE ENGINEER AND PERFORMED AT NO ADDITIONAL COST TO NCDOT.

TOTAL BILL OF MATERIAL

	PARTIAL REPLACEMENT OF STEEL GRID DECK	UNDER STRUCTURE WORK PLATFORM
	LUMP SUM	LUMP SUM
TOTAL	LUMP SUM	LUMP SUM

PROJECT NO. W-5601CK

NEW HANOVER COUNTY

STATION:

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

GENERAL NOTES AND TOTAL BILL OF MATERIAL

MODJESKI and MASTERS
Experience great bridges.

333 FAYETTEVILLE STREET, SUITE 505
RALEIGH, NC 27601
NC LICENSE NO. C-2979

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

NORTH CAROLINA PROFESSIONAL SEAL 032967 ENGINEER JASON R. DOUGHTY

10/17/2018

DocuSigned by: Jason R Doughty
SF73FA2DEA974E8...

DESIGNED BY:	J. BORUTA	DATE :	JUNE 2018
DRAWN BY:	K. WHITE	DATE :	JUNE 2018
CHECKED BY:	J. DOUGHTY	DATE :	JUNE 2018
DESIGN ENGINEER OF RECORD:	J. DOUGHTY	DATE :	JUNE 2018

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-4
1			3			TOTAL SHEETS
2			4			8

10/17/2018
400_007_W5601CK_SMU_GD4_640012.dgn