

**North Carolina Department of Transportation
Summary of Quantities**

WBS Number: 36059.23

Project Description: Landscape renovation of the I-40 Duplin County Rest Area in Warsaw, NC.

ITEM	DESC. NO	SECT	DESCRIPTION	QTY	UNIT
1	6645000000-N	SP	'CRIMSON QUEEN' JAPANESE MAPLE 3-4', #10 cont.	2	EA
2	6645000000-N	1670	MONTANA HOSTA 3 eye, #1 cont.	11	EA
3	6645000000-N	1670	'BOTTSTEIN HYDRANGEA 15-18"', #3	11	EA
4	6645000000-N	1670	'BLUE MAMMOTH' HOSTA 3 eye, #1	13	EA
5	6645000000-N	1670	HAPPY RETURNS DAYLILY #1 cont.	1827	EA
6	6645000000-N	1670	HENRY'S GARNET SWEETSPIRE 18-24"', #3 cont.	14	EA
7	6645000000-N	1670	LITTLE HENRY'S DWARF SWEETSPIRE 18-24"', #3 cont.	20	EA
8	6645000000-N	1670	PURPLE PIXIE FRINGE FLOWER 18-24"', #3 cont.	10	EA
9	6645000000-N	1670	VARIEGATED LIRIOPE #1 cot.	124	EA
10	6645000000-N	1670	DWARF FOUNTAIN GRASS #1 cont.	98	EA
11	6645000000-N	1670	LITTLE BUNNY DWARF FOUNTAIN GRASS #1 cont.	326	EA
12	6645000000-N	1670	ELEANOR TABER HAWTHORN 18-24"', #3 cont.	7	EA
13	6645000000-N	1670	KNOCKOUT ROSE (RED) 18-24"', #3 cont.	82	EA
14	6645000000-N	1670	AUTUMN JOY STONECROP #1 cont.	85	EA
15	6645000000-N	1670	RHEINGOLD ARBORVITAE 15"', #10 cont.	6	EA
16	6645000000-N	1670	WINE & ROSES WEIGELA 15-18"', #5 cont.	5	EA
17	6655000000-N	SP	WATER FOR PLANTING	50	M/G
18	6650000000-N	SP	MULCH FOR PLANTING	168	CY
19	6640000000-N	1670	EXISTING PLANT BED CLEAN-UP	1216	SY
20	2591000000-E	848	4" CONCRETE SIDEWALK	21	SY
21	6640000000-N	1670	COMMERCIAL GRADE STEEL LANDSCAPE METAL EDGING 4" WIDE, 12 GA, BROWN POWDER COAT FINISH	1494	LF
22	6640000000-N	1670	TOPSOIL - 2.5" DEPTH	74	CY
23	6640000000-N	1670	WASHED RIVER ROCK (2-3" DIA.) - 3" DEPTH	4	CY
24	6640000000-N	1670	WHITE PEBBLES (1-2" DIA.)- 3" DEPTH	2	CY
25	6640000000-N	1670	GEOTEXTILE FABRIC	35	SY