

PROJECT 17BP.3.R.18	FEDERAL PROJECT NUMBER 17BP.3.R.18	FED ITEM	CONT SEC	WORK TYPE RURAL/GRAD'G & DRAINAGE STRUC & SURF PRO	LOCATION SR 1554 ZONE:           ROUTE:
------------------------	---------------------------------------	----------	----------	---	---

BREAKDOWN ID 0001

WORK ITEM DESCRIPTION	CATG	SEQUENCE	ITEM	QUANTITY	UNIT
MOBILIZATION	0001	0001	0000100000-N	1.00	LS
CONSTRUCTION SURVEYING	0001	0002	0000400000-N	1.00	LS
REINFORCED BRIDGE APPROACH    FILL, STATION ***** -L- STA 16+40	0001	0003	0029000000-N	1.00	LS
REINFORCED BRIDGE APPROACH    FILL, STATION ***** -L- STA 20+47	0001	0004	0029000000-N	1.00	LS
UNDERCUT EXCAVATION	0001	0005	0036000000-E	5,500.00	CY
GRADING	0001	0006	0043000000-N	1.00	LS
SELECT GRANULAR MATERIAL,        CLASS III	0001	0007	0194000000-E	4,000.00	CY
SELECT GRANULAR MATERIAL	0001	0008	0195000000-E	2,000.00	CY
GEOTEXTILE FOR SOIL STABILIZA-TION	0001	0009	0196000000-E	2,330.00	SY
FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	0001	0010	0318000000-E	80.00	TON
FOUNDATION CONDITIONING GEO- TEXTILE	0001	0011	0320000000-E	240.00	SY
15" SIDE DRAIN PIPE	0001	0012	0343000000-E	16.00	LF
18" SIDE DRAIN PIPE	0001	0013	0344000000-E	435.00	LF
24" SIDE DRAIN PIPE	0001	0014	0345000000-E	40.00	LF
18" RC PIPE CULVERTS, CLASS IV	0001	0015	0448300000-E	88.00	LF
24" RC PIPE CULVERTS, CLASS IV	0001	0016	0448400000-E	140.00	LF
SHALLOW UNDERCUT	0001	0017	1099500000-E	1,000.00	CY
CLASS IV SUBGRADE STABILIZA- TION	0001	0018	1099700000-E	190.00	TON
AGGREGATE BASE COURSE	0001	0019	1121000000-E	600.00	TON
ASPHALT CONC BASE COURSE, TYPE B25.0B	0001	0020	1489000000-E	1,070.00	TON
ASPHALT CONC SURFACE COURSE,    TYPE SF9.5A	0001	0021	1525000000-E	690.00	TON
ASPHALT BINDER FOR PLANT MIX	0001	0022	1575000000-E	91.00	TON
RIGHT OF WAY MARKERS	0001	0023	2000000000-N	35.00	EA
SUBDRAIN EXCAVATION	0001	0024	2022000000-E	112.00	CY
SUBDRAIN COARSE AGGREGATE	0001	0025	2036000000-E	84.00	CY
6" PERFORATED SUBDRAIN PIPE	0001	0026	2044000000-E	500.00	LF
SUBDRAIN PIPE OUTLET	0001	0027	2070000000-N	1.00	EA
6" OUTLET PIPE	0001	0028	2077000000-E	6.00	LF
MASONRY DRAINAGE STRUCTURES	0001	0029	2286000000-N	6.00	EA
FRAME WITH TWO GRATES, STD       840.16	0001	0030	2364000000-N	3.00	EA

PROJECT 17BP.3.R.18	FEDERAL PROJECT NUMBER 17BP.3.R.18	FED ITEM	CONT SEC	WORK TYPE RURAL/GRAD'G & DRAINAGE STRUC & SURF PRO	LOCATION SR 1554 ZONE:           ROUTE:
------------------------	---------------------------------------	----------	----------	---	---

BREAKDOWN ID 0001

WORK ITEM DESCRIPTION	CATG	SEQUENCE	ITEM	QUANTITY	UNIT
FRAME WITH TWO GRATES, STD      840.29	0001	0031	2367000000-N	3.00	EA
SHOULDER BERM GUTTER	0001	0032	2556000000-E	150.00	LF
GENERIC GUARDRAIL ITEM Weathering ST BM Grd rail w/ Painted Laps	0001	0033	3420000000-E	600.00	LF
GENERIC GUARDRAIL ITEM Weathering Additional Guardrail Post	0001	0034	3435000000-N	5.00	EA
GENERIC GUARDRAIL ITEM Weathering Grd rail Anchor Unit Type III	0001	0035	3435000000-N	8.00	EA
GENERIC GUARDRAIL ITEM Weathering GRAU 350	0001	0036	3435000000-N	4.00	EA
RIP RAP, CLASS II	0001	0037	3635000000-E	90.00	TON
RIP RAP, CLASS B	0001	0038	3649000000-E	24.00	TON
GEOTEXTILE FOR DRAINAGE	0001	0039	3656000000-E	170.00	SY
WORK ZONE SIGNS (STATIONARY)	0001	0040	4400000000-E	406.00	SF
WORK ZONE SIGNS (PORTABLE)	0001	0041	4405000000-E	224.00	SF
WORK ZONE SIGNS (BARRICADE      MOUNTED)	0001	0042	4410000000-E	94.00	SF
DRUMS	0001	0043	4430000000-N	20.00	EA
CONES	0001	0044	4435000000-N	20.00	EA
BARRICADES (TYPE III)	0001	0045	4445000000-E	80.00	LF
FLAGGER	0001	0046	4455000000-N	10.00	DAY
PAINT PAVEMENT MARKING LINES    (4")	0001	0047	4810000000-E	11,000.00	LF
6" WATER LINE	0001	0048	5325600000-E	451.00	LF
8" WATER LINE	0001	0049	5325800000-E	938.00	LF
6" VALVE	0001	0050	5540000000-E	2.00	EA
RELOCATE WATER METER	0001	0051	5648000000-N	6.00	EA
RECONNECT WATER METER	0001	0052	5649000000-N	1.00	EA
ABANDON 6" UTILITY PIPE	0001	0053	5800000000-E	1,316.00	LF
TRENCHLESS INSTALLATION OF 8" IN SOIL	0001	0054	5871500000-E	469.00	LF
TRENCHLESS INSTALLATION OF 8" NOT IN SOIL	0001	0055	5871510000-E	469.00	LF
TEMPORARY SILT FENCE	0001	0056	6000000000-E	900.00	LF
STONE FOR EROSION CONTROL,      CLASS A	0001	0057	6006000000-E	45.00	TON
STONE FOR EROSION CONTROL,      CLASS B	0001	0058	6009000000-E	75.00	TON
SEDIMENT CONTROL STONE	0001	0059	6012000000-E	80.00	TON

PROJECT 17BP.3.R.18	FEDERAL PROJECT NUMBER 17BP.3.R.18	FED ITEM	CONT SEC	WORK TYPE RURAL/GRAD'G & DRAINAGE STRUC & SURF PRO	LOCATION SR 1554 ZONE:            ROUTE:
------------------------	---------------------------------------	----------	----------	---	--

BREAKDOWN ID 0001

WORK ITEM DESCRIPTION	CATG	SEQUENCE	ITEM	QUANTITY	UNIT
TEMPORARY MULCHING	0001	0060	6015000000-E	2.50	ACR
SEED FOR TEMPORARY SEEDING	0001	0061	6018000000-E	100.00	LB
FERTILIZER FOR TEMPORARY SEED-ING	0001	0062	6021000000-E	0.50	TON
SAFETY FENCE	0001	0063	6029000000-E	100.00	LF
SILT EXCAVATION	0001	0064	6030000000-E	40.00	CY
MATTING FOR EROSION CONTROL	0001	0065	6036000000-E	450.00	SY
1/4" HARDWARE CLOTH	0001	0066	6042000000-E	180.00	LF
FLOATING TURBIDITY CURTAIN	0001	0067	6048000000-E	135.00	SY
COIR FIBER WATTLE	0001	0068	6071012000-E	585.00	LF
POLYACRYLAMIDE (PAM)	0001	0069	6071020000-E	80.00	LB
COIR FIBER BAFFLE	0001	0070	6071030000-E	30.00	LF
SEEDING & MULCHING	0001	0071	6084000000-E	3.00	ACR
SEED FOR REPAIR SEEDING	0001	0072	6090000000-E	50.00	LB
FERTILIZER FOR REPAIR SEEDING	0001	0073	6093000000-E	0.25	TON
SEED FOR SUPPLEMENTAL SEEDING	0001	0074	6096000000-E	75.00	LB
FERTILIZER TOPDRESSING	0001	0075	6108000000-E	2.00	TON
RESPONSE FOR EROSION CONTROL	0001	0076	6117000000-N	25.00	EA
REMOVAL OF EXISTING STRUCTURE AT STATION ***** -L- sta 16+40	0001	0077	8035000000-N	1.00	LS
REMOVAL OF EXISTING STRUCTURE AT STATION ***** -L- sta 20+47.50	0001	0078	8035000000-N	1.00	LS
PDA TESTING	0001	0079	8112730000-N	2.00	EA
UNCLASSIFIED STRUCTURE EXCAVA-TION AT STATION ***** -L- sta 16+40	0001	0080	8121000000-N	1.00	LS
UNCLASSIFIED STRUCTURE EXCAVA-TION AT STATION ***** -L- sta 20+47.50	0001	0081	8121000000-N	1.00	LS
CLASS A CONCRETE (BRIDGE)	0001	0082	8182000000-E	96.00	CY
BRIDGE APPROACH SLABS, STATION***** -L- sta 16+40	0001	0083	8210000000-N	1.00	LS
BRIDGE APPROACH SLABS, STATION***** -L- sta 20+47.50	0001	0084	8210000000-N	1.00	LS
REINFORCING STEEL (BRIDGE)	0001	0085	8217000000-E	14,278.00	LB
HP12X53 STEEL PILES	0001	0086	8364000000-E	1,960.00	LF
HP14X73 STEEL PILES	0001	0087	8384000000-E	1,120.00	LF

PROJECT	FEDERAL PROJECT NUMBER	FED ITEM	CONT SEC	WORK TYPE	LOCATION
17BP.3.R.18	17BP.3.R.18			RURAL/GRAD'G & DRAINAGE STRUC & SURF PRO	SR 1554 ZONE:           ROUTE:

BREAKDOWN ID 0001

WORK ITEM DESCRIPTION	CATG	SEQUENCE	ITEM	QUANTITY	UNIT
PILE REDRIVES	0001	0088	8393000000-N	24.00	EA
TWO BAR METAL RAIL	0001	0089	8475000000-E	319.88	LF
1'-**"X *****" CONCRETE PARA- PET	0001	0090	8517000000-E	350.50	LF
1'-2"X1'-9" CONCRETE PARAPET					
RIP RAP CLASS II (2'-0" THICK)	0001	0091	8608000000-E	456.00	TON
GEOTEXTILE FOR DRAINAGE	0001	0092	8622000000-E	508.00	SY
ELASTOMERIC BEARINGS	0001	0093	8657000000-N	2.00	LS
3'-0" X 1'-9" PRESTRESSED CONCCORED SLABS	0001	0094	8762000000-E	1,155.00	LF
3'-0" X 2'-0" PRESTRESSED CONCCORED SLABS	0001	0095	8763000000-E	840.00	LF