

North Carolina Department of Transportation

BID FORM

WBS Element: 43812

**Project Description : Roundabout at the intersection of NC 179 Business and SR 1172
(Sunset Blvd.) in Sunset Beach, NC**

ITEM	DESC NO.	SEC T	DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT BID
1	0000100000-N	800	MOBILIZATION	1	LS		
2	0000400000-N	801	CONSTRUCTION SURVEYING	1	LS		
3	0043000000-N	226	GRADING	1	LS		
4	0318000000-E	300	FND CONDIT MATL MINOR STRS	60	TON		
5	0320000000-E	300	FND CONDIT GEOTEX	160	SY		
6	0342000000-E	310	30" SIDE DRN PIPE	28	LF		
7	0343000000-E	310	15" SIDE DRN PIPE	16	LF		
8	0344000000-E	310	18" SIDE DRN PIPE	16	LF		
9	0366000000-E	310	15" RC PIPE CULV III	340	LF		
10	0378000000-E	310	24" RC PIPE CULV III	48	LF		
11	0448200000-E	310	15" RCP CULV IV	100	LF		
12	0995000000-E	340	PIPE REMOVAL	8	LF		
13	1297000000-E	607	MILL ASP PVT 1.5" DTH	3010	SY		
14	1330000000-E	607	INCIDENTAL MILLING	240	SY		
15	1489000000-E	610	ASP CONC BASE CRS B25.0B	410	TON		
16	1498000000-E	610	ASP CONC INTR CRS I19.0B	400	TON		
17	1519000000-E	610	ASP CONC SURF CRS S9.5B	920	TON		
18	1575000000-E	620	ASP FOR PLANT MIX	100	TON		
19	2264000000-E	840	PIPE PLUGS	0.116	CY		
20	2286000000-N	840	MASNRY DRAINAGE STRUCT	14	EA		
21	2308000000-E	840	MASNRY DRAINAGE STRUCT	4.8	LF		
22	2364000000-N	840	FRM W/2GRTS 840.16 STD	1	EA		
23	2374000000-N	840	FRM-GRT-HD 840.03 TYPE 'E'	4	EA		
24	2374000000-N	840	FRM-GRT-HD 840.03 TYPE 'F'	6	EA		
25	2374000000-N	840	FRM-GRT-HD 840.03 TYPE 'G'	2	EA		
26	2535000000-E	846	9"-18" CONC CURB	290	LF		
27	2542000000-E	846	1'-6" CONC CURB & GUTTER	350	LF		
28	2549000000-E	846	2'-6" CONC CURB & GUTTER	1370	LF		
29	2591000000-E	848	4" CONC SIDEWALK	270	SY		

30	2605000000-N	848	CONC CURB RAMP	8	EA		
31	2647000000-E	852	5" MONO CONC ISLDS (SURF MTD)	260	SY		
32	2738000000-E	SP	GENERIC PAVNG ITEM - 10" CONC PAD	270	SY		
33	2738000000-E	SP	GENERIC PAVNG ITEM - DECORATIVE CROSSWALKS	230	SY		
34	2905000000-N	859	CONVERT DI TO JB	1	EA		
35	3649000000-E	876	RIP RAP, CLASS B	50	TON		
36	3656000000-E	876	GEOTEXTIL FOR DRN	115	SY		
37	4072000000-E	903	SUPPORT, 3-LB STL U-CHAN	590	LF		
38	4096000000-N	904	SIGN ERECTION, D	3	EA		
39	4102000000-N	904	SIGN ERECTION, E	22	EA		
40	4108000000-N	904	SIGN ERECTION, F	9	EA		
41	4116100000-N	904	SIGN ERECT, RELOC *D* GRD MTD	4	EA		
42	4116100000-N	904	SIGN ERECT, RELOC *E* GRD MTD	8	EA		
43	4155000000-N	907	DISPOSE SIGN SYST U-CHAN	12	EA		
44	4192000000-N	907	DISPOSE SUPPORT, U-CHAN	14	EA		
45	4238000000-N	907	DISPOS SIGN, D, E, F	8	EA		
46	4400000000-E	1110	WORK ZONE SIGNS (STAT)	128	SF		
47	4405000000-E	1110	WORK ZONE SIGNS (PORT)	388	SF		
48	4455000000-N	1150	FLAGGER	162	DAY		
49	4480000000-N	1165	TMA	1	EA		
50	4685000000-E	1205	THERMO PVT MKG LINES 4"90	4212	LF		
51	4686000000-E	1205	THERMO PVT MKG LINES 4"120	5575	LF		
52	4695000000-E	1205	THERMO PVT MKG LINES 8"90 MILS	330	LF		
53	4697000000-E	1205	THERMO PVT MKG LINE 8"120 MILS	288	LF		
54	4702000000-E	1205	12"WIDE THERMO 120 MILS	75	LF		
55	4725000000-E	1205	THERMO PVT SYMBOL 90MILS	12	EA		
56	4810000000-E	1205	PAINT PVT MKG 4"	41162	LF		
57	4815000000-E	1205	PAINT PVT MKG 6"	46	LF		
58	4825000000-E	1205	PAINT PVT MKG 12"	120	LF		
59	4835000000-E	1205	PAINT PVT MKG LINES 24"	120	LF		
60	4845000000-N	1205	PAINT PVT MKG SYM	24	EA		
61	4850000000-E	1205	LINE REM 4" WIDE	11913	LF		
62	4860000000-E	1205	LINE REM 8" WIDE	271	LF		
63	4870000000-E	1205	LINE REM 24" WIDE	12	LF		
64	4875000000-N	1205	REM OF SYMBL & CHARAC	8	EA		
65	4900000000-N	1251	PERM RAIS PVT MKR	61	EA		

66	6000000000-E	1605	TEMPORARY SILT FENCE	3170	LF		
67	6006000000-E	1610	EROS CONTRL STONE CL A	65	TON		
68	6009000000-E	1610	STONE FOR EROS CNTRL, B	20	TON		
69	6012000000-E	1610	SEDIMENT CONTROL STONE	110	TON		
70	6015000000-E	1615	TEMPORARY MULCHING	2.5	ACR		
71	6018000000-E	1620	SEED FOR TEMP SEEDING	100	LB		
72	6021000000-E	1620	FERT FOR TEMP SEEDING	0.5	TON		
73	6029000000-E	SP	SAFETY FENCE	400	LF		
74	6030000000-E	1630	SILT EXCAV	70	CY		
75	6042000000-E	1632	1/4" HARDWARE CLOTH	400	LF		
76	6071010000-E	SP	WATTLE	25	LF		
77	6071012000-E	SP	COIR FIBER WATTLE	75	LF		
78	6071020000-E	SP	POLYACRYLAMIDE (PAM)	5	LBS		
79	6084000000-E	1660	SEEDING AND MULCHING	3	ACR		
80	6087000000-E	1660	MOWING	3	ACR		
81	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB		
82	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON		
83	6096000000-E	1662	SEED FOR SUPP SEEDING	75	LB		
84	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75	TON		
85	6117000000-N	SP	RESPONSE FOR EROS CONTROL	13	EA		

TOTAL BID FOR PROJECT: _____

CONTRACTOR _____

ADDRESS _____

Federal Identification Number _____

Contractor's License Number _____

Authorized Agent _____

Title _____

Signature _____

Date _____

Witness _____ Title _____

Signature _____ Date _____



**THIS SECTION TO BE COMPLETED BY NORTH CAROLINA DEPARTMENT OF
TRANSPORTATION**

This bid has been reviewed in accordance with Article 103-1 of the Standard Specifications for Roads and Structures 2006.

Reviewed by _____

Date _____

Accepted by NCDOT _____