



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY
GOVERNOR

ANTHONY J. TATA
SECRETARY

January 22, 2015

Addendum No. 1

RE: **DD00137**
Halifax County

To Whom It May Concern:

Reference is made to the above-mentioned project. The following changes/additions/deletions have been made:

1. Project Special Provision ALUMINUM BOX CULVERT was replaced with ALUMINUM BOX CULVERT/ALUMINUM PIPE on Page 71. Replace Page 71 with the attached Page 71.
2. The description of Line Item 0037 was revised to show a 45' endwall instead of a 50' endwall. Replace ITEMIZED PROPOSAL SHEET FOR CONTRACT NO. DD00137 Page 3 of 3 (dated Dec 31, 2014) with the attached ITEMIZED PROPOSAL SHEET FOR CONTRACT NO. DD00137 Page 3 of 3 (dated Jan 21, 2015).
3. The EBS file was revised to show the change to Line Item 0037. Use the attached EBS file DD00137.EBS.

This sheet and attachments shall be made a part of the plans and bid documents and shall be submitted with the bid. Bids submitted without the addenda and attachments will be considered non-responsive.

If there are any questions, please contact me at (252) 237-6164

Respectfully,

J. Charles Cauley
Division Four Contracts and Proposals Engineer

JCC/
Attachment

Maintain the coir fiber wattle barriers until the project is accepted or until the coir fiber wattle barriers are removed, and remove and dispose of silt accumulations at the coir fiber wattle barriers when so directed in accordance with Section 1630 of the *2012 Standard Specifications*.

Measurement and Payment

Coir Fiber Wattle Barrier will be measured and paid as the actual number of linear feet of coir fiber wattle barrier installed and accepted. Such price and payment will be full compensation for all work covered by this provision, including, but not limited to, furnishing all materials, labor, equipment and incidentals necessary to install the coir fiber wattle barrier.

Payment will be made under:

Pay Item	Pay Unit
Coir Fiber Wattle Barrier	Linear Foot

PROJECT SPECIAL PROVISIONS **ALUMINUM BOX CULVERT/ALUMINUM PIPE**

Perform the required box culvert/aluminum pipe construction in accordance with this Special Provision.

The work covered by this special provision consists of furnishing all labor, equipment, materials and a manufacturer representative on site, to install the aluminum box culvert/aluminum pipe as indicated on the plans and Standard Specifications.

Design of the aluminum box culvert/aluminum pipe shall be the responsibility of the Contractor and shall comply with the latest AASHTO design specifications and requirements. The Contractor shall submit, fourteen (14) days prior to commencing work at each site, two sets of detailed plans and design calculations that have been checked and sealed by a North Carolina Registered Professional Engineer. The plans should be submitted to the Resident Engineer.

Payment will be made under:

Pay Item	Pay Unit
Aluminum Box Culvert Structure 21'-2" x 8'-10"	Each
Aluminum Pipe Structure 120"	Each

GENERAL ALUMINUM STRUCTURE REQUIREMENTS:

All items are incidental to Aluminum Box Culvert/Aluminum Pipe:

- All materials shall meet the requirements of the *2012 Standard Specifications*.
- Pipe material shall be made of aluminum alloy and in dimensions per the standard specifications and hydraulic recommendations.

County : Edgecombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	8804000000-N	SP	GENERIC CULVERT ITEM 120" ALUM. PIPE, 50' LONG, W/4 5' ENDWALL	Lump Sum	L.S.	
0038	8804000000-N	SP	GENERIC CULVERT ITEM 21'-2"X8'10" ALUM. BOX CULVERT , 50' LONG , W/45' ENDWALLS	Lump Sum	L.S.	
1537/Jan21/Q7168.7/D157550144000/E38						
				Total Amount Of Bid For Entire Project :		