



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

JAMES H. TROGDON, III  
SECRETARY

February 27, 2017

**Addendum No. 1**

RE: **DD00200**  
**Johnston County**  
**RESURFACING, MILLING AND WIDENING**

To Whom It May Concern:

Reference is made to the above-mentioned project. The following changes/additions/deletions have been made:

1. The Let Date for this project has been revised to March 7, 2017 to allow additional bidding time. All references in the Proposal to the Let Date of February 28, 2017 should be changed to March 7, 2017.
2. Replace Page 39 of the Proposal with the attached Page 39. This removes the Seeding and Mulching as an incidental item and makes Seeding and Mulching a separate Pay Item.
3. Replace the ITEMIZED PROPOSAL FOR CONTRACT NO. DD00200, Page 1 and 2 dated Feb 07, 2017 9:01 am with the attached ITEMIZED PROPOSAL FOR CONTRACT NO. DD00200, Page 1 and 2 dated Feb 27, 2017 4:16 pm. This adds Seeding and Mulching as a Pay Item.
4. Use the new DD00200.EBS file posted on the NCDOT bidding website under the March 7, 2017 letting and also on the Bid Express website under the March 7, 2017 letting.
5. Any bids already submitted for DD00200 for the February 28, 2017 letting will need to be resubmitted for DD00200 for the March 7, 2017 letting.

*Mailing Address:*  
NC DEPARTMENT OF TRANSPORTATION  
DIVISION FOUR OFFICE  
POST OFFICE BOX 3165  
WILSON, NC 27895

*Telephone:* (252) 237-6164  
*Fax:* (252) 234-6174  
*Customer Service:* 1-877-368-4968

*Website:* [www.ncdot.gov](http://www.ncdot.gov)

*Location:*  
509 WARD BOULEVARD  
WILSON, NC 27895

**This sheet and attachments shall be made a part of the plans and bid documents and shall be submitted with the bid. Bids submitted without the addenda and attachments will be considered non-responsive.**

If there are any questions, please contact me at (252) 237-6164

Sincerely,

DocuSigned by:  
  
BC8FE3BCFE014EA...  
2/27/2017

J. Charles Cauley  
Division Four Contracts and Proposals Engineer

JCC/  
Attachment

disposal site and for all labor, tools, equipment, and incidentals necessary to complete the work. Where ABC-M is used, seeding and mulching will not be required.

*Borrow Excavation* will be paid in accordance with Section 230 of the *2012 Standard Specifications* for earth material furnished by the Contractor. The requirements of Article 104-5 of the *2012 Standard Specifications* pertaining to revised contract prices for overrunning minor items will not apply to the item of *Borrow Excavation*.

*Aggregate Base Course Modified* will be paid for at the contract unit price per ton for the actual number of tons of aggregate which has been incorporated into the completed and accepted work. Sampling and acceptance will be determined in accordance with Section 1010.

The aggregate will be measured by being weighed in truck on certified platform scales or other certified weighing devices.

*Incidental Stone Base* will be measured and paid as provided in Article 545-6 of the *2012 Standard Specifications*. If ABC-M is used for Incidental Stone Base, payment will be made as referenced above.

Erosion control devices will be paid for as established elsewhere in the contract.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit</b>
Shoulder Reconstruction	Shoulder Mile
Borrow Excavation	Cubic Yard
Generic Paving Item - Aggregate Base Course Modified	Ton
Seeding and Mulching	Acre

### **SHOULDER RECONSTRUCTION PROCEDURE:**

(Rev. 2-7-17)

560

SP1 R10BR(rev)

Perform shoulder reconstruction immediately following paving operations and in no case allow paving operations to exceed shoulder operations by more than one week without written permission of the Engineer. Failure to meet this requirement shall be cause to cease paving operations until it can be met. Place final pavement marking after shoulder reconstruction.

Upon completion of shoulder reconstruction, remove construction signs and use on other projects or store at the county maintenance installation or as directed by the Engineer.

### **CONSTRUCTION SEQUENCE:**

(7-1-95) (Rev. 8-21-12)

560

SP1 R34R

Pave each section of roadway begun in a continuous operation. Do not begin work on another section of roadway unless satisfactory progress is being made toward completion of intersections and all other required incidental work by satisfactorily furnishing additional paving equipment and personnel, except for milling and patching operations.

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0003	1231000000-E	560	SHOULDER BORROW	1,163 CY		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	19.8 SMI		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH 1.5"	27,216 SY		
0006	1330000000-E	607	INCIDENTAL MILLING	2,271 SY		
0007	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	19,976 TON		
0008	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	2,144 TON		
0009	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	28,986 TON		
0010	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	3,269 TON		
0011	1880000000-E	SP	GENERIC PAVING ITEM AGGREGATE BASE COURSE MODIFIED	898 TON		
0012	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	5,032 SF		
0013	4415000000-N	1115	FLASHING ARROW BOARD	4 EA		
0014	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	4 EA		
0015	4430000000-N	1130	DRUMS	48 EA		
0016	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0017	4480000000-N	1165	TMA	2 EA		
0018	4516000000-N	1180	SKINNY DRUM	160 EA		
0019	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	172,375 LF		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	105,732	LF	
0021	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	21,656	LF	
0022	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,050	LF	
0023	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	130	LF	
0024	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	50	EA	
0025	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	171,864	LF	
0026	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	32,484	LF	
0027	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,050	LF	
0028	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	130	LF	
0029	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	44	EA	
0030	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	868	EA	
0031	6000000000-E	1605	TEMPORARY SILT FENCE	7,810	LF	
0032	6071012000-E	SP	COIR FIBER WATTLE	8,310	LF	
0033	6084000000-E	1660	SEEDING & MULCHING	7.5	ACR	
0034	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,980	LF	