



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

JAMES H. TROGDON, III
SECRETARY

March 7, 2017

Addendum No. 1

RE: **DD00204**
MILLING AND RESURFACING
US 70 FROM SR 1721 TO NC 111/US 117 BUS.
WAYNE COUNTY

To Whom It May Concern:

Reference is made to the above-mentioned project. The following changes/additions/deletions have been made:

1. Replace Page 69 with the attached Page 69. This will replace the incorrect Summary of Quantity sheet.
2. Change the quantity for Pay Item 0033 PAINT PAVEMENT PARKING SYMBOL to 119 EA as shown on the attached ITEMIZED PROPOSAL FOR CONTRACT NO. DD00204.
3. Add Pay Item 0037 THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS) as shown on the attached ITEMIZED PROPOSAL FOR CONTRACT NO. DD00204.
4. Replace the ITEMIZED PROPOSAL FOR CONTRACT NO. DD00204 dated Feb 17, 2017 with the attached ITEMIZED PROPOSAL FOR CONTRACT NO. DD00204 dated Mar 07, 2017.

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION FOUR OFFICE
POST OFFICE BOX 3165
WILSON, NC 27895

Telephone: (252) 237-6164
Fax: (252) 234-6174
Customer Service: 1-877-368-4968


Location:
509 WARD BOULEVARD
WILSON, NC 27895

Website: www.ncdot.gov

This sheet and attachments shall be made a part of the plans and bid documents and shall be submitted with the bid. Bids submitted without the addenda and attachments will be considered non-responsive.

If there are any questions, please contact me at (252) 237-6164

Sincerely,

DocuSigned by:

BC8FE3BCFE014EA...
3/7/2017

J. Charles Cauley
Division Four Contracts and Proposals Engineer

JCC/
Attachment

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO.	COUNTY MAP NO.	ROUTE	DESCRIPTION	TYP NO.	LANES	LANE TYPE	LENGTH	WIDTH	4895000000-E		4885000000-E		4695000000-E		4710000000-E		4725000000-E		4810000000-E		4820000000-E		4835000000-E		4845000000-N		4900000000-N						
									4" X 90 M YELLOW THERMO LF	4" X 90 M WHITE THERMO LF	4" X 120 M YELLOW THERMO LF	8" X 90 M WHITE THERMO LF	8" X 90 M YELLOW THERMO LF	24" X 120 M WHITE THERMO LF	THERMO STR ARROW/90 M EA	THERMO STR & RT ARROW/90 M EA	THERMO LT ARROW/90 M EA	4" WHITE PAINT LF	4" YELLOW PAINT LF	8" WHITE PAINT LF	8" YELLOW PAINT LF	24" WHITE PAINT LF	PAINT LT ARROW EA	PAINT STR & RT ARROW EA	PAINT STR ARROW EA	CRYSTAL & RED MARKERS EA	YELLOW & YELLOW MARKERS EA						
2017CPT 04.06.20961.1	Wayne	SR 1555 11TH ST.	FROM WAYNE MEMORIAL DR TO EXIST JOINT	3	2	ZWU	0.05	20																									
TOTAL FOR MAP NO. 20																																	
2017CPT 04.06.20961.1	Wayne	SR 1556 WAYNE MEMORIAL DR.	INTERSECTION SR 1555 SOUTH TO NINTH ST.	3	2	MU	0.31	26	1,600	1,600			500	770	24	8	5		1,600	1,600	500	770	24	24	2	2	5	8	50				
TOTAL FOR MAP NO. 21																																	
2017CPT 04.06.20961.1	Wayne	SR 1556 WAYNE MEMORIAL DR.	NINTH ST. TO INTERSECTION AT SR 1555	3	2	MD	0.31	26	3,000	1,600	416			372	73	8	8	11	1,600	3,416		372	73	11	8	8	8	41	30				
TOTAL FOR MAP NO. 22																																	
TOTAL FOR PROJ. NO. 2017CPT 04.06.20961.1																																	
GRAND TOTAL																																	
									4,600	3,200	416	500	1,642	1,142	97	16	13	11	4,256	10,328	6,072	500	1,642	1,142	145	13	15	16	91	121	30		
									7,800																								

PROJECT NO.	2017CPT 04.06.10961.1	SHEET NO.		TOTAL NO.	
	2017CPT 04.06.20961.1				

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH 1.5"	303,049 SY		
0003	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,080 TON		
0004	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	26,425 TON		
0005	1524200000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5D	450 TON		
0006	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	1,624 TON		
0007	1577000000-E	620	POLYMER MODIFIED ASPHALT BIN- DER FOR PLANT MIX	26 TON		
0008	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	400 SF		
0009	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	610 SF		
0010	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	32 SF		
0011	4415000000-N	1115	FLASHING ARROW BOARD	1 EA		
0012	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	1 EA		
0013	4422000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN (SHORT TERM)	60 DAY		
0014	4430000000-N	1130	DRUMS	340 EA		
0015	4435000000-N	1135	CONES	30 EA		
0016	4445000000-E	1145	BARRICADES (TYPE III)	32 LF		
0017	4455000000-N	1150	FLAGGER	40 DAY		
0018	4480000000-N	1165	TMA	2 EA		

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4510000000-N	SP	LAW ENFORCEMENT	320		HR
0020	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM SEQUENTIAL FLASHING WARNING LI GHTS	18		EA
0021	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM WORK ZONE PRESENCE LIGHTING	15		EA
0022	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	4,600		LF
0023	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	4,166		LF
0024	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	192,620		LF
0025	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	18,480		LF
0026	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	2,377		LF
0027	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	10,715		LF
0028	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	780		LF
0029	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	203		EA
0030	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	220,000		LF
0031	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	12,950		LF
0032	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	450		LF
0033	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	119		EA
0034	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	462		EA
0035	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,110		EA

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	9,250		
				LF		
0037	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	550		
				LF		

1748/Mar07/Q813388.0/D150277300000/E37

Total Amount Of Bid For Entire Project :
