


**This electronic collection of documents is provided
for the convenience of the user
and is Not a Certified Document –**

**The documents contained herein were originally issued
and sealed by the individuals whose names and license
numbers appear on each page, on the dates appearing
with their signature on that page.**

**This file or an individual page
shall not be considered a certified document.**

PROJECT: 17BP.4.R.65

CONTRACT:




STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

WAYNE COUNTY

**LOCATION: BRIDGE NO. 46 OVER NAHUNTA SWAMP
ON SR 1353 (HOOKS ROAD)**


TYPE OF WORK: GRADING, DRAINAGE, PAVING & STRUCTURE



STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	17BP.4.R.65	1	
STATE PROJ.NO.	F.A.PROJ.NO.	DESCRIPTION	
17BP.4.R.65		PE, UTIL., R/W CONST.	
		1223 Jones Franklin Rd. Raleigh, N.C. 27605 License No. F-0377 Bus.: 919 851 8077 Fax: 919 851 8107	
TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN			
CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION			

BRIDGE #950046

FINAL PLANS



DESIGN DATA

$$\text{ADT } 2015 = 680$$

T = 6 % *

V = 55 MPH

* (TTST = 3% + DUAL = 3%)

FUNC CLASS =

RURAL MAJOR COLLECTOR

REGIONAL TIER

PROJECT LENGTH

LENGTH ROADWAY PROJECT 17BP.4.R.65 =	0.078 MILES
LENGTH STRUCTURE PROJECT 17BP.4.R.65 =	0.015 MILES
TOTAL LENGTH PROJECT 17BP.4.R.65 =	0.093 MILES

NCDOT CONTACT: WADE A. HARPER
DIVISION 4 BRIDGE PROGRAM MANAGER

Prepared for:
DIVISION OF HIGHWAYS
DIVISION FOUR

509 Ward Boulevard, Wilson NC, 27895

2012 STANDARD SPECIFICATIONS

RIGHT OF WAY DATE: EDWARD G. WETHERILL, PE
PROJECT ENGINEER

LETTING DATE:


GREG S. PURVIS, PE
PROJECT DESIGN ENGINEER



HYDRAULICS ENGINEER

SIGNATURE:


P.E.



ROADWAY DESIGN ENGINEER

SIGNATURE

P.E.



8/17/99

GENERAL NOTES

GENERAL NOTES:

2012 SPECIFICATIONS

EFFECTIVE: 01-17-12
REVISED: 07-30-2012

GRADING AND SURFACING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. GRADE LINES MAY BE ADJUSTED AT THEIR BEGINNING AND ENDING AND AT STRUCTURES AS DIRECTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.

SUPERELEVATION:

ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

SHOULDER CONSTRUCTION:

ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01.

GUARDRAIL:

THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

END BENTS: THE SURVEYOR SHALL CHECK THE STRUCTURE END BENT PLANS, DETAILS, AND CROSS-SECTION PRIOR TO SETTING OF THE SLOPE STAKES FOR THE EMBANKMENT OR EXCAVATION APPROACHING A BRIDGE.

UTILITIES:

UTILITY OWNERS ON THIS PROJECT ARE CENTURYLINK (PHONE), WAYNE COUNTY (WATER), & TRI COUNTY ELECTRIC MEMBERSHIP CORP. (POWER). ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS

RIGHT OF WAY MARKERS:

ALL RIGHT OF WAY MARKERS ON THIS PROJECT SHALL BE PLACED BY CONTRACT.

LIST OF ROADWAY STANDARD DRAWINGS

2012 ROADWAY ENGLISH STANDARD DRAWINGS

EFF. 01-17-12
REV. 10-30-2012

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch – N. C. Department of Transportation – Raleigh, N. C., Dated January, 2012 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO.

TITLE

DIVISION 2 – EARTHWORK

200.02 Method of Clearing – Method II
225.02 Guide for Grading Subgrade – Secondary and Local
225.04 Method of Obtaining Superelevation – Two Lane Pavement

DIVISION 3 – PIPE CULVERTS

300.01 Method of Pipe Installation

DIVISION 4 – MAJOR STRUCTURES

422.11 Reinforced Bridge Approach Fills – Sub Regional Tier

DIVISION 5 – SUBGRADE, BASES AND SHOULDERS

560.01 Method of Shoulder Construction – High Side of Superelevated Curve – Method I

DIVISION 8 – INCIDENTALS

806.01 Concrete Right of Way Markers
840.00 Concrete Base Pad for Drainage Structures
840.25 Anchorage for Frames – Brick or Concrete or Precast
840.29 Frames and Narrow Slot Grates
840.35 Traffic Bearing Grated Drop Inlet
840.46 Traffic Bearing Precast Drainage Structure
840.66 Drainage Structure Steps
846.01 Concrete Curb, Gutter and Curb & Gutter
862.01 Guardrail Placement
862.02 Guardrail Installation
862.03 Structure Anchor Units
876.02 Guide for Rip Rap at Pipe Outlets

INDEX OF SHEETS

SHEET NUMBER

SHEET

1
1-A
1-B
1C-1 THRU 1C-2
2
2-A
3

4
EC-1 THRU EC-5
RF-1
X-1
X-2 THRU X-5
S-1 THRU S-18
SN

TITLE SHEET
INDEX OF SHEETS, GENERAL NOTES, AND LIST OF STANDARD DRAWINGS
CONVENTIONAL SYMBOLS
SURVEY CONTROL SHEET
TYPICAL SECTIONS, PAVEMENT SCHEDULE, & MISCELLANEOUS DETAILS
STRUCTURE ANCHOR UNIT DETAIL SHEETS 2 & 3 OF 7
SUMMARY OF DRAINAGE QUANTITIES, GUARDRAIL SUMMARY, EARTHWORK SUMMARY, PAVEMENT REMOVAL SUMMARY, SHOULDER BERM GUTTER AND RIGHT OF WAY AREA DATA
PLAN & PROFILE SHEET
EROSION CONTROL PLANS
REFORESTATION PLAN
CROSS-SECTION SUMMARY SHEET
CROSS-SECTIONS
STRUCTURE PLANS
STRUCTURE NOTES

PROJECT REFERENCE NO. <i>17BP.4.R.65</i>	SHEET NO. <i>1-A</i>
ROADWAY DESIGN ENGINEER <i>Greg S. Purvis</i> NOT A PROFESSIONAL SEAL 022999 ENGINEER GREG S. PURVIS 9/10/2015  WETHERILL ENGINEERING 1223 Jones Franklin Rd. Raleigh, N.C. 27606 License No. F-4377 Bus: 919 851 8077 Fax: 919 851 8107 TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION	

BRIDGE #950046

9/9/2015 8:47:30 AM
C:\Roadway\Pro\1950046_Edu.tsb.dgn
11/2/2015 WAYNE 46\Roadway\Pro\1950046_Edu.tsb.dgn

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS			PROJECT REFERENCE NO. <i>17BP.4.R.65</i>	SHEET NO. <i>1-B</i>
CONVENTIONAL PLAN SHEET SYMBOLS				
<i>BOUNDARIES AND PROPERTY:</i>				
State Line				
County Line				
Township Line				
City Line				
Reservation Line				
Property Line				
Existing Iron Pin		EIP		
Property Corner				
Property Monument		ECM		
Parcel/Sequence Number		(23)		
Existing Fence Line				
Proposed Woven Wire Fence				
Proposed Chain Link Fence				
Proposed Barbed Wire Fence				
Existing Wetland Boundary		WLB		
Proposed Wetland Boundary		WLB		
Existing Endangered Animal Boundary		EAB		
Existing Endangered Plant Boundary		EPB		
Known Soil Contamination: Area or Site				
Potential Soil Contamination: Area or Site				
<i>BUILDINGS AND OTHER CULTURE:</i>				
Gas Pump Vent or U/G Tank Cap				
Sign				
Well				
Small Mine				
Foundation				
Area Outline				
Cemetery				
Building				
School				
Church				
Dam				
<i>HYDROLOGY:</i>				
Stream or Body of Water				
Hydro, Pool or Reservoir				
Jurisdictional Stream		JS		
Buffer Zone 1		BZ 1		
Buffer Zone 2		BZ 2		
Flow Arrow				
Disappearing Stream				
Spring				
Wetland				
Proposed Lateral, Tail, Head Ditch				
False Sump				
<i>RAILROADS:</i>				
Standard Gauge		CSX TRANSPORTATION		
RR Signal Milepost		MILEPOST 35		
Switch		SWITCH		
RR Abandoned				
RR Dismantled				
<i>RIGHT OF WAY:</i>				
Baseline Control Point				
Existing Right of Way Marker				
Existing Right of Way Line				
Proposed Right of Way Line				
Proposed Right of Way Line with Iron Pin and Cap Marker				
Proposed Right of Way Line with Concrete or Granite RW Marker				
Proposed Control of Access Line with Concrete C/A Marker				
Existing Control of Access				
Proposed Control of Access				
Existing Easement Line		E		
Proposed Temporary Construction Easement		E		
Proposed Temporary Drainage Easement		TDE		
Proposed Permanent Drainage Easement		PDE		
Proposed Permanent Drainage / Utility Easement		DUE		
Proposed Permanent Utility Easement		PUE		
Proposed Temporary Utility Easement		TUE		
Proposed Aerial Utility Easement		AUE		
Proposed Permanent Easement with Iron Pin and Cap Marker				
<i>ROADS AND RELATED FEATURES:</i>				
Existing Edge of Pavement				
Existing Curb				
Proposed Slope Stakes Cut		C		
Proposed Slope Stakes Fill		F		
Proposed Curb Ramp		CR		
Existing Metal Guardrail				
Proposed Guardrail				
Existing Cable Guiderail				
Proposed Cable Guiderail				
Equality Symbol				
Pavement Removal				
<i>VEGETATION:</i>				
Single Tree				
Single Shrub				
Hedge				
Woods Line				
Orchard				
Vineyard		Vineyard		
<i>EXISTING STRUCTURES:</i>				
MAJOR:				
Bridge, Tunnel or Box Culvert		CONC		
Bridge Wing Wall, Head Wall and End Wall		CONC WW		
MINOR:				
Head and End Wall		CONC HW		
Pipe Culvert				
Footbridge				
Drainage Box: Catch Basin, DI or JB		CB		
Paved Ditch Gutter				
Storm Sewer Manhole		S		
Storm Sewer		S		
<i>UTILITIES:</i>				
POWER:				
Existing Power Pole				
Proposed Power Pole				
Existing Joint Use Pole				
Proposed Joint Use Pole				
Power Manhole		P		
Power Line Tower				
Power Transformer				
U/G Power Cable Hand Hole				
H-Frame Pole				
Recorded U/G Power Line		P		
Designated U/G Power Line (S.U.E.*)		P		
TELEPHONE:				
Existing Telephone Pole				
Proposed Telephone Pole				
Telephone Manhole		T		
Telephone Booth		3		
Telephone Pedestal		T		
Telephone Cell Tower				
U/G Telephone Cable Hand Hole		PH		
Recorded U/G Telephone Cable		T		
Designated U/G Telephone Cable (S.U.E.*)		T		
Recorded U/G Telephone Conduit		TC		
Designated U/G Telephone Conduit (S.U.E.*)		TC		
Recorded U/G Fiber Optics Cable		T FO		
Designated U/G Fiber Optics Cable (S.U.E.*)		T FO		
WATER:				
Water Manhole		W		
Water Meter				
Water Valve				
Water Hydrant				
Recorded U/G Water Line				
Designated U/G Water Line (S.U.E.*)		W		
Above Ground Water Line		A/G Water		
TV:				
TV Satellite Dish				
TV Pedestal				
TV Tower				
U/G TV Cable Hand Hole		TH		
Recorded U/G TV Cable		TV		
Designated U/G TV Cable (S.U.E.*)		TV		
Recorded U/G Fiber Optic Cable		TV FO		
Designated U/G Fiber Optic Cable (S.U.E.*)		TV FO		
GAS:				
Gas Valve				
Gas Meter				
Recorded U/G Gas Line		G		
Designated U/G Gas Line (S.U.E.*)		G		
Above Ground Gas Line		A/G Gas		
SANITARY SEWER:				
Sanitary Sewer Manhole		SS		
Sanitary Sewer Cleanout				
U/G Sanitary Sewer Line		SS		
Above Ground Sanitary Sewer		A/G Sanitary Sewer		
Recorded SS Forced Main Line		FSS		
Designated SS Forced Main Line (S.U.E.*)		FSS		
MISCELLANEOUS:				
Utility Pole				
Utility Pole with Base				
Utility Located Object				
Utility Traffic Signal Box		S		
Utility Unknown U/G Line		UTL		
U/G Tank; Water, Gas, Oil				
Underground Storage Tank, Approx. Loc.		UST		
A/G Tank; Water, Gas, Oil				
Geoenvironmental Boring				
U/G Test Hole (S.U.E.*)				
Abandoned According to Utility Records		AATUR		
End of Information		E.O.I.		

6/2/99

9/26/2015 9:54 AM
B:\2015\WAYNE 46\Roadway\Proj\950046_1s.tcdgn

SURVEY CONTROL SHEET 95-0046

PROJECT REFERENCE NO.	SHEET NO.
17BP.4.R.65	1C-1
Location and Surveys	



BASELINE DATA

BL	POINT	DESC.	NORTH	EAST	ELEVATION	EL STATION	OFFSET
1		95-0046-1	645993.1570	2294307.4200	115.70	OUTSIDE PROJECT LIMITS	
2		95-0046-2	646499.7730	2294605.4650	106.15	15+26.30	14.55 LT
3		BL-3	646737.7858	2294845.5600	105.25	18+62.62	15.32 RT

BENCHMARK DATA

BM 1 ELEVATION = 106.29
N 646280 E 2294403
L STATION 12+37.00 62 LEFT
R/R SPIKE IN 16" POPLAR

BM 2 ELEVATION = 104.16
N 646742 E 2294734
L STATION 17+93.00 72 LEFT
R/R SPIKE IN 18" OAK



DATUM DESCRIPTION

THE LOCALIZED COORDINATE SYSTEM DEVELOPED FOR THIS PROJECT IS BASED ON THE STATE PLANE COORDINATES ESTABLISHED BY NCGS FOR MONUMENT "GPS 95-0046-2"
WITH NAD 83/NA 2011 STATE PLANE GRID COORDINATES OF
NORTHING: 646499.770(±) EASTING: 2294605.471(±)
ELEVATION: 106.153(±)
THE AVERAGE COMBINED GRID FACTOR USED ON THIS PROJECT (GROUND TO GRID) IS: 0.999884100
THE N.C. LAMBERT GRID BEARING AND LOCALIZED HORIZONTAL GROUND DISTANCE FROM "GPS 95-0046-2" TO -L- STATION 21+89.46 IS
S 29°16'35.01" W 527.28
ALL LINEAR DIMENSIONS ARE LOCALIZED HORIZONTAL DISTANCES
VERTICAL DATUM USED IS NAVD 88

NOTES:

1. THE CONTROL DATA FOR THIS PROJECT CAN BE FOUND ELECTRONICALLY BY SELECTING PROJECT CONTROL DATA AT:
[HTTPS://CONNECT.NCDOT.GOV/RESOURCES/LOCATION/](https://connect.ncdot.gov/resources/location/)

THE FILES TO BE FOUND ARE AS FOLLOWS:
95-0046_LS_CONTROL.TXT

SITE CALIBRATION INFORMATION HAS NOT BEEN PROVIDED FOR THIS PROJECT. IF FURTHER INFORMATION IS NEEDED, PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.
- INDICATES GEODETIC CONTROL MONUMENTS USED OR SET FOR HORIZONTAL PROJECT CONTROL BY THE NCDOT LOCATION AND SURVEYS UNIT.
PROJECT CONTROL ESTABLISHED USING GLOBAL POSITIONING SYSTEM.

NOTE: DRAWING NOT TO SCALE

8:39:04 AM
8:39:04 AM

8:39:04 AM
8:39:04 AM

8:39:04 AM
8:39:04 AM

8:39:04 AM
8:39:04 AM

8:39:04 AM
8:39:04 AM

8:39:04 AM
8:39:04 AM

8:39:04 AM
8:39:04 AM

8:39:04 AM
8:39:04 AM

8:39:04 AM
8:39:04 AM

- 8:39:04 AM
8:39:04 AM

8:39:04 AM
8:39:04 AM


8:39:04 AM
8:39:04 AM

8:39:04 AM
8:39:04 AM


6/2/99

PAVEMENT SCHEDULE	
C1	PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, AT AN AVERAGE RATE OF 165 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.
C2	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, AT AN AVERAGE RATE OF 110 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT TO EXCEED 1½" IN DEPTH.
E1	PROP. APPROX. 6" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 342 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.
E2	PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 3" IN DEPTH OR GREATER THAN 5½" IN DEPTH.
T	EARTH MATERIAL.
U	EXISTING PAVEMENT.
V	MILLING BITUMINOUS PAVEMENT. (SEE MILLING DETAIL)
W	VARIABLE DEPTH ASPHALT PAVEMENT (SEE WEDGING DETAIL)

NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.




W: Detail Showing Method of Wedging



SHOULDER DETAIL

USE SHOULDER DETAIL IN CONJUNCTION WITH TYPICAL SECTIONS NO. 1 & 2:




TYPICAL SECTION NO. 1

USE TYPICAL SECTION NO. 1 AS FOLLOWS:

-L- STA. 13+22.00 TO -L- STA. 14+95.00


-L- STA. 16+38.00 TO -L- STA. 18+12.00



TYPICAL SECTION NO. 3

USE TYPICAL SECTION NO. 3 AS FOLLOWS:

-L- STA. 15+30.81 (BEGIN BRIDGE) TO -L- STA. 16+08.19 (END BRIDGE)




V: MILLING DETAIL

USE MILLING DETAIL AS FOLLOWS:

-L- STA. 13+22.00 TO -L- STA. 14+30.00

-L- STA. 17+50.00 TO -L- STA. 18+12.00



TYPICAL SECTION NO. 2

USE TYPICAL SECTION NO. 2 AS FOLLOWS:

-L- STA. 14+95.00 TO -L- STA. 15+30.81 (BEGIN BRIDGE)

-L- STA. 16+08.19 (END BRIDGE) TO -L- STA. 16+37.00

PROJECT REFERENCE NO. 17BP.4.R.65		SHEET NO. 2	
ROADWAY DESIGN ENGINEER G. S. PAVES NORTH CAROLINA PROFESSIONAL SEAL 022999 ENGINEER CREG S. PAVES 9/10/2015		PAVEMENT DESIGN ENGINEER	
 TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION		1223 Jones Franklin Rd. Raleigh, N.C. 27606 License No. F-5277 Bus: 919 851 8077 Fax: 919 851 8107	

BRIDGE #950046

COMPUTED BY: SLK DATE: 01/20/15
CHECKED BY: GSP DATE: 01/20/15

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS



1223 Jones Franklin Rd.
Raleigh, N.C. 27606
License No. F-0377
Bus: 919 851 8077
Fax: 919 851 8107

PROJECT REFERENCE NO.	SHEET NO.
17BP.4.R.65	3

SUMMARY OF EARTHWORK

STATION	STATION	UNCL EXCAV.	EMBANK. + %	BORROW	WASTE
—L— 13 + 22.00	—L— 15 + 30.81 (BEGIN BRIDGE)	9	89	80	
SUBTOTALS:		9	89	80	
—L— 16 + 08.19 (END BRIDGE)	—L— 18 + 12.00	3	124	121	
SUBTOTALS:		3	124	121	
PROJECT SUBTOTALS:		12	213	201	
LOSS DUE TO CLEARING & GRUBBING				10	
GRAND TOTALS:		12	213	211	
SAY:		25		225	

Note: Approximate quantities only. Unclassified Excavation, Borrow Excavation Fine Grading, Clearing and Grubbing, Breaking of Existing Pavement, and Removal of Existing Pavement will be paid for at the contract lump sum price for "Grading."

RIGHT OF WAY AREA DATA

PARCEL NO.	PROPERTY OWNERS NAMES	TOTAL ACREAGE	AREA TAKEN	AREA REMAINING RT.	AREA REMAINING LT.	PERM. DRAINAGE EASE.	PERM. UTILITY EASE.	TEMP. CONST. EASE.
1 (RIGHT)	KATHRYN H. EDWARDS & JOHN L. HOOKS		637.96 SF			196.58 SF		
1 (LEFT)	KATHRYN H. EDWARDS & JOHN L. HOOKS		473.05 SF					
2	TILLMAN FARMS LLC.		811.25 SF					
3	GEORGE L. HOOKS JR.		832.91 SF					

PAVEMENT REMOVAL SUMMARY

SURVEY LINE	STATION	STATION	LOCATION LT/RT/CL	YD ²
-L-	14 + 95	15 + 53	CL	123
-L-	15 + 87	16 + 38	CL	108
TOTAL:				231
SAY:				240

SHOULDER BERM GUTTER SUMMARY

SURVEY LINE	STATION	STATION	LENGTH
-L- RT.	14 + 95.00	15 + 19.81	24.81'
		TOTAL:	24.81'
		SAY:	26'

***SUB-REGIONAL & REGIONAL
LIST OF PIPES, ENDWALLS, ETC. (FOR PIPES 48" & UNDER)***


NOTE: Invert Elevations are for Bid Purposes only and shall not be used for project construction stakeout. See "Standard Specifications For Roads and Structures, Section 300-5".

[illegible]

"N" = DISTANCE FROM EDGE OF LANE TO FACE OF GUARDRAIL.
TOTAL SHOULDER WIDTH = DISTANCE FROM EDGE OF TRAVEL LANE TO SHOULDER BREAK POINT.
FLARE LENGTH = DISTANCE FROM LAST SECTION OF PARALLEL GUARDRAIL TO END OF GUARDRAIL.
W = TOTAL WIDTH OF FLARE FROM BEGINNING OF TAPER TO END OF GUARDRAIL.
G = GATING IMPACT ATTENUATOR TYPE 350
NG = NON-GATING IMPACT ATTENUATOR TYPE 350

GUARDRAIL SUMMARY

[illegible]




```
#####USER#####  
#####SYSTEM#####
```

VICINITY MAP

OFF-SITE DETOUR —●—●—●—●—●—

**LOCATION: BRIDGE NO. 46 OVER NAHUNTA SWAMP
ON SR 1353 (HOOKS ROAD)
TYPE OF WORK: GRADING, DRAINAGE, PAVING & STRUCTURE**

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	17BP.4.R.65	EC-1	
STATE PROJ.NO.	F.A.PROJ.NO.	DESCRIPTION	

Sed. #	Description	Symbol
1630.03	Temporary Silt Ditch	
1630.05	Temporary Diversion	
1605.01	Temporary Silt Fence	
1606.01	Special Sediment Control Fence	
1622.01	Temporary Berms and Slope Drains	
1630.02	Silt Basin Type B	
1633.01	Temporary Rock Silt Check Type-A	
	Temporary Rock Silt Check Type-A with Matting and Polyacrylamide (PAM)	
1633.02	Temporary Rock Silt Check Type-B	
	Wattle// Coir Fiber Wattle	
	Wattle// Coir Fiber Wattle with Polyacrylamide (PAM)	
1634.01	Temporary Rock Sediment Dam Type-A	
1634.02	Temporary Rock Sediment Dam Type-B	
1635.01	Rock Pipe Inlet Sediment Trap Type-A	
1635.02	Rock Pipe Inlet Sediment Trap Type-B	
1630.04	Stilling Basin	
1630.06	Special Stilling Basin	
	Rock Inlet Sediment Trap:	
1632.01	Type A	
1632.02	Type B	
1632.03	Type C	
	Skimmer Basin	
	Tiered Skimmer Basin	
	Infiltration Basin	

***Refer To E. C. Special Provisions
for Special Considerations.***

1632.01	Rock Inlet Sediment Trap	Type A
1632.02	Rock Inlet Sediment Trap	Type B
1632.03	Rock Inlet Sediment Trap	Type C
1633.01	Temporary Rock Silt Check	Type A
1633.02	Temporary Rock Silt Check	Type B
1634.01	Temporary Rock Sediment Dam	Type A
1634.02	Temporary Rock Sediment Dam	Type B
1635.01	Rock Pipe Inlet Sediment Trap	Type A
1635.02	Rock Pipe Inlet Sediment Trap	Type B
1640.01	Coir Fiber Baffle	
1645.01	Temporary Stream Crossing	

DIVISION OF HIGHWAYS


STATE OF NORTH CAROLINA

SOIL STABILIZATION TIMEFRAMES

SITE DESCRIPTION	STABILIZATION TIME	TIMEFRAME EXCEPTIONS
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HQW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HQW ZONES.

EROSION CONTROL PLAN

PROJECT REFERENCE NO.	SHEET NO.
17BP.4.R.65	EC-4/CONST.04
RW SHEET NO.	



NOTE:
UTILIZE TEMPORARY SEDIMENT BASIN OR SPECIAL STILLING BASIN(S) AS STILLING BASIN WHERE APPLICABLE.

NAD 83 NC GRID
NA 2011

BM 1
N=646280' E=2294403'
ELEV=106.29'
R/R SPIKE IN 16" POPLAR

BM 2
N=646742' E=2294734'
ELEV=104.16'
R/R SPIKE IN 18" OAK

+90.00
EX.RW, 40' RT

+50.00
EX.RW, 40' LT

+15.00
EX.RW, 40' LT

+50.00
EX.RW, 40' LT

PC Sta. 11+72.74

SR 1353 SR 1336 (NAHUNTA RD.)
TO
SR 1353 SR 1336 (NAHUNTA RD.)

HOOKS ROAD
SR 1353 - 20' PAVED ROADWAY

BEGIN SHOULDER
BERM GUTTER
STA. 14+95 (RT)

-L- PT Sta. 16+03.46

PROPOSED
EXCAVATION

TILLMAN FARMS LLC TO 106.1'

KATHRYN H EDWARDS
& JOHN L HOOKS

CL II RIP RAP
TO 106.1'

WOODS

WOODS

3

15


20

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	17BP.4.R.65	RF-1	
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	


PLANTING DETAILS
SEEDLING / LINER BAREROOT PLANTING DETAIL

HEALING IN


1. Locate a healing-in site in a shady, well protected area.
2. Excavate a flat bottom trench 12 inches deep and provide drainage.




3. Backfill the trench with 2 inches well rotted sawdust. Place a 2 inch layer of well rotted sawdust at a sloping angle at one end of the trench.



4. Place a single layer of plants against the sloping end so that the root collar is at ground level.




5. Place a 2 inch layer of well rotted sawdust over the roots maintaining a sloping angle.




6. Repeat layers of plants and sawdust as necessary and water thoroughly.

DIBBLE PLANTING METHOD
USING THE KBC PLANTING BAR



1. Insert planting bar as shown and pull handle toward planter.
2. Remove planting bar and place seedling at correct depth.
3. Insert planting bar 2 inches toward planter from seedling.




4. Pull handle of bar toward planter, firming soil at bottom.
5. Push handle forward firming soil at top.
6. Leave compaction hole open. Water thoroughly.

PLANTING NOTES:

PLANTING BAG
During planting, seedlings shall be kept in a moist canvas bag or similar container to prevent the root systems from drying.



KBC PLANTING BAR
Planting bar shall have a blade with a triangular cross section, and shall be 12 inches long, 4 inches wide and 1 inch thick at center.



ROOT PRUNING
All seedlings shall be root pruned, if necessary, so that no roots extend more than 10 inches below the root collar.

REFORESTATION

- TREE REFORESTATION SHALL BE PLANTED 6 FT. TO 10 FT. ON CENTER, RANDOM SPACING, AVERAGING 8 FT. ON CENTER, APPROXIMATELY 680 PLANTS PER ACRE.

REFORESTATION

MIXTURE, TYPE, SIZE, AND FURNISH SHALL CONFORM TO THE FOLLOWING:

25%	LIRIODENDRON TULIPIFERA	TULIP POPLAR	12 in - 18 in BR
25%	PLATANUS OCCIDENTALIS	AMERICAN SYCAMORE	12 in - 18 in BR
25%	FRAXINUS PENNSYLVANICA	GREEN ASH	12 in - 18 in BR
25%	BETULA NIGRA	RIVER BIRCH	12 in - 18 in BR

REFORESTATION DETAIL SHEET

N.C.D.O.T.- ROADSIDE ENVIRONMENTAL UNIT

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

PROJ. REFERENCE NO.	SHEET NO.
17BP.4.R.65	X-1

-L-

NOTE: EMBANKMENT COLUMN DOES NOT
INCLUDE BACKFILL FOR UNDERCUT

Station	Uncl. Exc.	Embt
L	(cu. yd.)	(cu. yd.)
13+22.00	0	0
13+50.00	1	1
13+72.00	0	1
14+00.00	0	3
14+50.00	1	13
15+00.00	3	22
15+30.81	4	31
Station	Uncl. Exc.	Embt
L	(cu. yd.)	(cu. yd.)
16+08.19	0	0
16+50.00	2	33
17+00.00	0	41
17+50.00	0	20
17+62.00	0	2
18+00.00	1	3
18+12.00	0	0


Approximate quantities only. Unclassified excavation, borrow excavation, shoulder borrow, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".


CROSS SECTION INDEX

SHEET	LINE	BEGIN STATION	END STATION
X-2	-L-	13+22.00	14+00.00
X-3	-L-	14+50.00	15+50.00
X-4	-L-	16+00.00	17+00.00
X-5	-L-	17+50.00	

8/23/99
1:33:50 PM
C:\2013\WAYNE 46\Roadway\Xsec\550046.FDY_XPL.dgn
9/2/2015


0 2.5 5	PROJ. REFERENCE NO.	SHEET NO.
	17BP.4.R.65	X-2







8/23/99

0 2.5 5	PROJ. REFERENCE NO.	SHEET NO.
	17BP.4.R.65	X-4



I:\34\35 PM
07/20/03
07/22/03
46\Roadway\Xsec\950046.FDY_XPL.dgn





LOW CHORD ELEVATIONS	
	ELEVATION @ C BRC.
END BENT 1	104.66 @ RT. END
END BENT 2	104.88 @ RT. END

HORIZONTAL CURVE DATA -L-


PI Sta 13+89.07 -L-
Δ = 13°-16'-03.8" (RT)
D = 3°-04'-49.5"
L = 430.71'
T = 216.32'
R = 1,860.00'

HYDRAULIC DATA

DESIGN DISCHARGE----- 1180 CFS
FREQUENCY OF DESIGN FLOOD----- 25 YR.
DESIGN HIGH WATER ELEVATION---- 105.1
DRAINAGE AREA----- 14.23 SQ.MI.
BASE DISCHARGE (Q100)----- 1800 CFS
BASE HIGH WATER ELEVATION----- 105.54

OVERTOPPING FLOOD DATA

OVERTOPPING DISCHARGE----- 1800+ CFS
FREQUENCY OF OVERTOPPING FLOOD- 100+ YRS
OVERTOPPING FLOOD ELEVATION---- 106.39
OVERTOPPING OCCURS @ C STA. 18+70



I HEREBY CERTIFY THESE PLANS ARE THE AS-BUILT PLANS

PROJECT NO. 17BP.4.R.65
WAYNE COUNTY
STATION: 15+69.50 -L-

SHEET 1 OF 2 REPLACES BRIDGE No. 46

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

GENERAL DRAWING

BRIDGE ON
SR 1353 (HOOKS RD.)
OVER NAHUNTA SWAMP
BETWEEN
SR 1336 & SR 1361

REVISIONS				SHEET NO.	
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		
				TOTAL SHEETS	18

DRAWN BY : J.M. BRITT DATE : 8-18-15
CHECKED BY : B.C. HUNT DATE : 8-19-15
DESIGN ENGINEER OF RECORD: G.M. GILLAND DATE : 8-19-15

NOTE :
W.P. #2 IS LOCATED
ON THE LONG CHORD



1223 Jones Franklin Rd.
Raleigh, N.C. 27606
Bus: 919 851 8077
Fax: 919 851 8107
License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

NOTES:

- ASSUMED LIVE LOAD = HL-93 OR ALTERNATE LOADING.
- FOR OTHER DESIGN DATA AND GENERAL NOTES, SEE SHEET SN.
- FOR EROSION CONTROL MEASURES, SEE EROSION CONTROL PLANS.
- THIS BRIDGE HAS BEEN DESIGNED IN ACCORDANCE WITH THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS.
- THIS BRIDGE IS LOCATED IN SEISMIC ZONE 1.

THE EXISTING STRUCTURE CONSISTING OF 2 SPANS @ 17'-6" EACH WITH A TIMBER DECK ON TIMBER JOISTS AND A CLEAR ROADWAY WIDTH OF 24'-9" ON A SUBSTRUCTURE CONSISTING OF TIMBER CAPS WITH TIMBER PILES AT VARIOUS CENTERS AND LOCATED AT THE PROPOSED STRUCTURE LOCATION SHALL BE REMOVED. THE EXISTING BRIDGE IS PRESENTLY POSTED FOR LOAD LIMIT.

REMOVAL OF THE EXISTING BRIDGE SHALL BE PERFORMED SO AS NOT TO ALLOW DEBRIS TO FALL INTO THE WATER. THE CONTRACTOR SHALL REMOVE THE BRIDGE AND SUBMIT PLANS FOR DEMOLITION IN ACCORDANCE WITH ARTICLE 402-2 OF THE STANDARD SPECIFICATIONS.

THE MATERIAL SHOWN IN THE CROSS-HATCHED AREA SHALL BE EXCAVATED FOR A DISTANCE OF 20 FT. EACH SIDE OF CENTERLINE ROADWAY AS DIRECTED BY ENGINEER. SEE SECTION 412 OF THE STANDARD SPECIFICATIONS.

THE SUBSTRUCTURE OF THE EXISTING BRIDGE INDICATED ON THE PLANS IS FROM THE BEST INFORMATION AVAILABLE. SINCE THIS INFORMATION IS SHOWN FOR THE CONVENIENCE OF THE CONTRACTOR, THE CONTRACTOR SHALL HAVE NO CLAIM WHATSOEVER AGAINST THE DEPARTMENT OF TRANSPORTATION FOR ANY DELAYS OR ADDITIONAL COST INCURRED BASED ON DIFFERENCE BETWEEN THE EXISTING BRIDGE SUBSTRUCTURE SHOWN ON THE PLANS AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE WITH "HEC 18-EVALUATING SCOUR AT BRIDGES".

- FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.
- FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.
- FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.
- FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.
- ASPHALT WEARING SURFACE IS INCLUDED IN ROADWAY QUANTITY ON ROADWAY PLANS.

FOUNDATION NOTES:

- FOR PILES, SEE GEOTECHNICAL SPECIAL PROVISIONS AND SECTION 450 OF THE STANDARD SPECIFICATIONS.
- PILES AT END BENT 1 ARE DESIGNED FOR A FACTORED RESISTANCE OF 65 TONS PER PILE. DRIVE PILES AT END BENT 1 TO A REQUIRED DRIVING RESISTANCE OF 110 TONS PER PILE. PILES AT BENT 1 ARE DESIGNED FOR A FACTORED RESISTANCE OF 90 TONS PER PILE. DRIVE PILES AT BENT 1 TO A REQUIRED DRIVING RESISTANCE OF 155 TONS PER PILE. THIS REQUIRED DRIVING RESISTANCE INCLUDES ADDITIONAL RESISTANCE FOR DOWNDRAW OR SCOUR.
- PILES AT END BENT 2 ARE DESIGNED FOR A FACTORED RESISTANCE OF 75 TONS PER PILE. DRIVE PILES AT END BENT 2 TO A REQUIRED DRIVING RESISTANCE OF 125 TONS PER PILE. INSTALL PILES AT BENT 1 TO A TIP ELEVATION NO HIGHER THAN 70.0.
- DRILLED-IN PILES ARE REQUIRED FOR BENT 1. EXCAVATE HOLES AT PILE LOCATIONS TO ELEVATION 70. FOR PILE EXCAVATION, SEE SECTION 450 OF THE STANDARD SPECIFICATIONS.
- CONCRETE OR GROUT IS REQUIRED TO FILL HOLES FOR PILE EXCAVATION AT BENT 1.
- THE SCOUR CRITICAL ELEVATION FOR BENT 1 IS ELEVATION 82.0. SCOUR CRITICAL ELEVATIONS ARE USED TO MONITOR POSSIBLE SCOUR PROBLEMS DURING THE LIFE OF THE STRUCTURE.
- IT HAS BEEN ESTIMATED THAT A HAMMER WITH AN EQUIVALENT RATED ENERGY IN THE RANGE OF 35 TO 45 FT-KIPS PER BLOW WILL BE REQUIRED TO DRIVE PILES AT END BENT 1 & 2 AND BENT 1. THIS ESTIMATED ENERGY RANGE DOES NOT RELEASE THE CONTRACTOR FROM PROVIDING DRIVING EQUIPMENT IN ACCORDANCE WITH SUBARTICLE 450-3(D)(2) OF THE STANDARD SPECIFICATIONS.


PROJECT NO. 17BP.4.R.65
WAYNE COUNTY
STATION: 15+69.50 -L-

SHEET 2 OF 2

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
GENERAL DRAWING
BRIDGE ON
SR 1353 (HOOKS RD.)
OVER NAHUNTA SWAMP
BETWEEN
SR 1336 & SR 1361


REVISONS				SHEET NO.
NO.	BY:	DATE:	NO.	DATE:
1			3	
2			4	
				S-2
				TOTAL SHEETS 18

TOTAL BILL OF MATERIAL																
	REMOVAL OF EXISTING STRUCTURE	PILE EXCAVATION IN SOIL	PILE EXCAVATION NOT IN SOIL	UNCLASSIFIED STRUCTURE EXCAVATION	CLASS A CONCRETE	BRIDGE APPROACH SLABS	REINFORCING STEEL	HP 12 x 53 STEEL PILES		HP 14 x 73 GALVANIZED STEEL PILES		VERTICAL CONCRETE BARRIER RAIL	ELASTOMERIC BEARINGS	RIP RAP CLASS II (2'-0" THICK)	GEOTEXTILE FOR DRAINAGE	3'-0" X 1'-9" PRESTRESSED CONCRETE CORED SLABS
	LUMP SUM	LIN. FT.	LIN. FT.	LUMP SUM	CU. YDS.	LUMP SUM	LBS.	No.	LIN. FT.	No.	LIN. FT.	LIN. FT.	LUMP SUM	TONS	SQ. YDS.	No. LIN. FT.
SUPERSTRUCTURE				LUMP SUM		LUMP SUM						150.50	LUMP SUM			20 750.00
END BENT 1					13.0		1,965	5	150.0					54	59	
BENT 1		133.0	63.0		9.8		1,933			7	245.0					
END BENT 2					13.0		1,965	5	150.0					24	27	
TOTAL	LUMP SUM	133.0	63.0	LUMP SUM	35.8	LUMP SUM	5,863	10	300.0	7	245.0	150.50	LUMP SUM	78	86	20 750.00



LOCATION SKETCH

DRAWN BY : J.M. BRITT DATE : 8-18-15
CHECKED BY: B.C. HUNT DATE : 8-19-15
DESIGN ENGINEER OF RECORD: G.M. GILLAND DATE : 8-19-15



1223 Jones Franklin Rd.
Raleigh, N.C. 27606
Bus: 919 851 8077
Fax: 919 851 8107
License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

LOAD AND RESISTANCE FACTOR RATING (LRFD) SUMMARY FOR PRESTRESSED CONCRETE GIRDERS

LEVEL	VEHICLE	WEIGHT (W) (TONS)	CONTROLLING LOAD RATING	MINIMUM RATING FACTORS (RF)	TONS = W X RF	STRENGTH I LIMIT STATE											SERVICE III LIMIT STATE						COMMENT NUMBER	
						LIVELOAD FACTORS	MOMENT					SHEAR					LIVELOAD FACTORS	MOMENT						
							DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)		DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)		
DESIGN LOAD RATING	HL-93(Inv)	N/A	1	1.037	--	1.75	0.283	1.83	30'	EL	14.5	0.574	1.04	30'	EL	1.45	0.80	0.283	1.58	30'	EL	14.5		
	HL-93(0pr)	N/A	--	1.344	--	1.35	0.283	2.38	30'	EL	14.5	0.574	1.34	30'	EL	1.45	N/A	--	--	--	--	--		
	HS-20(Inv)	36.000	2	1.183	42.587	1.75	0.283	2.53	30'	EL	11.6	0.574	1.18	30'	EL	1.45	0.80	0.283	2.20	30'	EL	11.6		
	HS-20(0pr)	36.000	--	1.533	55.205	1.35	0.283	3.28	30'	EL	11.6	0.574	1.53	30'	EL	1.45	N/A	--	--	--	--	--		
LEGAL LOAD RATING	SV	SNSH	13.500	--	2.895	39.081	1.4	0.283	5.18	30'	EL	14.5	0.574	2.89	30'	EL	1.45	0.80	0.283	3.56	30'	EL	14.5	
		SNGARBS2	20.000	--	2.240	44.792	1.4	0.283	4.53	30'	EL	11.6	0.574	2.24	30'	EL	1.45	0.80	0.283	3.15	30'	EL	11.6	
		SNAGRIS2	22.000	--	2.157	47.463	1.4	0.283	4.6	30'	EL	11.6	0.574	2.16	30'	EL	1.45	0.80	0.283	3.20	30'	EL	11.6	
		SNCOTTS3	27.250	--	1.462	39.849	1.4	0.283	2.6	30'	EL	14.5	0.574	1.46	30'	EL	1.45	0.80	0.283	1.79	30'	EL	14.5	
		SNAGGRS4	34.925	--	1.346	46.999	1.4	0.283	2.5	30'	EL	14.5	0.574	1.35	30'	EL	1.45	0.80	0.283	1.72	30'	EL	14.5	
		SNS5A	35.550	--	1.427	50.733	1.4	0.283	2.42	30'	EL	14.5	0.574	1.43	30'	EL	1.45	0.80	0.283	1.67	30'	EL	14.5	
		SNS6A	39.950	--	1.341	53.59	1.4	0.283	2.29	30'	EL	14.5	0.574	1.34	30'	EL	1.45	0.80	0.283	1.58	30'	EL	14.5	
		SNS7B	42.000	--	1.369	57.505	1.4	0.283	2.23	30'	EL	14.5	0.574	1.37	30'	EL	1.45	0.80	0.283	1.53	30'	EL	14.5	
	TTST	TNAGRIT3	33.000	--	1.593	52.58	1.4	0.283	2.97	30'	EL	14.5	0.574	1.59	30'	EL	1.45	0.80	0.283	2.04	30'	EL	14.5	
		TNT4A	33.075	--	1.483	49.043	1.4	0.283	2.82	30'	EL	14.5	0.574	1.48	30'	EL	1.45	0.80	0.283	1.94	30'	EL	14.5	
		TNT6A	41.600	--	1.433	59.622	1.4	0.283	2.56	30'	EL	14.5	0.574	1.43	30'	EL	1.45	0.80	0.283	1.76	30'	EL	14.5	
		TNT7A	42.000	--	1.363	57.264	1.4	0.283	2.64	30'	EL	14.5	0.574	1.36	30'	EL	1.45	0.80	0.283	1.82	30'	EL	14.5	
		TNT7B	42.000	--	1.331	55.915	1.4	0.283	2.49	30'	EL	14.5	0.574	1.33	30'	EL	1.45	0.80	0.283	1.72	30'	EL	14.5	
		TNAGRIT4	43.000	--	1.287	55.356	1.4	0.283	2.58	30'	EL	14.5	0.574	1.29	30'	EL	1.45	0.80	0.283	1.78	30'	EL	14.5	
TNAGT5A		45.000	--	1.381	62.151	1.4	0.283	2.5	30'	EL	14.5	0.574	1.38	30'	EL	1.45	0.80	0.283	1.72	30'	EL	14.5		
TNAGT5B	45.000	3	1.212	54.54	1.4	0.283	2.41	30'	EL	11.6	0.574	1.21	30'	EL	1.45	0.80	0.283	1.66	30'	EL	11.6			

LOAD FACTORS:

DESIGN LOAD RATING FACTORS	LIMIT STATE	γ_{DC}	γ_{DW}
	STRENGTH I	1.25	1.50
	SERVICE III	1.00	1.00

NOTES:

MINIMUM RATING FACTORS ARE BASED ON THE STRENGTH I AND SERVICE III LIMIT STATES.

ALLOWABLE STRESSES FOR SERVICE III LIMIT STATE ARE AS REQUIRED FOR DESIGN.

COMMENTS:

1.
2.
3.
4.

CONTROLLING LOAD RATING

1

DESIGN LOAD RATING (HL-93)

2


DESIGN LOAD RATING (HS-20)

3

LEGAL LOAD RATING **

** SEE CHART FOR VEHICLE TYPE

GIRDER LOCATION

I - INTERIOR GIRDER
EL - EXTERIOR LEFT GIRDER
ER - EXTERIOR RIGHT GIRDER

PROJECT NO. 17BP.4.R.65

WAYNE COUNTY

STATION: 15+69.50 -L-

ASSEMBLED BY :	C.C.WILLIAMS	DATE :	7/2015
CHECKED BY :	A.K.PASCHAL	DATE :	8/2015
DRAWN BY :	CVC	6/10	
CHECKED BY :	DNS	6/10	



DocuSigned by:
A. Keith Paschal
FBB6AD0BDB2FC48F...

8/12/2015

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH					
STANDARD LRFR SUMMARY FOR 30' CORED SLAB UNIT 90° SKEW (NON-INTERSTATE TRAFFIC)					
REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		
SHEET NO. S-3					TOTAL SHEETS 18

LOAD AND RESISTANCE FACTOR RATING (LRFD) SUMMARY FOR PRESTRESSED CONCRETE GIRDERS

LEVEL	VEHICLE	WEIGHT (W) (TONS)	CONTROLLING LOAD RATING	MINIMUM RATING FACTORS (RF)	TONS = W X RF	STRENGTH I LIMIT STATE										SERVICE III LIMIT STATE						COMMENT NUMBER		
						LIVELOAD FACTORS	MOMENT					SHEAR					LIVELOAD FACTORS	MOMENT						
							DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)		DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION		DISTANCE FROM LEFT END OF SPAN (ft)	
DESIGN LOAD RATING	HL-93(Inv)	N/A	1	1.088	--	1.75	0.277	1.34	45'	EL	22	0.539	1.23	45'	EL	2.2	0.80	0.277	1.09	45'	EL	22		
	HL-93(0pr)	N/A	--	1.590	--	1.35	0.277	1.74	45'	EL	22	0.539	1.59	45'	EL	2.2	N/A	--	--	--	--	--		
	HS-20(Inv)	36.000	2	1.336	48.104	1.75	0.277	1.65	45'	EL	22	0.539	1.45	45'	EL	2.2	0.80	0.277	1.34	45'	EL	22		
	HS-20(0pr)	36.000	--	1.882	67.763	1.35	0.277	2.14	45'	EL	22	0.539	1.88	45'	EL	2.2	N/A	--	--	--	--	--		
LEGAL LOAD RATING	SV	SNSH	13.500	--	2.611	35.252	1.4	0.277	4.02	45'	EL	22	0.539	4.01	45'	EL	2.2	0.80	0.277	2.61	45'	EL	22	
		SNGARBS2	20.000	--	2.108	42.166	1.4	0.277	3.25	45'	EL	22	0.539	2.94	45'	EL	2.2	0.80	0.277	2.11	45'	EL	22	
		SNAGRIS2	22.000	--	2.067	45.466	1.4	0.277	3.15	45'	EL	17.6	0.539	2.77	45'	EL	2.2	0.80	0.277	2.07	45'	EL	22	
		SNCOTTS3	27.250	--	1.304	35.527	1.4	0.277	2.01	45'	EL	22	0.539	2.01	45'	EL	2.2	0.80	0.277	1.30	45'	EL	22	
		SNAGGRS4	34.925	--	1.150	40.181	1.4	0.277	1.77	45'	EL	22	0.539	1.74	45'	EL	2.2	0.80	0.277	1.15	45'	EL	22	
		SNS5A	35.550	--	1.121	39.841	1.4	0.277	1.73	45'	EL	22	0.539	1.79	45'	EL	2.2	0.80	0.277	1.12	45'	EL	22	
		SNS6A	39.950	--	1.056	42.175	1.4	0.277	1.63	45'	EL	22	0.539	1.67	45'	EL	2.2	0.80	0.277	1.06	45'	EL	22	
		SNS7B	42.000	3	1.006	42.268	1.4	0.277	1.55	45'	EL	22	0.539	1.68	45'	EL	2.2	0.80	0.277	1.01	45'	EL	22	
	TTST	TNAGRIT3	33.000	--	1.296	42.759	1.4	0.277	2	45'	EL	22	0.539	1.96	45'	EL	2.2	0.80	0.277	1.30	45'	EL	22	
		TNT4A	33.075	--	1.309	43.305	1.4	0.277	2.02	45'	EL	22	0.539	1.88	45'	EL	2.2	0.80	0.277	1.31	45'	EL	22	
		TNT6A	41.600	--	1.099	45.712	1.4	0.277	1.69	45'	EL	22	0.539	1.83	45'	EL	2.2	0.80	0.277	1.10	45'	EL	22	
		TNT7A	42.000	--	1.120	47.043	1.4	0.277	1.73	45'	EL	22	0.539	1.69	45'	EL	2.2	0.80	0.277	1.12	45'	EL	22	
		TNT7B	42.000	--	1.166	48.975	1.4	0.277	1.8	45'	EL	22	0.539	1.61	45'	EL	2.2	0.80	0.277	1.17	45'	EL	22	
		TNAGRIT4	43.000	--	1.111	47.757	1.4	0.277	1.71	45'	EL	22	0.539	1.55	45'	EL	2.2	0.80	0.277	1.11	45'	EL	22	
		TNAGT5A	45.000	--	1.033	46.505	1.4	0.277	1.59	45'	EL	22	0.539	1.59	45'	EL	2.2	0.80	0.277	1.03	45'	EL	22	
		TNAGT5B	45.000	--	1.009	45.408	1.4	0.277	1.56	45'	EL	22	0.539	1.47	45'	EL	2.2	0.80	0.277	1.01	45'	EL	22	

LOAD FACTORS:

DESIGN LOAD RATING FACTORS	LIMIT STATE	γ_{DC}	γ_{DW}
	STRENGTH I	1.25	1.50
	SERVICE III	1.00	1.00

NOTES:

MINIMUM RATING FACTORS ARE BASED ON THE STRENGTH I AND SERVICE III LIMIT STATES.

ALLOWABLE STRESSES FOR SERVICE III LIMIT STATE ARE AS REQUIRED FOR DESIGN.

COMMENTS:

1.
2.
3.
4.

CONTROLLING LOAD RATING

1 DESIGN LOAD RATING (HL-93)


2 DESIGN LOAD RATING (HS-20)

3 LEGAL LOAD RATING **

** SEE CHART FOR VEHICLE TYPE

GIRDER LOCATION

I - INTERIOR GIRDER
EL - EXTERIOR LEFT GIRDER
ER - EXTERIOR RIGHT GIRDER




PROJECT NO. 17BP.4.R.65


WAYNE COUNTY

STATION: 15+69.50 -L-

ASSEMBLED BY : C.C.WILLIAMS	DATE : 7/2015
CHECKED BY : A.K.PASCHAL	DATE : 8/2015
DRAWN BY : CVC	6/10
CHECKED BY : DNS	6/10



STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH					
STANDARD LRFR SUMMARY FOR 45' CORED SLAB UNIT 90° SKEW (NON-INTERSTATE TRAFFIC)					
REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		
SHEET NO. S-4					TOTAL SHEETS 18



HALF SECTION
AT INTERMEDIATE DIAPHRAGMS

HALF SECTION
THROUGH VOIDS


TYPICAL SECTION

* - THE MAXIMUM BARRIER RAIL HEIGHT AND ASPHALT THICKNESS IS SHOWN. THE HEIGHT OF THE BARRIER RAIL AND ASPHALT THICKNESS VARIES WHILE THE TOP OF THE BARRIER RAIL FOLLOWS THE PROFILE OF THE GUTTERLINE. FOR RAIL HEIGHT DETAILS AND ASPHALT THICKNESS SEE THE "VERTICAL CONCRETE BARRIER RAIL SECTION" DETAIL.


FIXED END

FIXED END


FIXED END




SECTION AT END BENT



SECTION AT BENT




GROUTED RECESS AT END OF POST-TENSIONED STRAND OF CORED SLABS




END ELEVATION

SHOWING PLACEMENT OF DOUBLE STIRRUPS
AND LOCATION OF DOWEL HOLES.
(STRAND LAYOUT NOT SHOWN.)
INTERIOR SLAB UNIT SHOWN-EXTERIOR SLAB
UNIT SIMILAR EXCEPT SHEAR KEY LOCATION.




SHEAR KEY DETAIL

NOTE: OMIT SHEAR KEY ON OUTSIDE FACE
OF EXTERIOR CORED SLABS.




INTERIOR SLAB SECTION (30' UNIT) (9 STRANDS REQUIRED)




INTERIOR SLAB SECTION (45' UNIT) (13 STRANDS REQUIRED)

0.6" Ø LOW RELAXATION STRAND LAYOUT

PERMITTED THREADED INSERT
CAST IN OUTSIDE FACE OF
EXTERIOR UNIT AND
RECESSED 3/8" SIZE TO BE
DETERMINED BY
CONTRACTOR.



THREADED INSERT DETAIL



EXT. SLAB SECTION

(FOR PRESTRESSED STRAND LAYOUT, SEE
INTERIOR SLAB SECTION.)

- BOND SHALL BE BROKEN ON THESE STRANDS FOR A DISTANCE OF 2'-0" FROM END OF CORED SLAB UNIT. SEE STANDARD SPECIFICATIONS, ARTICLE 1078-7.
- OPTIONAL FULL LENGTH DEBONDED STRANDS. THESE STRANDS ARE NOT REQUIRED. IF THE FABRICATOR CHOOSES TO INCLUDE THESE STRANDS IN THE CORED SLAB UNIT, THE STRANDS SHALL BE DEBONDED FOR THE FULL LENGTH OF THE UNIT AT NO ADDITIONAL COST. SEE STANDARD SPECIFICATIONS, ARTICLE 1078-7.

DEBONDING LEGEND

PROJECT NO. 17BP.4.R.65
WAYNE COUNTY
STATION: 15+69.50 -L-


SHEET 1 OF 5




DocuSigned by:
A. Keith Paschal
F8B6AD0B2FC48F...
8/12/2015

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH					
STANDARD 3'-0" X 1'-9" PRESTRESSED CONCRETE CORED SLAB UNIT 90° SKEW					
REVISIONS					SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		
					TOTAL SHEETS 18

ASSEMBLED BY : C.C.WILLIAMS DATE : 7/2015
CHECKED BY : A.K.PASCHAL DATE : 8/2015
DRAWN BY : DGE 5/09
CHECKED BY : BCH 6/09
REV. 8/14 MAA/TMG



PLAN OF UNIT



DETAIL "A"

(TYPICAL EACH END OF UNIT)
NOTE: EXTERIOR UNIT SHOWN - INTERIOR UNIT SIMILAR EXCEPT OMIT #5 S3 BARS.

PROJECT NO. 17BP.4.R.65
WAYNE COUNTY
STATION: 15+69.50 -L-

SHEET 2 OF 5





DocuSigned by:
A. Keith Paschal
8/12/2015

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			S-6
2			4			TOTAL SHEETS 18

ASSEMBLED BY : C.C.WILLIAMS	DATE : 7/2015
CHECKED BY : A.K.PASCHAL	DATE : 8/2015
DRAWN BY : DGE	3/09
CHECKED BY : BCH	3/09
REV. 12/5/11	MAA/AAC
REV. 8/14	MAA/TMG

12-AUG-2015 10:04
S:\DPG\Division4\17BP4R65\CCWilliams\17BP4R65_SMU.CS.dgn
Kpaschal

STD. NO. 21" PCS_30_90S_30L



DETAIL "A"

(TYPICAL EACH END OF UNIT)
NOTE: EXTERIOR UNIT SHOWN - INTERIOR UNIT SIMILAR EXCEPT OMIT #5 S3 BARS.

PLAN OF UNIT

PROJECT No. 17BP.4.R.65
WAYNE COUNTY
STATION: 15+69.50 -L-

SHEET 3 OF 5



DocuSigned by:
A. Keith Paschal
8/12/2015

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

PLAN OF 45' UNIT
27'-10" CLEAR ROADWAY
90° SKEW


ASSEMBLED BY : C.C. WILLIAMS DATE : 7/2015
CHECKED BY : A.K. PASCHAL DATE : 8/2015
DRAWN BY : DGE 3/09
CHECKED BY : BCH 3/09

REV. 12/5/11 MAA/AAC
REV. 8/14 MAA/TMG

12-AUG-2015 10:04
S:\DPG\Division4\17BP4R65\CCWilliams\17BP4R65_SMU_CS.dgn
Kpaschal

REVISIONS						SHEET NO. S-7
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 18
2			4			

STD. NO. 21" PCS_30_90S_45L




FIXED END
(TYPE I - 40 REQ'D)

ELASTOMERIC BEARING DETAILS

ELASTOMER IN ALL BEARINGS SHALL BE 50 DUROMETER HARDNESS.

GUTTERLINE ASPHALT THICKNESS & RAIL HEIGHT		
	ASPHALT OVERLAY THICKNESS	RAIL HEIGHT
	@ MID-SPAN	@ MID-SPAN
30' UNIT	2 ⁵ / ₈ "	3'-8 ⁵ / ₈ "
45' UNIT	2"	3'-8"



ALL BAR DIMENSIONS ARE OUT TO OUT

NOTES

ALL PRESTRESSING STRANDS SHALL BE 7-WIRE LOW RELAXATION GRADE 270 STRANDS AND SHALL CONFORM TO AASHTO M203 EXCEPT FOR SAMPLING REQUIREMENTS WHICH SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.

ALL REINFORCING STEEL CAST WITH THE CORED SLAB SECTIONS SHALL BE GRADE 60 AND SHALL BE INCLUDED IN THE UNIT PRICE BID FOR PRESTRESSED CONCRETE CORED SLABS.

RECESSES FOR TRANSVERSE STRANDS SHALL BE GROUTED AFTER THE TENSIONING OF THE STRANDS.

THE 2¹/₂" Ø DOWEL HOLES AT FIXED ENDS OF SLAB SECTIONS SHALL BE FILLED WITH NON-SHRINK GROUT.

THE BACKER RODS SHALL CONFORM TO THE REQUIREMENTS OF TYPE M BOND BREAKER, SEE SECTION 1028 OF THE STANDARD SPECIFICATIONS.

WHEN CORED SLABS ARE CAST, AN INTERNAL HOLD-DOWN SYSTEM SHALL BE EMPLOYED TO PREVENT VOIDS FROM RISING OR MOVING SIDEWAYS, AT LEAST SIX WEEKS PRIOR TO CASTING CORED SLABS, THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER FOR REVIEW AND COMMENT, DETAILED DRAWINGS OF THE PROPOSED HOLD-DOWN SYSTEM. IN ADDITION TO STRUCTURAL DETAILS, LOCATION AND SPACING OF THE HOLD-DOWNS SHALL BE INDICATED.

ALL REINFORCING STEEL IN THE VERTICAL CONCRETE BARRIER RAIL SHALL BE EPOXY COATED.

PRESTRESSING STRANDS SHALL BE CUT FLUSH WITH THE CORED SLAB UNIT ENDS.

APPLY EPOXY PROTECTIVE COATING TO CORED SLAB UNIT ENDS.

GROOVED CONTRACTION JOINTS, 1/2" IN DEPTH, SHALL BE TOOLED IN ALL EXPOSED FACES OF THE BARRIER RAIL AND IN ACCORDANCE WITH ARTICLE 825-10(B) OF THE STANDARD SPECIFICATIONS. A CONTRACTION JOINT SHALL BE LOCATED AT EACH THIRD POINT BETWEEN BARRIER RAIL EXPANSION JOINTS. ONLY ONE CONTRACTION JOINT IS REQUIRED AT MIDPOINT OF BARRIER RAIL SEGMENTS LESS THAN 20 FEET IN LENGTH AND NO CONTRACTION JOINTS ARE REQUIRED FOR THOSE SEGMENTS LESS THAN 10 FEET IN LENGTH.

FLAME CUTTING OF THE TRANSVERSE POST-TENSIONING STRAND IS NOT ALLOWED.

THE TRANSFER OF LOAD FROM THE ANCHORAGES TO THE CORED SLAB UNIT SHALL BE DONE WHEN THE CONCRETE HAS REACHED A COMPRESSIVE STRENGTH OF NOT LESS THAN THE REQUIRED STRENGTH SHOWN IN THE "CONCRETE RELEASE STRENGTH" TABLE.

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.

THE PERMITTED THREADED INSERTS ARE DETAILED AS AN OPTION FOR THE CONTRACTOR TO ATTACH FALSEWORK AND FORMWORK DURING CONSTRUCTION.

THE PERMITTED THREADED INSERTS IN THE EXTERIOR UNITS SHALL BE SIZED BY THE CONTRACTOR, SPACED AT 4'-0" CENTERS AND GALVANIZED IN ACCORDANCE WITH SECTION 1076 OF THE STANDARD SPECIFICATIONS. STAINLESS STEEL THREADED INSERTS MAY BE USED AS AN ALTERNATE.

THE PERMITTED THREADED INSERTS SHALL BE GROUTED BY THE CONTRACTOR IMMEDIATELY FOLLOWING REMOVAL OF THE FALSEWORK.

THE COST OF THE PERMITTED THREADED INSERTS SHALL BE INCLUDED IN THE PRICE BID FOR THE PRECAST UNITS.

GRADE 270 STRANDS	
	0.6" Ø L.R.
AREA (SQUARE INCHES)	0.217
ULTIMATE STRENGTH (LBS. PER STRAND)	58,600
APPLIED PRESTRESS (LBS. PER STRAND)	43,950

CONCRETE RELEASE STRENGTH	
UNIT	PSI
30' UNIT	4000
45' UNIT	4000

PROJECT NO. 17BP.4.R.65
WAYNE COUNTY
STATION: 15+69.50 -L-



SHEET 4 OF 5



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
STANDARD
3'-0" X 1'-9"
PRESTRESSED CONCRETE
CORED SLAB UNIT
90° SKEW


REVISIONS						SHEET NO. S-8
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 18
2			4			

STD. NO. 21" PCS3_30_90S




SECTION T-T
AT OPEN JOINT AT BENT
(THIS IS TO BE USED WHERE
FOAM JOINT IS NOT USED)

SECTION S-S
AT DAM IN OPEN JOINT
(THIS IS TO BE USED ONLY
WHEN SLIP FORM IS USED)



ELEVATION AT EXPANSION JOINTS



END VIEW

SIDE VIEW

END OF RAIL DETAILS

ASSEMBLED BY : C.C.WILLIAMS	DATE : 7/2015
CHECKED BY : A.K.PASCHAL	DATE : 8/2015
DRAWN BY : DGE 5/09	REV. 11/14
CHECKED BY : BCH 6/09	MAA/TMG

BILL OF MATERIAL FOR ONE 30' CORED SLAB UNIT							
BAR	NUMBER	SIZE	TYPE	EXTERIOR UNIT		INTERIOR UNIT	
				LENGTH	WEIGHT	LENGTH	WEIGHT
B2	2	#4	STR	29'-8"	40	29'-8"	40
S1	8	#5	3	4'-3"	35	4'-3"	35
S2	64	#4	3	5'-4"	228	5'-4"	228
* S3	39	#5	1	5'-7"	227		
REINFORCING STEEL				LBS.	303		303
* EPOXY COATED REINFORCING STEEL				LBS.	227		
5000 P.S.I. CONCRETE				CU. YDS.	4.4		4.4
0.6" Ø L.R. STRANDS				No.	9		9

BILL OF MATERIAL FOR ONE 45' CORED SLAB UNIT							
BAR	NUMBER	SIZE	TYPE	EXTERIOR UNIT		INTERIOR UNIT	
				LENGTH	WEIGHT	LENGTH	WEIGHT
B5	4	#4	STR	23'-3"	62	23'-3"	62
S1	8	#5	3	4'-3"	35	4'-3"	35
S2	94	#4	3	5'-4"	335	5'-4"	335
* S3	54	#5	1	5'-7"	314		
REINFORCING STEEL				LBS.	432		432
* EPOXY COATED REINFORCING STEEL				LBS.	314		
5000 P.S.I. CONCRETE				CU. YDS.	6.5		6.5
0.6" Ø L.R. STRANDS				No.	13		13

DEAD LOAD DEFLECTION AND CAMBER	
	3'-0" x 1'-9"
30' CORED SLAB UNIT	0.6" Ø L.R. STRAND
CAMBER (SLAB ALONE IN PLACE)	1/4" ↑
DEFLECTION DUE TO SUPERIMPOSED DEAD LOAD**	1/8" ↓
FINAL CAMBER	1/8" ↑

** INCLUDES FUTURE WEARING SURFACE

DEAD LOAD DEFLECTION AND CAMBER	
	3'-0" x 1'-9"
45' CORED SLAB UNIT	0.6" Ø L.R. STRAND
CAMBER (SLAB ALONE IN PLACE)	7/8" ↑
DEFLECTION DUE TO SUPERIMPOSED DEAD LOAD**	1/8" ↓
FINAL CAMBER	3/4" ↑

** INCLUDES FUTURE WEARING SURFACE

CORED SLABS REQUIRED			
	NUMBER	LENGTH	TOTAL LENGTH
30' UNIT			
EXTERIOR C.S.	2	30'-0"	60'-0"
INTERIOR C.S.	8	30'-0"	240'-0"
TOTAL	10		300'-0"

CORED SLABS REQUIRED			
	NUMBER	LENGTH	TOTAL LENGTH
45' UNIT			
EXTERIOR C.S.	2	45'-0"	90'-0"
INTERIOR C.S.	8	45'-0"	360'-0"
TOTAL	10		450'-0"

ASSEMBLED BY : C.C.WILLIAMS		DATE : 7/2015	
CHECKED BY : A.K.PASCHAL		DATE : 8/2015	
DRAWN BY : DGE 5/09		REV. 11/14	MAA/TMG
CHECKED BY : BCH 6/09			

12-AUG-2015 10:04
S:\DPG1\Division4\17BP4R65\CCWilliams\17BP4R65.SMU.CS.dgn
kpaschal

PROJECT NO. 17BP.4.R.65
WAYNE COUNTY
STATION: 15+69.50 -L-

SHEET 5 OF 5



DocuSigned by:
A. Keith Paschal
FBB6AD0B2FC48F...
8/12/2015

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH STANDARD 3'-0" X 1'-9" PRESTRESSED CONCRETE CORED SLAB UNIT 90° SKEW						
REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-9
1			3			TOTAL SHEETS
2			4			18

STD. NO. 21" PCS3_30_90S

NOTES

THE GUARDRAIL ANCHOR ASSEMBLY SHALL CONSIST OF A 1/4" HOLD DOWN PLATE AND 7 - 7/8" Ø BOLTS WITH NUTS AND WASHERS.

THE HOLD-DOWN PLATE SHALL CONFORM TO AASHTO M270 GRADE 36. AFTER FABRICATION, THE HOLD-DOWN PLATE SHALL BE HOT-DIP GALVANIZED IN ACCORDANCE WITH AASHTO M111.

BOLTS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A307 AND NUTS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M291. BOLTS, NUTS AND WASHERS SHALL BE GALVANIZED. (AT THE CONTRACTOR'S OPTION, STAINLESS STEEL BOLTS, NUTS AND WASHERS MAY BE USED AS AN ALTERNATE FOR THE 7/8" Ø GALVANIZED BOLTS, NUTS AND WASHERS, THEY SHALL CONFORM TO OR EXCEED THE MECHANICAL REQUIREMENTS OF ASTM A307. THE USE OF THIS ALTERNATE SHALL BE APPROVED BY THE ENGINEER.)




THE GUARDRAIL ANCHOR ASSEMBLY IS REQUIRED AT ALL POINTS WHERE APPROACH GUARDRAIL IS TO BE ATTACHED TO THE END OF BARRIER RAIL. FOR POINTS OF ATTACHMENT, SEE SKETCH.

AFTER INSTALLATION, THE EXPOSED THREAD OF THE BOLT SHALL BE BURRED WITH A SHARP POINTED TOOL.

THE COST OF THE GUARDRAIL ANCHOR ASSEMBLY SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR VERTICAL CONCRETE BARRIER RAIL.

THE VERTICAL REINFORCING BARS MAY BE SHIFTED SLIGHTLY IN THE VERTICAL CONCRETE BARRIER RAIL TO CLEAR ASSEMBLY BOLTS.

THE 1 1/4" Ø HOLES SHALL BE FORMED OR DRILLED WITH A CORE BIT. IMPACT TOOLS WILL NOT BE PERMITTED. ANY CONCRETE DAMAGED BY THIS WORK SHALL BE REPAIRED TO THE SATISFACTION OF THE ENGINEER.



SKETCH SHOWING POINTS OF ATTACHMENT

* DENOTES GUARDRAIL ANCHOR ASSEMBLY

LOCATION OF ANCHORS FOR GUARDRAIL

END BENT #1 SHOWN, END BENT #2 SIMILAR.

PROJECT NO. 17BP.4.R.65
WAYNE COUNTY
STATION: 15+69.50-L-



DocuSigned by:
A. Keith Paschal
F1B6AD0B2FC48F...
8/12/2015

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
STANDARD
GUARDRAIL ANCHORAGE
DETAILS
FOR VERTICAL CONCRETE
BARRIER RAIL

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			S-10
2			4			TOTAL SHEETS 18

(SHT 1) STD. NO. GRA3

ASSEMBLED BY : C.C.WILLIAMS	DATE : 8/2015
CHECKED BY : A.K.PASCHAL	DATE : 8/2015
DRAWN BY : MAA 5/10	REV. 12/5/11 MAA/GM
CHECKED BY : GM 5/10	REV. 6/13 MAA/GM
	REV. 1/15 MAA/TMG


NOTES

STIRRUPS IN CAP MAY BE SHIFTED AS NECESSARY TO CLEAR DOWELS.


THE CONCRETE IN THE SHADED AREA OF THE WING SHALL BE POURED AFTER THE VERTICAL CONCRETE BARRIER RAIL IS CAST IF SLIP FORMING IS USED.

FOR PILE SPLICE DETAILS, SEE SHEET 4 OF 4.

FOR WING DETAILS, SEE SHEET 3 OF 4.



PLAN



ELEVATION

TOP OF PILE ELEVATIONS

①	104.36
②	104.03
③	103.70
④	103.37
⑤	103.04

PROJECT NO. 17BP.4.R.65

WAYNE COUNTY

STATION: 15+69.50 -L-

SHEET 1 OF 4

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

SUBSTRUCTURE
END BENT No. 1



DocuSigned by:
A. Keith Paschal
F8B6AD0B2FC48F...
8/12/2015

ASSEMBLED BY : C.C.WILLIAMS DATE : 7/2015
CHECKED BY : A.K.PASCHAL DATE : 8/2015
DRAWN BY : DGE 01/10
CHECKED BY : MKT 01/10
REV. 4/15 MAA/TMG

WINGS NOT SHOWN FOR CLARITY.
FOR SECTION A-A, SEE SHEET 4 OF 4.
CONCRETE COLLARS FOR STEEL PILES NOT SHOWN IN PLAN AND ELEVATION VIEWS FOR CLARITY.
SEE "CORROSION PROTECTION FOR STEEL PILES DETAIL", SHEET 4 OF 4.

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			S-11
2			4			TOTAL SHEETS 18

STD. NO. EB_30_90S

STIRRUPS IN CAP MAY BE SHIFTED AS
NECESSARY TO CLEAR DOWELS.

THE CONCRETE IN THE SHADED AREA OF THE WING SHALL BE POURED AFTER THE VERTICAL CONCRETE BARRIER RAIL IS CAST IF SLIP FORMING IS USED.

FOR PILE SPLICE DETAILS, SEE SHEET 4 OF 4

FOR WING DETAILS, SEE SHEET 3 OF 4.



WINGS NOT SHOWN FOR CLARITY.
FOR SECTION A-A, SEE SHEET 4 OF 4.
CONCRETE COLLARS FOR STEEL PILES NOT SHOWN IN PLAN AND ELEVATION VIEWS FOR CLARITY.
SEE "CORROSION PROTECTION FOR STEEL PILES DETAIL", SHEET 4 OF 4.

PROJECT NO. 17BP.4.R.65
WAYNE COUNTY
 STATION: 15+69.50 -L-


SHEET 2 OF 4




DocuSigned by:
A. Keith Paschal
F8B6AD6DB2FC48F...
8/12/2015

REVISIONS						SHEET NO. S-12
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 18
2			4			


STD. NO. EB_30_90S




PLAN OF WING (W1)




PLAN OF WING (W2)




ELEVATION OF WING (W1)



ELEVATION OF WING (W2)



SECTION X-X



SECTION Y-Y

ASSEMBLED BY : C.C.WILLIAMS DATE : 7/2015
 CHECKED BY : A.K.PASCHAL DATE : 8/2015
 DRAWN BY : DGE 02/10
 CHECKED BY : MKT 02/10
 REV. 4/15 MAA/TMG

12-AUG-2015 10:04
 S:\DPG\Division4\17BP4R65\CCWilliams\17BP4R65_SMU.CS.dgn
 Kpaschal




DocuSigned by:
 A. Keith Paschal
 8/12/2015

PROJECT NO. 17BP.4.R.65
 WAYNE COUNTY
 STATION: 15+69.50 -L-

SHEET 3 OF 4

REVISIONS						SHEET NO. S-13
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 18
2			4			

STD. NO. EB_30_90S




BAGGED STONE AND PIPE SHALL BE PLACED IMMEDIATELY AFTER COMPLETION OF END BENT EXCAVATION. PIPE MAY BE EITHER CONCRETE, CORRUGATED STEEL, CORRUGATED ALUMINUM ALLOY, OR CORRUGATED PLASTIC. PERFORATED PIPE WILL NOT BE ALLOWED.


BAGGED STONE SHALL REMAIN IN PLACE UNTIL THE ENGINEER DIRECTS THAT IT BE REMOVED. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF SILT ACCUMULATIONS AT BAGGED STONE WHEN SO DIRECTED BY THE ENGINEER. BAGS SHALL BE REMOVED AND REPLACED WHENEVER THE ENGINEER DETERMINES THAT THEY HAVE DETERIORATED AND LOST THEIR EFFECTIVENESS.

NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK AND THE ENTIRE COST OF THIS WORK SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR THE SEVERAL PAY ITEMS.


TEMPORARY DRAINAGE AT END BENT



PILE SPLICE DETAILS




BILL OF MATERIAL FOR ONE END BENT					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	8	#9	1	38'-0"	1034
B2	16	#4	STR	19'-1"	204
B3	9	#4	STR	2'-5"	15
D1	20	#6	STR	1'-6"	45
H1	24	#4	2	7'-10"	126
K1	12	#4	STR	2'-11"	23
S1	46	#4	3	7'-5"	228
S2	46	#4	4	3'-2"	97
S3	10	#4	5	6'-6"	43
V1	48	#4	STR	4'-8"	150
REINFORCING STEEL (FOR ONE END BENT)					1965 LBS.
CLASS A CONCRETE BREAKDOWN (FOR ONE END BENT)					
POUR #1 CAP, LOWER PART OF WINGS & COLLARS					11.2 C.Y.
POUR #2 UPPER PART OF WINGS					1.8 C.Y.
TOTAL CLASS A CONCRETE					13.0 C.Y.




CORROSION PROTECTION FOR STEEL PILES DETAIL

(END BENT No. 1 SHOWN, END BENT No. 2 SIMILAR BY ROTATION)



DETAIL "A"

(END BENT No. 1 SHOWN, END BENT No. 2 SIMILAR BY ROTATION)





NOTES

STIRRUPS IN CAP MAY BE SHIFTED AS NECESSARY
TO CLEAR DOWELS.

★ INVERT ALTERNATE STIRRUPS.

GALVANIZE THE FULL LENGTH OF EACH INTERIOR BENT PILE IN ACCORDANCE WITH SECTION 1076 OF THE STANDARD SPECIFICATIONS.



DETAIL "A"

(DIMENSIONS ARE TYPICAL EACH BEARING)

TOP OF PILE ELEVATIONS	
①	104.37
②	104.18
③	103.98
④	103.79
⑤	103.60
⑥	103.40
⑦	103.21

PROJECT NO. 17BP.4.R.65

WAYNE COUNTY

STATION: 15+69.50 -L-

SHEET 1 OF 2


STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

SUBSTRUCTURE
BENT No. 1

DocuSigned by:
A. Keith Paschal
F8B6AD8DB2FC48F...
8/12/2015

REVISIONS						SHEET NO. S-15
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 18
2			4			

STD. NO. 14" HP_BT_30_90S_<60'





ELEVATION



FOR SECTION A-A, SEE SHEET 2 OF 2

ASSEMBLED BY : C.C.WILLIAMS		DATE : 8/2015	
CHECKED BY : A.K.PASCHAL		DATE : 8/2015	
DRAWN BY : DGE 05/10		REV. 11/14	MAA/TMG
CHECKED BY : MKT 05/10			

12-AUG-2015 10:04
S:\DPC1\Division4\17BP4R65\CCWilliams\17BP4R65_SMU_CS.dgn
kpaschal



BILL OF MATERIAL					
FOR ONE BENT					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	4	#10	1	34'-10"	600
B2	4	#10	STR	32'-2"	554
B3	4	#5	STR	32'-2"	134
B4	8	#4	STR	17'-4"	93
B5	8	#4	STR	2'-11"	16
D1	40	#6	STR	1'-6"	90
S1	32	#5	2	8'-1"	270
S2	14	#4	3	7'-7"	71
U1	4	#4	4	5'-10"	16
U2	6	#4	4	5'-0"	20
U3	2	#9	4	10'-1"	69
REINFORCING STEEL (FOR ONE BENT)					1933 LBS
CLASS A CONCRETE BREAKDOWN (FOR ONE BENT)					
TOTAL CLASS A CONCRETE					9.8 C.Y.
HP 14 X 73 GALVANIZED STEEL PILES (FOR ONE BENT)					
No. 7				LIN. FT.	245
PILE EXCAVATION IN SOIL				LIN. FT.	133
PILE EXCAVATION NOT IN SOIL				LIN. FT.	63



DocuSigned by:
A. Keith Paschal
FBB6AD0B2FC48F...
8/12/2015

PROJECT NO. 17BP.4.R.65
WAYNE COUNTY
STATION: 15+69.50 -L-

SHEET 2 OF 2

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH					
SUBSTRUCTURE					
BENT No. 1					
REVISIONS					
NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		
SHEET NO. S-16					TOTAL SHEETS 18

STD. NO. 14" HP_BT_30_90S_<60'

DRAWN BY : C.C.WILLIAMS	DATE : 8/2015
CHECKED BY : A.K.PASCHAL	DATE : 8/2015
DRAWN BY : DGE 05/10	REV. 11/14
CHECKED BY : MKT 05/10	MAA/TMG

12-AUG-2015 10:04
S:\DPG1\Division4\17BP4R65\CCWilliams\17BP4R65_SMU.CS.dgn
Kpaschal

STANDARD NOTES

DESIGN DATA:

SPECIFICATIONS	- - - - -	A.A.S.H.T.O. (CURRENT)
LIVE LOAD	- - - - -	SEE PLANS
IMPACT ALLOWANCE	- - - - -	SEE A.A.S.H.T.O.
STRESS IN EXTREME FIBER OF		
STRUCTURAL STEEL - AASHTO M270 GRADE 36	-	20,000 LBS. PER SQ. IN.
- AASHTO M270 GRADE 50W	-	27,000 LBS. PER SQ. IN.
- AASHTO M270 GRADE 50	-	27,000 LBS. PER SQ. IN.
REINFORCING STEEL IN TENSION		
	GRADE 60 - -	24,000 LBS. PER SQ. IN.
CONCRETE IN COMPRESSION	- - - - -	1,200 LBS. PER SQ. IN.
CONCRETE IN SHEAR	- - - - -	SEE A.A.S.H.T.O.
STRUCTURAL TIMBER - TREATED OR		
UNTREATED - EXTREME FIBER STRESS	- - - - -	1,800 LBS. PER SQ. IN.
COMPRESSION PERPENDICULAR TO GRAIN OF TIMBER	- - - -	375 LBS. PER SQ. IN.
EQUIVALENT FLUID PRESSURE OF EARTH	- - - - -	30 LBS. PER CU. FT.
		(MINIMUM)

MATERIAL AND WORKMANSHIP:

EXCEPT AS MAY OTHERWISE BE SPECIFIED ON PLANS OR IN THE SPECIAL PROVISIONS, ALL MATERIAL AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE 2012 "STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES" OF THE N. C. DEPARTMENT OF TRANSPORTATION.

STEEL SHEET PILING FOR PERMANENT OR TEMPORARY APPLICATIONS SHALL BE HOT ROLLED.

CONCRETE:

UNLESS OTHERWISE REQUIRED ON PLANS, CLASS A CONCRETE SHALL BE USED FOR ALL PORTIONS OF ALL STRUCTURES WITH THE EXCEPTION THAT: CLASS AA CONCRETE SHALL BE USED IN BRIDGE SUPERSTRUCTURES, ABUTMENT BACKWALLS, AND APPROACH SLABS; AND CLASS B CONCRETE SHALL BE USED FOR SLOPE PROTECTION AND RIP RAP.

CONCRETE CHAMFERS:

UNLESS OTHERWISE NOTED ON THE PLANS, ALL EXPOSED CORNERS ON STRUCTURES SHALL BE CHAMFERED 3/4" WITH THE FOLLOWING EXCEPTIONS: TOP CORNERS OF CURBS MAY BE ROUNDED TO 1-1/2" RADIUS WHICH IS BUILT INTO CURB FORMS; CORNERS OF TRANSVERSE FLOOR EXPANSION JOINTS SHALL BE ROUNDED WITH A 1/4" FINISHING TOOL UNLESS OTHERWISE REQUIRED ON PLANS; AND CORNERS OF EXPANSION JOINTS IN THE ROADWAY FACES AND TOPS OF CURBS AND SIDEWALKS SHALL BE ROUNDED TO A 1/4" RADIUS WITH A FINISHING STONE OR TOOL UNLESS OTHERWISE REQUIRED ON PLANS.

DOWELS:

DOWELS WHEN INDICATED ON PLANS AS FOR CULVERT EXTENSIONS, SHALL BE EMBEDDED AT LEAST 12" INTO THE OLD CONCRETE AND GROUTED INTO PLACE WITH 1:2 CEMENT MORTAR.

ALLOWANCE FOR DEAD LOAD DEFLECTION, SETTLEMENT, ETC. IN CASTING SUPERSTRUCTURES:

BRIDGES SHALL BE BUILT ON THE GRADE OR VERTICAL CURVE SHOWN ON PLANS. SLABS, CURBS AND PARAPETS SHALL CONFORM TO THE GRADE OR CURVE. ALL DIMENSIONS WHICH ARE GIVEN IN SECTION AND ARE AFFECTED BY DEAD LOAD DEFLECTIONS ARE DIMENSIONS AT CENTER LINE OF BEARING UNLESS OTHERWISE NOTED ON PLANS. IN SETTING FORMS FOR STEEL BEAM BRIDGES AND PRESTRESSED CONCRETE GIRDER BRIDGES, ADJUSTMENTS SHALL BE MADE DUE TO THE DEAD LOAD DEFLECTIONS FOR THE ELEVATIONS SHOWN. WHERE BLOCKS ARE SHOWN OVER BEAMS FOR BUILDING UP TO THE SLAB, THE VERTICAL DIMENSIONS OF THE BLOCKS SHALL BE ADJUSTED BETWEEN BEARINGS TO COMPENSATE FOR DEAD LOAD DEFLECTIONS, VERTICAL CURVE ORDINATE, AND ACTUAL BEAM CAMBER. WHERE BOTTOM OF SLAB IS IN LINE WITH BOTTOM OF TOP FLANGES, DEPTH OF SLAB BETWEEN BEARINGS SHALL BE ADJUSTED TO COMPENSATE FOR DEAD LOAD DEFLECTION, VERTICAL CURVE ORDINATE, AND ACTUAL BEAM CAMBER. IN SETTING FALSEWORK AND FORMS FOR REINFORCED CONCRETE SPANS, AN ALLOWANCE SHALL BE MADE FOR DEAD LOAD DEFLECTIONS, SETTLEMENT OF FALSEWORK, AND PERMANENT CAMBER WHICH SHALL BE PROVIDED FOR IN ADDITION TO THE ELEVATIONS SHOWN. AFTER REMOVAL OF THE FALSEWORK, THE FINISHED STRUCTURES SHALL CONFORM TO THE PROFILE AND ELEVATIONS SHOWN ON THE PLANS AND CONSTRUCTION ELEVATIONS FURNISHED BY THE ENGINEER. DETAILED DRAWINGS FOR FALSEWORK OR FORMS FOR BRIDGE SUPERSTRUCTURE AND ANY STRUCTURE OR PARTS OF A STRUCTURE AS NOTED ON THE PLANS SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL BEFORE CONSTRUCTION OF THE FALSEWORK OR FORMS IS STARTED.

REINFORCING STEEL:

ALL REINFORCING STEEL SHALL BE DEFORMED. DIMENSIONS RELATIVE TO PLACEMENT OF REINFORCING ARE TO CENTERS OF BARS UNLESS OTHERWISE INDICATED IN THE PLANS. DIMENSIONS ON BAR DETAILS ARE TO CENTERS OF BARS OR ARE OUT TO OUT AS INDICATED ON PLANS. WIRE BAR SUPPORTS SHALL BE PROVIDED FOR REINFORCING STEEL WHERE INDICATED ON THE PLANS. WHEN BAR SUPPORT PIECES ARE PLACED IN CONTINUOUS LINES, THEY SHALL BE SO PLACED THAT THE ENDS OF THE SUPPORTING WIRES SHALL BE LAPPED TO LOCK LEGS ON ADJOINING PIECES.

STRUCTURAL STEEL:

AT THE CONTRACTOR'S OPTION, HE MAY SUBSTITUTE 7/8" Ø SHEAR STUDS FOR THE ¾" Ø STUDS SPECIFIED ON THE PLANS. THIS SUBSTITUTION SHALL BE MADE AT THE RATE OF 3 - 7/8" Ø STUDS FOR 4 - ¾" Ø STUDS, AND STUD SPACING CHANGES SHALL BE MADE AS NECESSARY TO PROVIDE THE SAME EQUIVALENT NUMBER OF 7/8" Ø STUDS ALONG THE BEAM AS SHOWN FOR ¾" Ø STUDS BASED ON THE RATIO OF 3 - 7/8" Ø STUDS FOR 4 - ¾" Ø STUDS. STUDS OF THE LENGTH SPECIFIED ON THE PLANS MUST BE PROVIDED. THE MAXIMUM SPACING SHALL BE 2'-0". EXCEPT AT THE INTERIOR SUPPORTS OF CONTINUOUS BEAMS WHERE THE COVER PLATE IS IN CONTACT WITH BEARING PLATE, THE CONTRACTOR MAY, AT HIS OPTION, SUBSTITUTE FOR THE COVER PLATES DESIGNATED ON THE PLANS COVER PLATES OF THE EQUIVALENT AREA PROVIDED THESE PLATES ARE AT LEAST 5/16" IN THICKNESS AND DO NOT EXCEED A WIDTH EQUAL TO THE FLANGE WIDTH LESS 2" OR A THICKNESS EQUAL TO 2 TIMES THE FLANGE THICKNESS. THE SIZE OF FILLET WELDS SHALL CONFORM TO THE REQUIREMENTS OF THE CURRENT ANSI/AASHTO/AWS "BRIDGE WELDING CODE". ELECTROSLAG WELDING WILL NOT BE PERMITTED. WITH THE SOLE EXCEPTION OF EDGES AT SURFACES WHICH BEAR ON OTHER SURFACES, ALL SHARP EDGES AND ENDS OF SHAPES AND PLATES SHALL BE SLIGHTLY ROUNDED BY SUITABLE MEANS TO A RADIUS OF APPROXIMATELY 1/16 INCH OR EQUIVALENT FLAT SURFACE AT A SUITABLE ANGLE PRIOR TO PAINTING, GALVANIZING, OR METALLIZING.

HANDRAILS AND POSTS:

METAL STANDARDS AND FACES OF THE CONCRETE END POSTS FOR THE METAL RAIL SHALL BE SET NORMAL TO THE GRADE OF THE CURB, UNLESS OTHERWISE SHOWN ON PLANS. THE METAL RAIL AND TOPS OF CONCRETE POSTS USED WITH THE ALUMINUM RAIL SHALL BE BUILT PARALLEL TO THE GRADE OF THE CURB. METAL HANDRAILS SHALL BE IN ACCORDANCE WITH THE PLANS. RAILS SHALL BE AS MANUFACTURED FOR BRIDGE RAILING. CASTINGS SHALL BE OF A UNIFORM APPEARANCE. FINIS AND OTHER DEFORMATIONS RESULTING FROM CASTING OR OTHERWISE SHALL BE REMOVED IN A MANNER SO THAT A UNIFORM COLORING OF THE COMPLETED CASTING SHALL BE OBTAINED. CASTINGS WITH DISCOLORATIONS OR OF NON-UNIFORM COLORING WILL NOT BE ACCEPTED. CERTIFIED MILL REPORTS ARE REQUIRED FOR METAL RAILS AND POSTS.

SPECIAL NOTES:

GENERALLY, IN CASE OF DISCREPANCY, THIS STANDARD SHEET OF NOTES SHALL GOVERN OVER THE SPECIFICATIONS, BUT THE REMAINDER OF THE PLANS SHALL GOVERN OVER NOTES HEREON, AND SPECIAL PROVISIONS SHALL GOVERN OVER ALL. SEE SPECIFICATIONS ARTICLE 105-4.

ENGLISH

JANUARY, 1990

STD. NO. SN