



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

March 15, 2022

Addendum No. 1

RE: **DD00380**
Halifax County

To Whom It May Concern:


Reference is made to the above-mentioned project. The following additions have been made:

1. Water line relocation may be needed on the project. The utility items have been added to the Proposal Item Sheet. Please replace these pages with the Proposal Item Sheets dated March 15, 2022.

This sheet and attachments shall be made a part of the plans and bid documents and shall be submitted with the bid. Bids submitted without the addenda and attachments will be considered non-responsive.

If there are any questions, please contact me at (252) 640-6433.

Sincerely,

DocuSigned by:

BD9FE36C1AA642B...
03/15/2022

Vickie P. Gardner
Division Four Contract Engineer

VPG/
Attachment

County: Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000910000-N	SP	GENERIC MISCELLANEOUS ITEM BACK HOE	6 HR		
0003	0000910000-N	SP	GENERIC MISCELLANEOUS ITEM EXCAVATOR	6 HR		
0004	0000910000-N	SP	GENERIC MISCELLANEOUS ITEM EXPLORATORY EXCAVATION	4 HR		
0005	0000910000-N	SP	GENERIC MISCELLANEOUS ITEM PIPE TRANSPORT	2 HR		
0006	0000920000-E	SP	GENERIC MISCELLANEOUS ITEM BACKFILL	250 CY		
0007	0000920000-E	SP	GENERIC MISCELLANEOUS ITEM EXCAVATION	350 CY		
0008	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0009	0106000000-E	230	BORROW EXCAVATION	40 CY		
0010	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	110 SY		
0011	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	100 SY		
0012	0314000000-E	SP	SELECT MATERIAL, CLASS ***** CLASS IV	500 TON		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	150 TON		
0014	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	150 SY		
0015	0992000000-E	SP	GENERIC PIPE ITEM INSTALLATION OF 72" PIPE WITH HEADWALL	1 EA		
0016	1330000000-E	607	INCIDENTAL MILLING	20 SY		
0017	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	20 TON		

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	25 TON		
0019	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	3 TON		
0020	3635000000-E	876	RIP RAP, CLASS II	35 TON		
0021	3649000000-E	876	RIP RAP, CLASS B	40 TON		
0022	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	200 SY		
0023	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	200 SF		
0024	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	64 SF		
0025	4422000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN (SHORT TERM)	6 DAY		
0026	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0027	4455000000-N	1150	FLAGGER	6 DAY		
0028	6000000000-E	1605	TEMPORARY SILT FENCE	200 LF		
0029	6012000000-E	1610	SEDIMENT CONTROL STONE	80 TON		
0030	6036000000-E	1631	MATTING FOR EROSION CONTROL	200 SY		
0031	6037000000-E	SP	COIR FIBER MAT	100 SY		
0032	6042000000-E	1632	1/4" HARDWARE CLOTH	60 LF		
0033	6070000000-N	1639	SPECIAL STILLING BASINS	2 EA		
0034	6071010000-E	SP	WATTLE	100 LF		
0035	6071020000-E	SP	POLYACRYLAMIDE (PAM)	3 LB		
0036	6084000000-E	1660	SEEDING & MULCHING	0.3 ACR		
0037	6111000000-E	SP	IMPERVIOUS DIKE	40 LF		

County : Halifax

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6132000000-N	SP	GENERIC EROSION CONTROL ITEM PUMP AROUND OPERATION	1 EA		
0039	5325800000-E	1510	8" WATER LINE	100 LF		
0040	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	618 LB		
0041	5546000000-E	1515	8" VALVE	2 EA		

0955/Mar15/Q3860.3/D124262410000/E41

Total Amount Of Bid For Entire Project :