

**This electronic collection of documents is provided
for the convenience of the user
and is Not a Certified Document –**

**The documents contained herein were originally issued
and sealed by the individuals whose names and license
numbers appear on each page, on the dates appearing
with their signature on that page.**

**This file or an individual page
shall not be considered a certified document.**


09/08/19

4/30/2018
X:\NCDOT\Division 4 Wayne #40\Roadway\Pro\B950040_rdy_tsh.dgn
User:nboayue

TIP PROJECT: 17BP.4.R.85

CONTRACT: DD00250

See Sheet 1A For Index of Sheets
See Sheet 1B For Conventional Plan Sheet Symbols
See Sheet 1C-1 For Survey Control Sheets



STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS


WAYNE COUNTY

LOCATION: BRIDGE NO. 40 ON SR 1513 (RED HILL ROAD)
OVER IVY SWAMP

TYPE OF WORK: GRADING, DRAINAGE, PAVING, AND STRUCTURE


STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	17BP.4.R.85	1	
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	
17BP.4.R.85	N/A	PE	
17BP.4.R.85	N/A	RW, UTIL	
17BP.4.R.85	N/A	CONST.	

NAD 83 NA 2011



DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

GRAPHIC SCALES



DESIGN DATA

ADT 2016 = 280
T = 6 %
V = 60 MPH

FUNC CLASS =
LOCAL-RURAL
SUBREGIONAL TIER

PROJECT LENGTH

LENGTH ROADWAY TIP PROJECT 17BP.4.R.85 = 0.055 mile
LENGTH STRUCTURES TIP PROJECT 17BP.4.R.85 = 0.011 mile
TOTAL LENGTH TIP PROJECT 17BP.4.R.85 = 0.066 mile

Prepared For:
DIVISION OF HIGHWAYS
1000 Birch Ridge Dr., Raleigh NC, 27610



TGS ENGINEERS
706 HILLSBOROUGH ST
SUITE 200
RALEIGH, NC 27603

PH (919) 773-8887
CORP. LICENSE NO.:
C-0275

2018 STANDARD SPECIFICATIONS

RIGHT OF WAY DATE:
JANUARY 30, 2018


LETTING DATE:
MAY 22, 2018

NYA K. BOAYUE, PE
PROJECT ENGINEER

PAUL SCHULKEN, EI
PROJECT DESIGN ENGINEER

RACHEL EVANS, PE
PROJECT ENGINEER
NCDOT DIVISION 4

HYDRAULICS ENGINEER




DocuSigned by:
Benjamin J. Hester
SIGNATURE: P.E. 5/1/2018

ROADWAY DESIGN ENGINEER



DocuSigned by:
Rachel Evans
SIGNATURE: P.E. 5/2/2018



8/17/99

5/1/2018 11:00 AM
X:\CDDT\Division 4 Wayne #40\Roadway\Proj\B950040_rdu_psh_1A.dgn
User: bboone

PROJECT REFERENCE NO.			SHEET NO.		
17BP.4.R.85			1A		
			ROADWAY DESIGN ENGINEER NORTH CAROLINA PROFESSIONAL SEAL 020111 5/2/2018		
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED					
TGS ENGINEERS		TGS ENGINEERS 706 HILLSBOROUGH ST. SUITE 200 RALEIGH, NC 27603 PH (919) 773-8887 CORP. LICENSE NO.: C-0275			

INDEX OF SHEETS		EFF. 01-16-2018		GENERAL NOTES Cont'd:		2018 SPECIFICATIONS	
SHEET NUMBER	SHEET		REV.			EFFECTIVE: 01-16-2018	
1	TITLE SHEET	2018 ROADWAY ENGLISH STANDARD DRAWINGS				REVISED:	
1A	INDEX OF SHEETS, GENERAL NOTES, AND STANDARD DRAWINGS	The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated January, 2018 are applicable to this project and by reference hereby are considered a part of these plans:		SUBSURFACE DRAINS:		SUBSURFACE DRAINS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. NO. 815.02 AT LOCATIONS DIRECTED BY THE ENGINEER.	
1B	CONVENTIONAL SYMBOLS			UNDERDRAINS:		UNDERDRAINS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. NO. 815.03 AT LOCATIONS DIRECTED BY THE ENGINEER.	
2A-1	PAVEMENT SCHEDULE AND TYPICAL SECTIONS	STD.NO.	TITLE	DRIVEWAYS:		DRIVEWAYS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. 848.02 USING 3 FOOT RADII OR RADII AS SHOWN ON THE PLANS. LOCATIONS OF DRIVES WILL BE AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.	
3B-1	ROADWAY SUMMARIES	DIVISION 2 - EARTHWORK 200.02 Method of Clearing - Method II 225.02 Guide for Grading Subgrade - Secondary and Local 225.04 Method of Obtaining Superelevation - Two Lane Pavement 235.01 Embankment Monitoring		GUARDRAIL:		THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.	
3D-1	DRAINAGE SUMMARIES	DIVISION 3 - PIPE CULVERTS 300.01 Method of Pipe Installation 310.10 Driveway Pipe Construction		TEMPORARY SHORING:		SHORING REQUIRED FOR THE MAINTENANCE OF TRAFFIC WILL BE PAID FOR AS "EXTRA WORK" IN ACCORDANCE WITH SECTION 104-7.	
3G-1	GEOTECHNICAL SUMMARIES	DIVISION 4 - MAJOR STRUCTURES 422.02 Bridge Approach Fills - Type II Modified Approach Fill		SUBSURFACE PLANS:		NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.	
4 THRU 6	PLAN AND PROFILE SHEET	DIVISION 5 - SUBGRADE, BASES AND SHOULDERS 560.01 Method of Shoulder Construction - High Side of Superelevated Curve - Method I		END BENTS:		THE ENGINEER SHALL CHECK THE STRUCTURE END BENT PLANS, DETAILS, AND CROSS-SECTION PRIOR TO SETTING OF THE SLOPE STAKES FOR THE EMBANKMENT OR EXCAVATION APPROACHING A BRIDGE.	
RW01 THRU RW05	RIGHT OF WAY SHEETS	DIVISION 6 - ASPHALT BASES AND PAVEMENTS 654.01 Pavement Repairs		UTILITIES:		UTILITY OWNERS ON THIS PROJECT ARE CENTURYLINK STANTONSBURG POWER WAYNE COUNTY WATER ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS.	
TMP-1 THRU TMP-3	TRAFFIC MANAGEMENT PLANS	DIVISION 8 - INCIDENTALS 815.03 Pipe Underdrain and Blind Drain 840.29 Frames and Narrow Slot Flat Grates 840.35 Traffic Bearing Grated Drop Inlet - for Cast Iron Double Frame and Grates 846.04 Drop Inlet Installation in Shoulder Berm Gutter 848.02 Driveway Turnout - Radius Type 862.01 Guardrail Placement 862.02 Guardrail Installation 862.03 Structure Anchor Units 876.02 Guide for Rip Rap at Pipe Outlets		RIGHT-OF-WAY MARKERS:		ALL RIGHT-OF-WAY MARKERS ON THIS PROJECT SHALL BE PLACED BY OTHERS.	
PMP-1	PAVEMENT MARKING PLANS						
EC-1 THRU EC-7	EROSION CONTROL PLANS						
RF-1	REFORESTATION PLANS						
UO-1 THRU UO-3	UTILITIES BY OTHERS PLANS						
X-1A	CROSS-SECTION SUMMARY SHEET						
X-1 THRU X-3	CROSS-SECTIONS						
S-1 THRU S-15	STRUCTURE PLANS						
		GENERAL NOTES:		2018 SPECIFICATIONS			
				EFFECTIVE: 01-16-2018			
				REVISED:			
		GRADE LINE:					
		GRADING AND SURFACING:					
		THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. GRADE LINES MAY BE ADJUSTED AT THEIR BEGINNING AND ENDING AND AT STRUCTURES AS DIRECTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.					
		GRADING:					
		THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED OR FUTURE SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. GRADE LINES MAY BE ADJUSTED AT THEIR BEGINNING AND ENDING AND AT STRUCTURES AS DIRECTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.					
		CLEARING:					
		CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.					
		SUPERELEVATION:					
		ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.					
		SHOULDER CONSTRUCTION:					
		ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01					
		SIDE ROADS:					
		THE CONTRACTOR WILL BE REQUIRED TO DO ALL NECESSARY WORK TO PROVIDE SUITABLE CONNECTIONS WITH ALL ROADS, STREETS, AND DRIVES ENTERING THIS PROJECT. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PARTICULAR ITEMS INVOLVED.					

Note: Not to Scale

**S.U.E. = Subsurface Utility Engineering*

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJECT REFERENCE NO.	SHEET NO.
17BP.4.R.85	1B

CONVENTIONAL PLAN SHEET SYMBOLS

BOUNDARIES AND PROPERTY:

State Line	
County Line	
Township Line	
City Line	
Reservation Line	
Property Line	
Existing Iron Pin	
Property Corner	
Property Monument	
Parcel/Sequence Number	
Existing Fence Line	
Proposed Woven Wire Fence	
Proposed Chain Link Fence	
Proposed Barbed Wire Fence	
Existing Wetland Boundary	
Proposed Wetland Boundary	
Existing Endangered Animal Boundary	
Existing Endangered Plant Boundary	
Known Soil Contamination: Area or Site	
Potential Soil Contamination: Area or Site	

BUILDINGS AND OTHER CULTURE:

Gas Pump Vent or U/G Tank Cap	
Sign	
Well	
Small Mine	
Foundation	
Area Outline	
Cemetery	
Building	
School	
Church	
Dam	

HYDROLOGY:

Stream or Body of Water	
Hydro, Pool or Reservoir	
Jurisdictional Stream	
Buffer Zone 1	
Buffer Zone 2	
Flow Arrow	
Disappearing Stream	
Spring	
Wetland	
Proposed Lateral, Tail, Head Ditch	
False Sump	

RAILROADS:

Standard Gauge	
RR Signal Milepost	
Switch	
RR Abandoned	
RR Dismantled	

RIGHT OF WAY:

Baseline Control Point	
Existing Right of Way Marker	
Existing Right of Way Line	
Proposed Right of Way Line	
Proposed Right of Way Line with Iron Pin and Cap Marker	
Proposed Right of Way Line with Concrete or Granite RW Marker	
Proposed Control of Access Line with Concrete C/A Marker	
Existing Control of Access	
Proposed Control of Access	
Existing Easement Line	
Proposed Temporary Construction Easement	
Proposed Temporary Drainage Easement	
Proposed Permanent Drainage Easement	
Proposed Permanent Drainage / Utility Easement	
Proposed Permanent Utility Easement	
Proposed Temporary Utility Easement	
Proposed Aerial Utility Easement	

Proposed Permanent Easement with Iron Pin and Cap Marker

ROADS AND RELATED FEATURES:

Existing Edge of Pavement	
Existing Curb	
Proposed Slope Stakes Cut	
Proposed Slope Stakes Fill	
Proposed Curb Ramp	
Existing Metal Guardrail	
Proposed Guardrail	
Existing Cable Guiderail	
Proposed Cable Guiderail	

Equality Symbol	
Pavement Removal	

VEGETATION:

Single Tree	
Single Shrub	
Hedge	
Woods Line	

Orchard	
Vineyard	

EXISTING STRUCTURES:

MAJOR:	
Bridge, Tunnel or Box Culvert	
Bridge Wing Wall, Head Wall and End Wall	
MINOR:	
Head and End Wall	
Pipe Culvert	
Footbridge	
Drainage Box: Catch Basin, DI or JB	
Paved Ditch Gutter	
Storm Sewer Manhole	
Storm Sewer	

UTILITIES:

POWER:	
Existing Power Pole	
Proposed Power Pole	
Existing Joint Use Pole	
Proposed Joint Use Pole	
Power Manhole	
Power Line Tower	
Power Transformer	
U/G Power Cable Hand Hole	
H-Frame Pole	
Recorded U/G Power Line	
Designated U/G Power Line (S.U.E.*)	

TELEPHONE:

Existing Telephone Pole	
Proposed Telephone Pole	
Telephone Manhole	
Telephone Booth	
Telephone Pedestal	
Telephone Cell Tower	
U/G Telephone Cable Hand Hole	
Recorded U/G Telephone Cable	
Designated U/G Telephone Cable (S.U.E.*)	
Recorded U/G Telephone Conduit	
Designated U/G Telephone Conduit (S.U.E.*)	
Recorded U/G Fiber Optics Cable	
Designated U/G Fiber Optics Cable (S.U.E.*)	

WATER:

Water Manhole	
Water Meter	
Water Valve	
Water Hydrant	
Recorded U/G Water Line	
Designated U/G Water Line (S.U.E.*)	
Above Ground Water Line	

TV:

TV Satellite Dish	
TV Pedestal	
TV Tower	
U/G TV Cable Hand Hole	
Recorded U/G TV Cable	
Designated U/G TV Cable (S.U.E.*)	
Recorded U/G Fiber Optic Cable	
Designated U/G Fiber Optic Cable (S.U.E.*)	

GAS:

Gas Valve	
Gas Meter	
Recorded U/G Gas Line	
Designated U/G Gas Line (S.U.E.*)	
Above Ground Gas Line	

SANITARY SEWER:

Sanitary Sewer Manhole	
Sanitary Sewer Cleanout	
U/G Sanitary Sewer Line	
Above Ground Sanitary Sewer	
Recorded SS Forced Main Line	
Designated SS Forced Main Line (S.U.E.*)	

MISCELLANEOUS:


Utility Pole	
Utility Pole with Base	
Utility Located Object	
Utility Traffic Signal Box	
Utility Unknown U/G Line	
U/G Tank; Water, Gas, Oil	
Underground Storage Tank, Approx. Loc.	
A/G Tank; Water, Gas, Oil	
Geoenvironmental Boring	
U/G Test Hole (S.U.E.*)	
Abandoned According to Utility Records	
End of Information	

6/2/2018


4/30/2018 11:00 AM X:\Roadway\Division 4 Wayne #40\Roadway\Proj\B950040_rdu_tup.dgn User:boalm

PAVEMENT SCHEDULE	
C1	PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.
C2	PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.
C3	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 112 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT TO EXCEED 2" IN DEPTH.
E1	PROP. APPROX. 4" ASPHALT CONCRETE BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.
E2	PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0C, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 3" IN DEPTH OR GREATER THAN 5½" IN DEPTH.
R1	SHOULDER BERM GUTTER
T	EARTH MATERIAL
U	EXISTING PAVEMENT
V	MILLING EXISTING PAVEMENT (SEE MILLING DETAILS THIS SHEET)
W	VARIABLE DEPTH ASPHALT PAVEMENT (SEE WEDGING DETAILS THIS SHEET)

NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.




Detail Showing Method of Wedging



USE MILLING DETAIL AS FOLLOWS:

MILLING AND RESURFACING AT TIE-INS:
-L- STA. 13+50.00 TO -L- STA. 13+75.00
-L- STA. 16+75.00 TO -L- STA. 17+00.00


NOTE:
PERFORM ADDITIONAL MILLING OPERATIONS AS NEEDED
FROM STA. 13+75.00 TO 14+30.00. SEE PROFILE SHEET 6.



TYPICAL SECTION NO. 1

USE TYPICAL SECTION NO. 1


-L- STA. 13+50.00 TO -L- STA. 14+30.00
-L- STA. 15+85.00 TO -L- STA. 17+00.00



TYPICAL SECTION NO. 2

USE TYPICAL SECTION NO. 2

-L- STA. 14+30.00 TO -L- STA. 14+76.88 (BEGIN BRIDGE)
-L- STA. 15+34.13 (END BRIDGE) TO -L- STA. 15+85.00




TYPICAL SECTION NO. 3

USE TYPICAL SECTION NO. 3

-L- STA. 14+76.88 TO -L- STA. 15+34.13

FULL DEPTH PAVED SHOULDER



INSET A


MIRROR FOR LEFT SIDE

USE INSET A

-L- STA. 13+50.00 TO -L- STA. 14+49.00 LT (BEGIN SHOULDER BERM GUTTER)
-L- STA. 16+00.00 (END SHOULDER BERM GUTTER) TO -L- STA. 16+60.33 LT

-L- STA. 13+50.67 TO -L- STA. 14+49.00 RT (BEGIN SHOULDER BERM GUTTER)
-L- STA. 16+00.00 (END SHOULDER BERM GUTTER) TO -L- STA. 16+60.33 RT

SHOULDER BERM GUTTER



INSET B

MIRROR FOR LEFT SIDE

USE INSET B

-L- STA. 14+49.00 TO -L- STA. 14+66.00 (BEGIN APPROACH SLAB) (LT/RT)
-L- STA. 15+45.00 (END APPROACH SLAB) TO -L- STA. 16+00.00 (LT/RT)

COMPUTED BY: PAS PAS DATE: 21 NOV 2017
CHECKED BY: NKB DATE: 3 MAR 2018

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJECT REFERENCE NO.	SHEET NO.
<i>17BP.4R.85</i>	<i>3B-1</i>
 TGS ENGINEERS 706 HILLSBOROUGH ST. SUITE 200 RALEIGH, NC 27603 PH (919) 773-8887 CORP. LICENSE NO.: C-0275	

SUMMARY OF EARTHWORK

IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBT + 25%	BORROW	WASTE
-L- 13+00.00 TO 14+76.88 (BEGIN BRIDGE)	55		16		39
-L- 15+34.13 (END BRIDGE) TO 17+00.00	18		13		6
SUBTOTAL	73		29		44
MATERIAL FOR SHOULDER CONSTRUCTION			31	*31	
PROJECT TOTAL	73		60	31	44
EST. 5% TO REPLACE TOP SOIL ON BORROW PIT				2	
GRAND TOTAL	73		60	33	44
SAY	80			40	

Earthwork quantities are calculated by the Roadway Design Unit. These earthwork quantities are based in part on subsurface data provided by the Geotechnical Engineering Unit.

Approximate quantities only. Clearing and Grubbing, Unclassified Excavation, Borrow Excavation, Fine Grading, and Removal of Existing Asphalt Pavement will be paid for at the contract lump sum price for "Grading".

* UNCLASSIFIED EXCAVATION INCLUDES 52 CY OF PAVEMENT REMOVAL UNSUITABLE FOR SHOULDER CONSTRUCTION

PER "GEOTECHNICAL REPORT - DESIGN AND CONSTRUCTION RECOMMENDATIONS"
DATED FEBRUARY 19, 2018.

ESTIMATED UNDERCUT	= 300 CY	(CONTINGENCY, AS DIRECTED BY THE ENGINEER)
SELECT GRANULAR MATERIAL	= 450 CY	(CONTINGENCY, TO BE USED AS UNDERCUT AREAS BACKFILL)
DDE	= 30 CY	

PAVEMENT REMOVAL SUMMARY

IN SQUARE YARDS

SURVEY LINE	STATION	STATION	LOCATION LT/RT/CL	SY
-L-	14 + 30	14 + 91	CL	136.69
-L-	15 + 26	15 + 85	CL	129.47
TOTAL:				266.16
SAY:				270

SHOULDER BERM GUTTER SUMMARY

SURVEY LINE	STATION	STATION	LOCATION	LENGTH (LF)
-L-	14 + 49.00	14 + 66.00	LT	17.00'
-L-	15 + 45.00	16 + 00.00	LT	55.00'
-L-	14 + 49.00	14 + 66.00	RT	17.00'
-L-	15 + 45.00	16 + 00.00	RT	55.00'
TOTAL:				144
SAY:				144

"N" = DISTANCE FROM EDGE OF LANE TO FACE OF GUARDRAIL.
 TOTAL SHOULDER WIDTH = DISTANCE FROM EDGE OF TRAVEL LANE TO SHOULDER BREAK POINT.
 FLARE LENGTH = DISTANCE FROM LAST SECTION OF PARALLEL GUARDRAIL TO END OF GUARDRAIL.
 W = TOTAL WIDTH OF FLARE FROM BEGINNING OF TAPER TO END OF GUARDRAIL.
 G = GATING IMPACT ATTENUATOR TYPE 350
 NG = NON-GATING IMPACT ATTENUATOR TYPE 350

GUARDRAIL SUMMARY

[illegible]

[illegible]

COMPUTED BY: Tyler C. Bottoms DATE: 2/14/18
CHECKED BY: DATE:

PROJECT NO.	SHEET NO.
17BP.4.R.85	3G-1

(1-16-18)

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS


SUMMARY OF SUBSURFACE DRAINAGE

LINE	Station	Station	Location LT/RT/CL	Drain Type* UD/BD/SD	LF
CONTINGENCY				SD	200
				TOTAL LF:	200

*UD = Underdrain
*BD = Blind Drain
*SD = Subsurface Drain


1

BM#|



SEE SHEET 6 FOR -L- PROFILE

8/17/99
4/30/2018
X:\Roadway\Division 4 Wayne #40\Roadway\Proj\B50040_rdu\psh_05.dgn
User: bboone




HELEN GAIL PARKER DAVIS
DB 89E PG 622


NAD 83 NA 2011

PROJECT REFERENCE NO. 17BP.4.R.85		SHEET NO. 05	
RW SHEET NO.			
ROADWAY DESIGN ENGINEER SEAL 020111 5/2/2018		HYDRAULICS ENGINEER SEAL 044158 5/2/2018	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED			
TGS ENGINEERS 706 HILLSBOROUGH ST. SUITE 200 RALEIGH, NC 27603 PH (919) 773-8887 CORP. LICENSE NO.: C-0275		TGS ENGINEERS 706 HILLSBOROUGH ST. SUITE 200 RALEIGH, NC 27603 PH (919) 773-8887 CORP. LICENSE NO.: C-0275	

MATCH LINE -L- STA. 14+60.00
SEE SHEET NO. 4





RONALD B LANCASTER, ET AL.
DB 1751 PG 499



SEE SHEET 6 FOR -L- PROFILE

FOR STRUCTURE PLANS, SEE SHEET S-1 THRU S-15

5/14/99
4/30/2018
X:\CADD\Division 4 Wayne *40\Roadway\Proj\9950040_rdy_psh_06.dgn
User: rchabrowne

PROJECT REFERENCE NO. 17BP.4.R.85		SHEET NO. 06
ROADWAY DESIGN ENGINEER  5/2/2018	HYDRAULICS ENGINEER  5/1/2018	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED		


BRIDGE HYDRAULIC DATA

DESIGN DISCHARGE = 440 CFS
DESIGN FREQUENCY = 25 YRS
DESIGN HW ELEVATION = 67.6 FT
BASE DISCHARGE = 650 CFS
BASE FREQUENCY = 100 YRS
BASE HW ELEVATION = 68.3 FT
OVERTOPPING DISCHARGE = - CFS
OVERTOPPING FREQUENCY = >500(+) YRS
OVERTOPPING ELEVATION = 71.4 FT*

*OVERTOPPING ELEVATION REPRESENTS
LOWEST HIGH POINT ON DECK/ROADWAY
WHICH OCCURS AT SAG @ -L- STA.17+00

DATE OF SITE VISIT = 10/25/17
APPROX. W.S. ELEVATION
ON DATE OF SITE VISIT = 62.3 FT

BRIDGE STA = 15+05.50 -L-
ELEV. = 72.53'
2" CORED SLAB SECTIONS
SKEW = 90°00'00"
SPAN = 1@57'-3"



SEE SHEETS 4 & 5 FOR -L- PLAN

02-MAY-2018 07:22
M:\2018\351800284 NCDOT\J-950040 Div4 Ivy Swamp ROW Staking\DELIVERABLES\4-10-2018\950040_ls_rw01.dgn
\$\$\$\$\$USERNAME\$\$\$\$\$

09/08/99

TIP PROJECT: 95-0040

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

RIGHT OF WAY, EASEMENTS
AND PROPERTY TIES

WILSON COUNTY


LOCATION: BRIDGE 40 OVER IVY SWAMP ON SR 1513
(RED HILL ROAD)
TYPE OF WORK: BRIDGE REPLACEMENT

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	95-0040	1	



BEGIN TIP PROJECT 950040

-L- STA. 10+00.00



END TIP PROJECT 950040

-L- STA. 20+15.70



DATUM DESCRIPTION

THE LOCALIZED COORDINATE SYSTEM DEVELOPED FOR THIS PROJECT IS BASED ON THE STATE PLANE COORDINATES ESTABLISHED BY NCDOT FOR MONUMENT "950040-2" WITH NAD 83/NA 2011 STATE PLANE GRID COORDINATES OF NORTHING: 669066.518(±) EASTING: 2341780.844(±) ELEVATION: 97.274(±) THE AVERAGE COMBINED GRID FACTOR USED ON THIS PROJECT (GROUND TO GRID) IS: 0.99988981 THE N.C. LAMBERT GRID BEARING AND LOCALIZED HORIZONTAL GROUND DISTANCE FROM "950040-2" TO -L- STATION 10+00.00 IS N 89° 22' 24.06" E 547.53' ALL LINEAR DIMENSIONS ARE LOCALIZED HORIZONTAL DISTANCES VERTICAL DATUM USED IS NAVD 88

Prepared in the Office of:
DIVISION OF HIGHWAYS
1000 Birch Ridge Dr., Raleigh NC, 27610


2017 STANDARD SPECIFICATIONS

RIGHT OF WAY DATE:

LETTING DATE:

PROFESSIONAL LAND
SURVEYOR

SIGNATURE:



SURVEY CONTROL SHEET
W/ EXISTING CENTERLINE ALIGNMENTS PRIOR TO CONSTRUCTION

BENCHMARK DATA

BM1 ELEVATION = 69.58
N 669001 E 2342695
BENCH TIE NAIL IN 24" OAK

BM2 ELEVATION = 69.04
N 669094 E 2343115
BENCH TIE NAIL IN 10" OAK

BASELINE DATA

BL	POINT	DESC.	NORTH	EAST	ELEVATION
1		GPS-1	669076.0220	2341068.3530	109.91
2		GPS-2	669066.5180	2341780.8440	97.27
101		BL-101	669060.7800	2342274.8125	84.52
102		BL-102	669055.2973	2342798.9346	72.24
103		BL-103	669047.2018	2343343.8220	73.31

ALIGNMENT DATA

EL				
POINT	N	E	BEARING	DIST
POT	669072.506	2342328.344		
LINE			S 89°16'53.2" E	1015.70
POT	669059.769	2343343.965		

- NOTES:
- PROJECT CONTROL WAS ESTABLISHED USING GNSS, THE GLOBAL NAVIGATION SATELLITE SYSTEM.
 - THE SURVEY CONTROL DATA FOR THIS PROJECT HAS BEEN COMPILED FROM VARIOUS SOURCES. IF FURTHER INFORMATION REGARDING PROJECT CONTROL IS NEEDED, PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.

6/2/99

REVISIONS

REVISIONS

05-APR-2018 1:55 PM J:\Projects\950040\Drawings\950040-1a-rw02c-2.dgn
\$\$\$\$\$SYTIME\$\$\$\$\$

PROPOSED ALIGNMENT CONTROL SHEET

L				
POINT	N	E	BEARING	DIST
POT	669072.506	2342328.344		
LINE			S 89°16'53.2" E	1015.70
POT	669059.769	2343343.965		

NOTES:

1. PROJECT CONTROL WAS ESTABLISHED USING GNSS, THE GLOBAL NAVIGATION SATELLITE SYSTEM.
2. THE PROPOSED ALIGNMENT CONTROL DATA FOR THIS PROJECT HAS BEEN COMPILED FROM VARIOUS SOURCES. IF FURTHER INFORMATINO REGARDING PROJECT CONTROL IS NEEDED, PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.

REVISIONS

02-MAY-2008 08:00 NCDOT\J-950040 Div4 Ivg Swc\p ROW Staking\DRAWINGS\950040.lis.rw02d-1.dgn
\$\$\$\$\$SYTIME\$\$\$\$\$

6/2/99


6/2/99

REVISIONS

02-MAY-2008 08:54 NCDOT\J-950040 Div4 Ivg Swc\p ROW Staking\DRAWINGS\950040.ls-rw02e-1.dgn
\$\$\$\$\$PERMANENT\$\$\$\$\$

RIGHT OF WAY CONTROL SHEET

PROJECT REFERENCE NO.	SHEET NO.
95-0040	RW02E-1
Location and Surveys	



I, JAMES M. GELLENTHIN, a Professional Land Surveyor in the state of North Carolina hereby certify to the best of my knowledge and belief that the following work item(s) (R/W Staking) performed under my responsible charge meet NCDOT Survey Standards as directed in the NCDOT Location & Surveys guidelines and procedures.

I further certify that the right of way and permanent easement points shown herein and outlined in the tables shown hereon (localized coordinates, station/offset) have been checked and are accurate representations of the right of way and permanent easement points depicted on the corresponding highway plans. I also certify that the right of way and permanent easement points shown herein have been field monumented under my supervision from existing survey control provided by others; that the depicted property data shown herein were surveyed by others; and these monuments denote the right of way and easement boundaries at the time of staking which may be subject to change due to right of way revisions (See deeds for final determination).

Witness my original signature, registration number and seal this 2nd day of May, 2018.

Professional Land Surveyor

L-3860
PLS * Seal


ROW MARKER PERMANENT EASEMENT - E

ALIGN	STATION	OFFSET	NORTH	EAST
L	13+65.00	-30.00	669097.9270	2342693.7000
L	14+22.00	-30.00	669097.2080	2342750.6930
L	14+22.00	-36.00	669103.2160	2342750.7540
L	14+50.00	-72.00	669138.8620	2342779.2070
L	14+59.00	-54.00	669120.7530	2342787.9910
L	15+87.00	30.00	669035.1460	2342914.9310
L	15+87.00	55.00	669010.1480	2342914.6190
L	16+07.00	55.00	669009.9020	2342934.5980
L	16+07.00	30.00	669034.8880	2342934.9190

- NOTES:
- 1. IF FURTHER INFORMATION REGARDING PROJECT CONTROL IS NEEDED, PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.
 - 2. PROJECT CONTROL WAS ESTABLISHED USING GNSS, THE GLOBAL NAVIGATION SATELLITE SYSTEM.

SURVEY CONTROL SHEET

W/ EXISTING CENTERLINE ALIGNMENTS PRIOR TO CONSTRUCTION



NC GRID
NAD 83 NA 2011

I, James M Gellenthin, a Professional Land Surveyor in the state of North Carolina hereby certify to the best of my knowledge and belief that the following work item(s) (R/W Staking) performed under my responsible charge meet NCDOT Survey Standards as directed in the NCDOT Location & Surveys guidelines and procedures.

I further certify that the right of way and permanent easement points shown herein and outlined in the tables shown hereon (localized coordinates, station/offset) have been checked and are accurate representations of the right of way and permanent easement points depicted on the corresponding highway plans. I also certify that the right of way and permanent easement points shown herein have been field monumented under my supervision from existing survey control provided by others; that the depicted property data shown herein were surveyed by others; and these monuments denote the right of way and easement boundaries at the time of staking which may be subject to change due to right of way revisions (See deeds for final determination).

Witness my original signature, registration number and seal this 9th day of April, 2018.



Professional Land Surveyor

L-3860
PLS ■

Seal



NOTES:

REVISIONS


6/2/99

09-APR-2018 14:03
NCDOIT\J-950040 Div4 Ivy Swamp ROW Staking\DELIVERABLES\4-9-2018\B950040_1s-rw04.dgn
Matthew
12-EZDFC2


STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

TRANSPORTATION MANAGEMENT PLAN

WAYNE COUNTY
BRIDGE #950040



NCDOT CONTACT INFORMATION:
Phone: 252 640 6434 Fax: 252 234 6174
RACHEL EVANS, PE
Project Manager




PLAN PREPARED FOR N.C.D.O.T. BY:



TGS ENGINEERS
804-C N. LAFAYETTE ST
SHELBY, NC 28150
PH (704) 476-0003
CORP. LICENSE NO.: C-0275

NYA K. BOAYUE, PE PROJECT ENGINEER
PAUL SCHULKEN, EI DESIGN ENGINEER




INDEX OF SHEETS

SHEET NO.	TITLE
TMP-1	TITLE SHEET, VICINITY MAP, AND INDEX OF SHEETS
TMP-1A	LIST OF APPLICABLE ROADWAY STANDARD DRAWINGS, AND LEGEND
TMP-1B	TRANSPORTATION OPERATIONS PLAN: (MANAGEMENT STRATEGIES, GENERAL NOTES, AND LOCAL NOTES)
TMP-1C	SPECIAL SIGN DESIGN
TMP-2	OVERVIEW AND PHASING
TMP-3	OFFSITE DETOUR LOCATION AND BARRICADE PLACEMENT
PMP-1	FINAL PAVEMENT MARKING PLAN AND SCHEDULE

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

APPROVED: _____
DATE: _____



SHEET NO.
TMP-1

PROJECT: 17BP.4.R.85

PROJ. REFERENCE NO.	SHEET NO.
17BP.4.R.85	TMP-1A

TCS
ENGINEERS

TCS ENGINEERS
804-C N. LAFAYETTE ST
SHELBY, NC 28150
PH (704) 476-0003
CORP. LICENSE NO.: C-0275


ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS SHOWN IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1101.01	WORK ZONE ADVANCE WARNING SIGNS
1101.02	TEMPORARY LANE CLOSURES
1101.03	TEMPORARY ROAD CLOSURES
1101.11	TRAFFIC CONTROL DESIGN TABLES
1110.01	STATIONARY WORK ZONE SIGNS
1110.02	PORTABLE WORK ZONE SIGNS
1130.01	DRUM
1135.01	CONES
1145.01	BARRICADES
1150.01	FLAGGING DEVICES
1165.01	WORK VEHICLE LIGHTING SYSTEMS AND TMA DELINEATION
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - TWO-LANE AND MULTI-LANE ROADWAYS
1205.12	PAVEMENT MARKINGS - BRIDGES
1261.01	GUARDRAIL AND BARRIER DELINEATORS - INSTALLATION SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATORS - TYPES AND MOUNTING
1262.01	GUARDRAIL END DELINEATION


LEGEND

GENERAL

-  DIRECTION OF TRAFFIC FLOW
-  DIRECTION OF PEDESTRIAN TRAFFIC FLOW
-  EXIST. PVMT.
-  NORTH ARROW
-  PROPOSED PVMT.
-  TEMP. SHORING (LOCATION PURPOSES ONLY)




SIGNALS

-  EXISTING
-  PROPOSED
-  TEMPORARY

PAVEMENT MARKINGS

-  EXISTING LINES
-  TEMPORARY LINES

TRAFFIC CONTROL DEVICES

-  BARRICADE (TYPE III)
-  CONE
-  DRUM
-  SKINNY DRUM
-  TUBULAR MARKER
-  TEMPORARY CRASH CUSHION
-  FLASHING ARROW BOARD
-  FLAGGER
-  LAW ENFORCEMENT
-  TRUCK MOUNTED ATTENUATOR (TMA)
-  CHANGEABLE MESSAGE SIGN

TEMPORARY SIGNING

-  PORTABLE SIGN
-  STATIONARY SIGN
-  STATIONARY OR PORTABLE SIGN

PAVEMENT MARKERS

-  CRYSTAL/CRYSTAL
-  CRYSTAL/RED
-  YELLOW/YELLOW

PAVEMENT MARKING SYMBOLS


-   
- PAVEMENT MARKING SYMBOLS


APPROVED: _____

DATE: _____

DocuSigned by:

5/2/2018 10:22:40P...





ROADWAY STANDARD
DRAWINGS & LEGEND

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

PROJ. REFERENCE NO.	SHEET NO.
17BP.4.R.85	TMP-1B
 TGS SHELBY 804-C N. LAFAYETTE ST SHELBY, NC 28150 PH (704) 476-0003 CORP. LICENSE NO.: C-0275	

GENERAL NOTES

CHANGES MAY BE REQUIRED WHEN PHYSICAL DIMENSIONS IN THE DETAIL DRAWINGS, STANDARD DETAILS, AND ROADWAY DETAILS ARE NOT ATTAINABLE TO MEET FIELD CONDITIONS OR RESULT IN DUPLICATE OR UNDESIRE

OVERLAPPING OF DEVICES. MODIFICATION MAY INCLUDE: MOVING, SUPPLEMENTING, COVERING, OR REMOVAL OF DEVICES AS DIRECTED BY THE ENGINEER.

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT EXCEPT WHEN OTHERWISE NOTED IN THE PLAN OR DIRECTED BY THE ENGINEER.

TRAFFIC PATTERN ALTERATIONS

- A) THE CONTRACTOR SHALL PROVIDE ONE MONTH NOTICE TO THE ENGINEER, COUNTY EMS AND COUNTY SCHOOL OFFICIALS PRIOR TO ROAD CLOSURES.

SIGNING

- B) INSTALL ADVANCE WORK ZONE WARNING SIGNS WHEN WORK IS WITHIN 40 FT FROM THE EDGE OF TRAVEL LANE AND NO MORE THAN THREE (3) DAYS PRIOR TO THE BEGINNING OF CONSTRUCTION.

- C) PROVIDE SIGNING AND DEVICES REQUIRED TO CLOSE THE ROAD ACCORDING TO THE ROADWAY STANDARD DRAWINGS AND TRAFFIC CONTROL PLANS.

PROVIDE SIGNING REQUIRED FOR THE OFF-SITE DETOUR ROUTE AS SHOWN IN THE TRAFFIC CONTROL PLANS.

- D) COVER OR REMOVE ALL SIGNS AND DEVICES REQUIRED TO CLOSE THE ROAD WHEN ROAD CLOSURE IS NOT IN OPERATION.

COVER OR REMOVE ALL SIGNS REQUIRED FOR THE OFF-SITE DETOUR WHEN THE DETOUR IS NOT IN OPERATION.

- E) ENSURE ALL NECESSARY SIGNING IS IN PLACE PRIOR TO ALTERING ANY TRAFFIC PATTERN.

TRAFFIC BARRIERS

- F) INSTALL TEMPORARY TRAFFIC BARRIER SYSTEM A MAXIMUM OF TWO (2) WEEKS PRIOR TO BEGINNING WORK IN ANY LOCATION. ONCE THE TEMPORARY TRAFFIC BARRIER SYSTEM IS INSTALLED AT ANY LOCATION, PROCEED IN A CONTINUOUS MANNER TO COMPLETE THE PROPOSED WORK IN THAT LOCATION.

TRAFFIC CONTROL DEVICES

- G) PLACE TYPE III BARRICADES, WITH "ROAD CLOSED" SIGN R11-2 ATTACHED, OF SUFFICIENT LENGTH TO CLOSE ENTIRE ROADWAY.

GENERAL NOTES

PAVEMENT MARKINGS AND MARKERS

- H) INSTALL PAVEMENT MARKINGS ON THE FINAL SURFACE AS SHOWN IN THE PAVEMENT MARKING PLAN. (SEE NOTE ON PASSING ZONES, SHEET PMP-1)

- I) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.

- J) REMOVE ANY CONFLICTING MARKINGS OR MARKERS BEFORE SHIFTING TRAFFIC TO A NEW PATTERN.

LANE AND SHOULDER CLOSURE REQUIREMENTS

- K) WHEN PERSONNEL AND/OR EQUIPMENT ARE WORKING WITHIN 15 FT OF AN OPEN TRAVEL LANE, CLOSE THE NEAREST OPEN SHOULDER USING ROADWAY STANDARD DRAWING NO. 1101.04 UNLESS THE WORK AREA IS PROTECTED BY BARRIER OR GUARDRAIL OR A LANE CLOSURE IS INSTALLED.

- L) WHEN PERSONNEL AND/OR EQUIPMENT ARE WORKING ON THE SHOULDER ADJACENT TO AN UNDIVIDED FACILITY AND WITHIN 5 FT OF AN OPEN TRAVEL LANE, CLOSE THE NEAREST OPEN TRAVEL LANE USING ROADWAY STANDARD DRAWING NO. 1101.02 UNLESS THE WORK AREA IS PROTECTED BY BARRIER OR GUARDRAIL.

MANAGEMENT STRATEGIES

DURING CONSTRUCTION OF THE PROPOSED STRUCTURE, SR 1513 (RED HILL ROAD) WILL BE CLOSED TO THROUGH TRAFFIC. SR 1513 (RED HILL ROAD) TRAFFIC WILL BE MAINTAINED ON THE FOLLOWING DETOUR: FROM SR 1514 (ST. JAMES CHURCH ROAD) TO 1631 (ST. JAMES CHURCH ROAD) TO SR 1632 (PELT ROAD) TO NC 111 / NC 222.

COORDINATE CONSTRUCTION ACTIVITES OF THIS PROJECT WITH 17BP.4.R.86 SO THAT BRIDGE NO. 950040 AND BRIDGE NO. 970016 ARE NOT CLOSED TO TRAFFIC AT THE SAME TIME.

LOCAL NOTES

ACCESS TO ALL DRIVEWAYS MUST BE PROVIDED AT ALL TIMES WITHIN THE PROJECT LIMITS.

THE CONTRACTOR SHALL COORDINATE WITH THE RESIDENT ENGINEER ON BUS TURNAROUNDS AND PROVIDE BUS TURNAROUNDS WITH ABC AS APPLICABLE.

APPROVED: _____ DATE: _____ DocuSigned by: K. BOMME 5/2/2018 SEAL 020111 ENGINEER K. BOMME

SIGN NUMBER: DET-1 TYPE: D QUANTITY: SEE PLANS SIGN WIDTH: 3'-6" HEIGHT: 2'-6" TOTAL AREA: 8.8 Sq.Ft. BORDER TYPE: FLUSH RECESS: 0.38" WIDTH: 0.5" RADII: 1.5" NO. Z BARS: LENGTH: BACKG COLOR: Orange COPY COLOR: Black <table><tr><th>SYMBOL</th><th>X</th><th>Y</th><th>WID</th><th>HT</th></tr><tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td><td> </td><td> </td></tr></table> MAT'L: 0.125" (3.2 mm) ALUMINUM	SYMBOL	X	Y	WID	HT																																									DESIGN BY: SGM PROJECT ID: 17BP.4.R.85 CHECKED BY: LOCATION: WAYNE COUNTY Dec 19, 2017 DIV: 4 3'-6" 2'-6" 6.75" 6"D 4.5" 6"D 6.75" 2.9" 36.2" 2.9" RED HILL ROAD BORDER R=1.5" TH=0.5" IN=0.38" Panel Style: Traffic Control.ssi M.U.T.C.D.: 2009 Edition Spacing Factor is 1 unless specified otherwise																																																																																																																																																																																																																																					
SYMBOL	X	Y	WID	HT																																																																																																																																																																																																																																																																															
LETTER POSITIONS <table><tr><th colspan="24">Letter locations are panel edge to lower left corner</th><th>Series/Size</th></tr><tr><th colspan="24"></th><th>Text Length</th></tr><tr><td></td><td>R</td><td>E</td><td>D</td><td></td><td>H</td><td>I</td><td>L</td><td>L</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>D 2000</td></tr><tr><td></td><td>2.9</td><td>8</td><td>12.8</td><td>16.8</td><td>22.8</td><td>28.4</td><td>30.8</td><td>35.4</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>36.2</td></tr><tr><td></td><td>R</td><td>O</td><td>A</td><td>D</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>D 2000</td></tr><tr><td></td><td>11</td><td>15.9</td><td>21</td><td>27</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>20.1</td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr></table> FILENAME: 970016_TC_TMP_01C(SD) NORTH CAROLINA D.O.T. SIGN DETAIL		Letter locations are panel edge to lower left corner																								Series/Size																									Text Length		R	E	D		H	I	L	L																			D 2000		2.9	8	12.8	16.8	22.8	28.4	30.8	35.4																			36.2		R	O	A	D																							D 2000		11	15.9	21	27																							20.1																																																																																																																
Letter locations are panel edge to lower left corner																								Series/Size																																																																																																																																																																																																																																																											
																								Text Length																																																																																																																																																																																																																																																											
	R	E	D		H	I	L	L																			D 2000																																																																																																																																																																																																																																																								
	2.9	8	12.8	16.8	22.8	28.4	30.8	35.4																			36.2																																																																																																																																																																																																																																																								
	R	O	A	D																							D 2000																																																																																																																																																																																																																																																								
	11	15.9	21	27																							20.1																																																																																																																																																																																																																																																								

4/30/2018
X:\NC001\Division 4 Wayne #40\Traffic\TrafficControl\TCP\950040_TC_TMP_01C(SD).dgn
User:tbodyue

APPROVED: _____

DATE: _____

DocuSigned by:
Boyd
5/2/2018

NORTH CAROLINA
PROFESSIONAL
SEAL
020111
ENGINEER
MAY K. BOYD


DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
WORK ZONE TRAFFIC CONTROL

SPECIAL SIGN DESIGN

Wayne County
Bridge #950040

PROJ. REFERENCE NO.	SHEET NO.
17BP.4.R.85	TMP-2
TGS ENGINEERS 804-C N. LAFAYETTE ST SHELBY, NC 28150 PH (704) 476-0003 CORP. LICENSE NO.: C-0275	



PHASING NOTES

- STEP 1: INSTALL ALL DETOUR ROUTE SIGNS AS SHOWN ON SHEET TMP-3.
- STEP 2: INSTALL TYPE III BARRICADES AND SIGNS, AND CLOSE SR 1513 (RED HILL RD) TO TRAFFIC AS SHOWN IN ROADWAY STANDARD DRAWING 1101.03 (SHEET 1 OF 9) AND TMP-2 AND TMP-3.

PLACE TRAFFIC ON DETOUR.
- STEP 3: DEMOLISH AND REMOVE THE EXISTING BRIDGE OVER IVY SWAMP.

CONSTRUCT THE NEW BRIDGE OVER IVY SWAMP FROM -L- STA. 14+78.00 TO 15+33.00.

CONSTRUCT THE ROADWAY ON SR 1513 (RED HILL RD) FROM -L- STA. 13+50.00 TO -L- STA. 14+78.00 (BEGIN BRIDGE) AND FROM -L- STA. 15+33.00 (END BRIDGE) TO 17+00.00 UP TO AND INCLUDING THE FINAL LAYER OF SURFACE COURSE.
- STEP 4: REFERRING TO SHEET PMP-1, PLACE PERMANENT PAVEMENT MARKINGS ON THE FOLLOWING: SR 1513 (RED HILL RD) FROM STA. 13+50.00 TO STA. 17+00.00.
- STEP 5: REMOVE BARRICADES, SIGNS, AND ALL OTHER TRAFFIC CONTROL DEVICES AND OPEN SR 1513 (RED HILL RD) TO TRAFFIC IN FINAL PATTERN.

APPROVED: _____

DATE: _____

DocuSigned by:
W. K. Bortue
5/2/2018

PROFESSIONAL SEAL

020111

ENGINEER

W. K. BORTUE

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

DIVISION OF HIGHWAYS



STATE OF NORTH CAROLINA

DEPARTMENT OF TRANSPORTATION

WORK ZONE TRAFFIC CONTROL

OVERVIEW
AND PHASING




4/30/2018
X:\NCDOT\Division 4 Wayne #40\Traffic\TrafficControl\TCP\950040_TC_TMP_03\DETOUR.dgn
User:nboayue



REFER TO ROADWAY STANDARD
DRAWING 1101.03, SHEET 1 OF 9
FOR APPLICABLE NOTES.

Wayne County
Bridge #950040


PROJ. REFERENCE NO.	SHEET NO.
17BP.4.R.85	TMP-3
 TGS ENGINEERS 804-C N. LAFAYETTE ST SHELBY, NC 28150 PH (704) 476-0003 CORP. LICENSE NO.: C-0275	



* SEE SHEET TMP-1C
FOR SIGN DESIGN

APPROVED: _____

DATE: _____




**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**



**OFFSITE DETOUR
ROUTE AND
BARRICADE PLACEMENT**

Wayne County
Bridge #950040

PROJ. REFERENCE NO.	SHEET NO.
17BP.4.R.85	PMP - 1
TGS ENGINEERS 804-C N. LAFAYETTE ST SHELBY, NC 28150 PH (704) 476-0003 CORP. LICENSE NO.: C-0275	



FINAL PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM	TOTAL QUANTITY	
PA	WHITE EDGELINE (2X)	PAINTE PAVEMENT MARKING LINES (4")	1400	LF
PI	YELLOW DOUBLE CENTER (2X)	PAINTE PAVEMENT MARKING LINES (4")	1400	LF
			TOTAL 2800	LF

NOTE: FOR EACH PAINT PAVEMENT MARKING ITEM, 1X IMPLIES A SINGLE APPLICATION AND 2X IMPLIES TWO APPLICATIONS.

NOTE:
PASSING ZONES WILL BE DETERMINED IN THE FIELD
AND MUST BE APPROVED BY THE ENGINEER.

APPROVED: _____

DATE: _____

DocuSigned by:


5/2/2018

SEAL
020111
NORTH CAROLINA
PROFESSIONAL
ENGINEER
N.K. BONYE

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
WORK ZONE TRAFFIC CONTROL

FINAL PAVEMENT
MARKING PLAN
AND SCHEDULE


TIP PROJECT: 17BP.4.R.85



STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
PLAN FOR PROPOSED
HIGHWAY EROSION CONTROL
WAYNE COUNTY

LOCATION: BRIDGE NO. 40 ON SR 1513 (RED HILL ROAD)
OVER IVY SWAMP

TYPE OF WORK: GRADING, DRAINAGE, PAVING, AND STRUCTURE



EROSION AND SEDIMENT CONTROL MEASURES

Std. #	Description	Symbol
1630.03	Temporary Silt Ditch	—
1630.05	Temporary Diversion	—
1605.01	Temporary Silt Fence	—
1606.01	Special Sediment Control Fence	—
1622.01	Temporary Berms and Slope Drains	—
1630.02	Silt Basin Type B	—
1633.01	Temporary Rock Silt Check Type-A	—
	Temporary Rock Silt Check Type-A with Matting and Polyacrylamide (PAM)	—
1633.02	Temporary Rock Silt Check Type-B	—
	Wattle/Coir Fiber Wattle	—
	Wattle/Coir Fiber Wattle with Polyacrylamide (PAM)	—
1634.01	Temporary Rock Sediment Dam Type-A	—
1634.02	Temporary Rock Sediment Dam Type-B	—
1635.01	Rock Pipe Inlet Sediment Trap Type-A	—
1635.02	Rock Pipe Inlet Sediment Trap Type-B	—
1630.04	Stilling Basin	—
1630.06	Special Stilling Basin	—
	Rock Inlet Sediment Trap:	—
1632.01	Type A	—
1632.02	Type B	—
1632.03	Type C	—
	Skimmer Basin	—
	Tiered Skimmer Basin	—
	Infiltration Basin	—

THIS PROJECT CONTAINS
EROSION CONTROL PLANS
FOR CLEARING AND
GRUBBING PHASE OF
CONSTRUCTION.

THIS PROJECT HAS
BEEN DESIGNED TO
SENSITIVE WATERSHED
STANDARDS.

ENVIRONMENTALLY
SENSITIVE AREA(S) EXIST
ON THIS PROJECT

Refer To E. C. Special Provisions
for Special Considerations.

GRAPHIC SCALE



PLANS

THESE EROSION AND SEDIMENT
CONTROL PLANS COMPLY WITH
THE REGULATIONS SET FORTH
BY THE NCG-010000 GENERAL
CONSTRUCTION PERMIT EFFECTIVE
AUGUST 1, 2016 AND ISSUED BY
THE NORTH CAROLINA DEPARTMENT
OF ENVIRONMENT AND NATURAL
RESOURCES DIVISION OF WATER
RESOURCES.

Prepared in the Office of:



TGS ENGINEERS
706 HILLSBOROUGH ST
SUITE 200
RALEIGH, NC 27603

PH (919) 773-8887
CORP. LICENSE NO.:
C-0275

Designed by:

BEN HENEGAR, PE

NAME

3564

LEVEL III CERTIFICATION NO.

Reviewed in the Office of:

ROADSIDE ENVIRONMENTAL UNIT

1425 Rock Quarry Rd, Suite 106
Raleigh, NC 27610

2018 STANDARD SPECIFICATIONS

Reviewed by:

DONALD R. PEARSON, JR. EI, CPESC


Roadway Standard Drawings

The following roadway english standards as appear in "Roadway Standard Drawings"- Roadway Design Unit - N. C. Department of Transportation - Raleigh, N. C., dated January 2018 and the latest revision thereto are applicable to this project and by reference hereby are considered a part of these plans.

1604.01	Railroad Erosion Control Detail	1632.01	Rock Inlet Sediment Trap Type A
1605.01	Temporary Silt Fence	1632.02	Rock Inlet Sediment Trap Type J
1606.01	Special Sediment Control Fence	1632.03	Rock Inlet Sediment Trap Type C
1607.01	Gravel Construction Entrance	1633.01	Temporary Rock Silt Check Type A
1622.01	Temporary Berms and Slope Drains	1633.02	Temporary Rock Silt Check Type J
1630.01	Riser Basin	1634.01	Temporary Rock Sediment Dam Type A
1630.02	Silt Basin Type J	1634.02	Temporary Rock Sediment Dam Type J
1630.03	Temporary Silt Ditch	1635.01	Rock Pipe Inlet Sediment Trap Type A
1630.04	Stilling Basin	1635.02	Rock Pipe Inlet Sediment Trap Type J
1630.05	Temporary Diversion	1640.01	Coir Fiber Wattle
1630.06	Special Stilling Basin	1645.01	Temporary Stream Crossing
1631.01	Matting Installation		

TEMPORARY ROCK SILT CHECK TYPE 'A' WITH EXCELSIOR MATTING AND POLYACRYLAMIDE (PAM)

PROJECT REFERENCE NO.	SHEET NO.
17BP4R85	EC-2
RW SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER




NOTES:

INSTALL TEMPORARY ROCK SILT CHECK TYPE A IN ACCORDANCE WITH ROADWAY STANDARD DRAWING NO. 1633.01.


USE EXCELSIOR FOR MATTING MATERIAL AND ANCHOR MATTING SECTION AT TOP AND BOTTOM WITH CLASS B STONE.

PRIOR TO POLYACRYLAMIDE (PAM) APPLICATION, OBTAIN A SOIL SAMPLE FROM PROJECT LOCATION, AND FROM OFFSITE MATERIAL, AND ANALYZE FOR APPROPRIATE PAM FLOCCULANT TO BE APPLIED TO EACH ROCK SILT CHECK.


INITIALLY APPLY 4 OUNCES OF POLYACRYLAMIDE (PAM) TO TOP OF MATTING SECTION AND AFTER EVERY RAINFALL EVENT THAT EQUALS OR EXCEEDS 0.50 INCHES.



INSET A



SECTION A-A




SECTION B-B


NOT TO SCALE

PROJECT REFERENCE NO.	SHEET NO.
17BP.4R.85	EC-2A
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

WATTLE BARRIER DETAIL



ISOMETRIC VIEW



FRONT VIEW

NOTES:

USE MINIMUM 18 IN. NOMINAL DIAMETER EXCELSIOR WATTLE AND LENGTH OF 10 FT.

EXCAVATE A 2 TO 3 INCH TRENCH FOR WATTLE TO BE PLACED.

DO NOT PLACE WATTLES ON TOE OF SLOPE.



USE 2 FT. WOODEN STAKES WITH A 2 IN. BY 2 IN. NOMINAL CROSS SECTION.

INSTALL A MINIMUM OF 2 UPSLOPE STAKES AND 4 DOWNSLOPE STAKES AT AN ANGLE TO WEDGE WATTLE TO GROUND.

PROVIDE STAPLES MADE OF 0.125 IN. DIAMETER STEEL WIRE FORMED INTO A U SHAPE NOT LESS THAN 12" IN LENGTH.

INSTALL STAPLES APPROXIMATELY EVERY 1 LINEAR FOOT ON BOTH SIDES OF WATTLE AND AT EACH END TO SECURE IT TO THE SOIL.

FOR BREAKS ALONG LARGE SLOPES, USE MAXIMUM SPACING OF 25 FT.



TOP VIEW

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

PROJECT REFERENCE NO.	SHEET NO.
17BP.4R.85	EC-3
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER


SOIL STABILIZATION TIMEFRAMES

SITE DESCRIPTION	STABILIZATION TIME	TIMEFRAME EXCEPTIONS
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HQW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HQW ZONES.

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	L DITCH	13+00	13+65	LT	95
SUBTOTAL					95
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					1430
TOTAL					1525
SAY					1525

8/17/99
3/14/2018
X:\NCDOT\Division 4 Wayne #40\Environmental\Design\B950040.cg_psh_04.dgn
11:28:00 AM
11/28/2018



PROJECT REFERENCE NO.		SHEET NO.	
17BP.4.R.85		EC-4	
RW SHEET NO.		4	
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER	
TGS ENGINEERS		TGS ENGINEERS	
706 HILLSBOROUGH ST., SUITE 200		706 HILLSBOROUGH ST., SUITE 200	
RALEIGH, NC 27603		RALEIGH, NC 27603	
PH (919) 773-8887		PH (919) 773-8887	
CORP. LICENSE NO.: C-0275		CORP. LICENSE NO.: C-0275	

CLEARING AND GRUBBING EROSION CONTROL FOR CONSTRUCTION SHEET 04

HELEN GAIL PARKER DAVIS
DB 89E PG 622

ENVIRONMENTALLY SENSITIVE AREA
SEE PROJECT SPECIAL PROVISIONS

Wattle Barrier (Typ.)

END PROJECT 17BP.4.R.85
-L- POT STA. 17+00.00

MATCH LINE -L- STA.14+60.00
SEE SHEET NO.4

CLASS 'II' RIP-RAP
STRUCTURE PAY
ITEM

CLASS 'B' RIP-RAP
EST. 3 TONS
GEOTEXTILE
EST. 10 SY

VARIABLE WIDTH
STD. BASE DITCH
SEE DETAIL 2
EST. 10 CY DDE
L=20'
S=0.5%

RONALD B LANCASTER, ET AL
DB 1751 PG 499

NOTE:
PLACE TEMPORARY ROCK SILT CHECKS TYPE - A AT
DRAINAGE OUTLETS.

SEE SHEET 6 FOR -L- PROFILE

FOR STRUCTURE PLANS, SEE SHEET S-? THRU S-??

DETAIL 2

VARIABLE WIDTH STANDARD BASE DITCH
(Not to Scale)

Min. D= 1.0 Ft. to 0.0 Ft.
B= 2.0 Ft. to 8.0 Ft.

L-STA. 15 + 97 RT

DAWN PAGE DAVIS
DB 3038 PG 45

HELEN GAIL PARKER DAVIS
DB 89E PG 622

1

BEGIN PROJECT 17BP.4.R.85
-L- POT STA. 13+50.00

BEGIN CONSTRUCTION
-L- POT STA. 13+00.00

VARIABLE WIDTH
STD. BASE DITCH
SEE DETAIL 2
EST. 15 CY DDE
L = 35'
S = 0.3%

CLASS 'B' RIP-RAP
EST. 3 TONS
GEOTEXTILE
EST. 10 SY

CLASS 'B' RIP-RAP
EST. 3 TONS
GEOTEXTILE
EST. 10 SY



MATCH LINE -L- STA.14+60.00
SEE SHEET NO.5

BL-101

BENTON FAMILY FARMS LLC
DB 2759 PG 580
PC N SLIDE 34G

2

BM#1



SEE SHEET 6 FOR -L- PROFILE

NAD 83 NA 2011

HELEN GAIL PARKER DAVIS
DB 89E PG 622

END PROJECT 17BP.4.R.85
-L- POT STA. 17+00.00

BM#2

1

MATCH LINE -L- STA. 14+60.00
SEE SHEET NO. 4

Wattle Barrier (Typ.)

BZ 2-

BZ 1-

- SEAT = 70.60'

~~RIPRAP~~

|||

BZ 1

BZ

WOODS

EXISTING R/W

WOODS

EXISTING R/W

NC-222

-103

CLASS 'II' RIP-RAP
STRUCTURE PAY
ITEM

CLASS 'B' RIP-RAP
EST. 3 TONS
GEOTEXTILE
EST. 10 SY

VARIABLE WIDTH
STD. BASE DITCH
SEE DETAIL 2
EST. 10 CY DDE
L=20'
S=0.5%

RONALD B LANCASTER, ET AL.
DB 1751 PG 499

3

DETAIL 2

VARIABLE WIDTH STANDARD BASE DITCH
(Not to Scale)

Min. D= 1.0 Ft. to 0.0 Ft.
B= 2.0 Ft. to 8.0 Ft.

B = 2.0 Ft. to 8.0 Ft.

-L- STA. 15+97 RT

SEE SHEET 6 FOR -L- PROFILE

FOR STRUCTURE PLANS, SEE SHEET S-? THRU S-??

8/17/99

3/14/2018
X:\NCDDOT\Division 4 Wayne #40\Environmental\Design\B950040_ec_psh_05.dgn

PRELIMINARY PLANS
DO NOT USE FOR CONSTRUCTION

REFORESTATION

TREE REFORESTATION SHALL BE PLANTED 6 FT. TO 10 FT. ON CENTER, RANDOM SPACING, AVERAGING 8 FT. ON CENTER, APPROXIMATELY 680 PLANTS PER ACRE.

REFORESTATION

MIXTURE, TYPE, SIZE, AND FURNISH SHALL CONFORM TO THE FOLLOWING:


25%	LIRIODENDRON TULIPIFERA	TULIP POPLAR	12 in - 18 in 3R
25%	PLATANUS OCCIDENTALIS	AMERICAN SYCAMORE	12 in - 18 in 3R
25%	FRAXINUS PENNSYLVANICA	GREEN ASH	12 in - 18 in 3R
25%	BETULA NIGRA	RIVER BIRCH	12 in - 18 in 3R

PLANTING DETAILS


SEEDLING / LINER BAREROOT PLANTING DETAIL

HEALING IN


1. Locate a healing-in site in a shady, well protected area.
2. Excavate a flat bottom trench 12 inches deep and provide drainage.




3. Backfill the trench with 2 inches well rotted sawdust. Place a 2 inch layer of well rotted sawdust at a sloping angle at one end of the trench.



4. Place a single layer of plants against the sloping end so that the root collar is at ground level.




5. Place a 2 inch layer of well rotted sawdust over the roots maintaining a sloping angle.




6. Repeat layers of plants and sawdust as necessary and water thoroughly.


DOUBLE PLANTING METHOD
USING THE K3C PLANTING BAR




1. Insert planting bar as shown and pull handle toward planter.




2. Remove planting bar and place seedling at correct depth.




3. Insert planting bar 2 inches toward planter from seedling.



4. Pull handle of bar toward planter, firming soil at bottom.



5. Push handle forward firming soil at top.




6. Leave compaction hole open. Water thoroughly.

PLANTING NOTES:

PLANTING BAG
During planting, seedlings shall be kept in a moist canvas bag or similar container to prevent the root systems from drying.




K3C PLANTING BAR
Planting bar shall have a blade with a triangular cross section, and shall be 12 inches long, 4 inches wide and 1 inch thick at center.



ROOT PRUNING
All seedlings shall be root pruned, if necessary, so that no roots extend more than 10 inches below the root collar.

TIP PROJECT: 17BP.4.R.85



STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

UTILITIES BY OTHERS PLANS
WAYNE COUNTY


LOCATION: BRIDGE NO. 40 ON SR 1513 (RED HILL ROAD)
OVER IVY SWAMP

TYPE OF WORK: POWER, WATER & COMMUNICATION

T.I.P. NO.	SHEET NO.
17BP.4.R.85	UO-1

NOTE:
ALL PROPOSED UTILITY WORK SHOWN
ON THIS SHEET WILL BE DONE
BY OTHERS.
NO PAYMENT WILL BE MADE TO THE
CONTRACTOR FOR PROPOSED UTILITY
WORK SHOWN ON THIS SHEET.

NAD 83 NA 2011



GRAPHIC SCALES



INDEX OF SHEETS

SHEET NO.:	DESCRIPTION:
UO-1	TITLE SHEET
UO-2	UBO SYMBOLOGY SHEET
UO-3	UBO PLAN SHEET

UTILITY OWNERS WITH CONFLICTS


- (A) POWER - STANTONSBURG POWER
- (B) WATER - WAYNE COUNTY WATER
- (C) COMMUNICATION - CENTURYLINK



PREPARED IN THE OFFICE OF:

TGS ENGINEERS
706 HILLSBOROUGH ST. SUITE 200
RALEIGH, NC 27603
PH (919) 773-8887
CORP. LICENSE NO.: C-0275

UTILITY PROJECT MANAGER
PROJECT UTILITY COORDINATOR
PROJECT UTILITY XXXX



DIVISION OF HIGHWAYS
UTILITIES UNIT
1555 MAIL SERVICES CENTER
RALEIGH NC 27699-1555
PHONE (919) 707-5690
FAX (919) 250-4151

UTILITIES REGIONAL ENGINEER
DAVID BEAMAN DIV. UTILITIES COORDINATOR
UTILITIES AREA COORDINATOR
UTILITIES COORDINATOR


5/14/99
5/8/2018
\\utlities\6\Location\Utility_Relocations\Relocation_Plans\B9E0040_UB0_2.dgn
U:\Electronics

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJECT REFERENCE NO.	SHEET NO.
17BP.4.R.85	U0-2

UTILITIES PLAN SHEET SYMBOLS

PROPOSED WATER SYMBOLS

Water Line (Sized as Shown)	
11¼ Degree Bend	
22½ Degree Bend	
45 Degree Bend	
90 Degree Bend	
Plug	
Tee	
Cross	
Reducer	
Gate Valve	
Butterfly Valve	
Tapping Valve	
Line Stop	
Line Stop with Bypass	
Blow Off	
Fire Hydrant	
Relocate Fire Hydrant	
Remove Fire Hydrant	
Water Meter	
Relocate Water Meter	
Remove Water Meter	
Water Pump Station	
RPZ Backflow Preventer	
DCV Backflow Preventer	
Relocate RPZ Backflow Preventer	
Relocate DCV Backflow Preventer	

PROPOSED SEWER SYMBOLS

Gravity Sewer Line (Sized as Shown)	
Force Main Sewer Line (Sized as Shown)	
Manhole (Sized per Note)	
Sewer Pump Station	

PROPOSED MISCELLANEOUS UTILITIES SYMBOLS


Power Pole	
Telephone Pole	
Joint Use Pole	
Telephone Pedestal	
Utility Line by Others (Type as Shown)	
Trenchless Installation	
Encasement by Open Cut	
Encasement	




Thrust Block	
Air Release Valve	
Utility Vault	
Concrete Pier	
Steel Pier	
Plan Note	
Pay Item Note	

NOTE

PAY ITEM

EXISTING UTILITIES SYMBOLS


Power Pole	
Telephone Pole	
Joint Use Pole	
Utility Pole	
Utility Pole with Base	
H-Frame Pole	
Power Transmission Line Tower	
Water Manhole	
Power Manhole	
Telephone Manhole	
Sanitary Sewer Manhole	
Hand Hole for Cable	
Power Transformer	
Telephone Pedestal	
CATV Pedestal	
Gas Valve	
Gas Meter	
Located Miscellaneous Utility Object	
Abandoned According to Utility Records	
End of Information	

*Underground Power Line	
*Underground Telephone Cable	
*Underground Telephone Conduit	
*Underground Fiber Optics Telephone Cable	
*Underground TV Cable	
*Underground Fiber Optics TV Cable	
*Underground Gas Pipeline	
Aboveground Gas Pipeline	
*Underground Water Line	
Aboveground Water Line	
*Underground Gravity Sanitary Sewer Line	
Aboveground Gravity Sanitary Sewer Line	
*Underground SS Forced Main Line	
Underground Unknown Utility Line	
SUE Test Hole	
Water Meter	
Water Valve	
Fire Hydrant	
Sanitary Sewer Cleanout	

*For Existing Utilities	
Utility Line Drawn from Record (Type as Shown)	
Designated Utility Line (Type as Shown)	


6/23/16


4/30/2018
\\NCDOT\Division 4 Wayne #40\Roadway\CorridorModeling\B950040_Rdy_xpl.dgn
User:rbalme



6/23/16

4/30/2018
\\NCDOT\Division 4 Wayne #40\Roadway\CorridorModeling\B950040_Rdy_xpl.dgn
User:rbalme






3/22/2018 10:40:00 AM X:\NCDOT\Division 4 Wayne #40\Structures\90%\DGN\S-00_...Wayne 0040_Tsh.dgn User:tfennis

PROJECT: 17BP.4.R.85

CONTRACT: DD00250

STRUCTURE



STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS


WAYNE COUNTY

LOCATION: BRIDGE NO. 40 ON SR 1513 (RED HILL ROAD)
OVER IVY SWAMP


TYPE OF WORK: GRADING, DRAINAGE, PAVING, AND STRUCTURE

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	17BP.4.R.85		
STATE PROJ. NO.	P.A. PROJ. NO.	DESCRIPTION	
17BP.4.R.85	N/A	PE	
17BP.4.R.85	N/A	R/W, UTIL	
17BP.4.R.85	N/A	CONSTRUCTION	

NAD 83 NA 2011



DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED



DESIGN DATA
ADT 2016 = 280
T = 6 %
V = 60 MPH

FUNC CLASS =
LOCAL-RURAL
SUBREGIONAL TIER

PROJECT LENGTH

LENGTH ROADWAY PROJECT 17BP.4.R.85 = 0.055 mile
LENGTH STRUCTURES PROJECT 17BP.4.R.85 = 0.011 mile
TOTAL LENGTH PROJECT 17BP.4.R.85 = 0.066 mile

PLANS PREPARED BY:
TGS ENGINEERS
706 HILLSBOROUGH ST
SUITE 200
RALEIGH, NC 27603

2018 STANDARD SPECIFICATIONS

LETTING DATE:
MAY 22, 2018


PLANS PREPARED BY:
NCDOT DIVISION 4


MARC CHEEK, PE
STRUCTURES DESIGN ENGINEER

STRUCTURES DESIGN
ENGINEER



4/2/2018





FOUNDATION LAYOUT PLAN

ALL END BENT PILES ARE HP 12x53 STEEL PILES. DIMENSIONS LOCATING PILES ARE SHOWN TO THE CENTERLINE OF PILES. ORIENT PILES AS SHOWN.

FOUNDATION RECOMMENDATION NOTES

FOR PILES, SEE SECTION 450 OF THE STANDARD SPECIFICATIONS.

PILES AT END BENT NO. 1 AND END BENT NO. 2 ARE DESIGNED FOR A FACTORED RESISTANCE OF 75 TONS PER PILE.

DRIVE PILES AT END BENT NO. 1 AND END BENT NO. 2 TO A REQUIRED DRIVING RESISTANCE OF 125 TONS PER PILE.

INSTALL PILES AT END BENT NO. 2 TO A TIP ELEVATION NO HIGHER THAN 45.0 FT.

TESTING PILES WITH THE PDA DURING DRIVING, RESTRIKING OR REDRIVING MAY BE REQUIRED. THE ENGINEER WILL DETERMINE THE NEED FOR PDA TESTING. FOR PDA TESTING, SEE SECTION 450 OF THE STANDARD SPECIFICATIONS.

PROJECT NO. 17BP.4.R.85

WAYNE COUNTY


STATION: 15+05.50 -L-

SHEET 2 OF 3

		STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED		GENERAL DRAWING FOR BRIDGE ON SR 1513 OVER IVY SWAMP BETWEEN NC 111 AND SR 1514	
TGS ENGINEERS 804-C N. LAFAYETTE ST SHELBY, NC 28150 PH (704) 476-0003 CORP. LICENSE NO.: C-0275		REVISIONS	
		SHEET NO.	
		S-2	
		TOTAL SHEETS	
		15	

DRAWN BY :	TBE	DATE :	3/18
CHECKED BY :	MGC	DATE :	3/18

NOTES



LOCATION SKETCH

TOTAL BILL OF MATERIAL

	REMOVAL OF EXISTING STRUCTURE	ASBESTOS ASSESSMENT	PDA TESTING	UNCLASSIFIED STRUCTURE EXCAVATION	CLASS "A" CONCRETE	BRIDGE APPROACH SLABS	REINFORCING STEEL	PILE DRIVING EQUIPMENT SETUP FOR HP 12x53 STEEL PILES	HP 12x53 STEEL PILES	PILE REDRIVES	VERTICAL CONCRETE BARRIER RAIL	RIP RAP CLASS II (2'-0" THK.)	GEOTEXTILE FOR DRAINAGE	ELASTOMERIC BEARINGS	3'-0" x 1'-9" PRESTRESSED CONCRETE CORED SLABS		
	LUMP SUM	LUMP SUM	EACH	LUMP SUM	C.Y.	LUMP SUM	LBS.	EACH	NO.	LIN. FT.	EACH	LIN. FT.	TONS	SQ. YDS.	LUMP SUM	NO.	LIN. FT.
SUPERSTRUCTURE												110.00				11	605.00
END BENT 1					21.6		2,636	7	7	350	4		135	150			
END BENT 2					21.6		2,636	7	7	350	4		145	160			
TOTALS	LUMP SUM	LUMP SUM	1	LUMP SUM	43.2	LUMP SUM	5,272	14	14	700	8	110.00	280	310	LUMP SUM	11	605.00

PROJECT NO. 17BP.4.R.85
WAYNE COUNTY
 STATION: 15+05.50 -L-

SHEET 3 OF 3



4/2/2018

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETE

TGS ENGINEERS
804-C N. LAFAYETTE ST
SHELBY, NC 28150
PH (704) 476-0003
CORP. LICENSE NO.: C-027

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

GENERAL DRAWING
FOR BRIDGE ON SR 1513
OVER IVY SWAMP
BETWEEN NC 111 AND SR 1514

REVISIONS						SHEET NO. S-3
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 15
2			4			

DRAWN BY :	TBE	DATE :	1/18
CHECKED BY :	MGC	DATE :	3/18

LOAD AND RESISTANCE FACTOR RATING (LRFD) SUMMARY FOR PRESTRESSED CONCRETE GIRDERS

LEVEL	VEHICLE	WEIGHT (W) (TONS)	CONTROLLING LOAD RATING	MINIMUM RATING FACTORS (RF)	TONS = W X RF	STRENGTH I LIMIT STATE											SERVICE III LIMIT STATE						COMMENT NUMBER	
						LIVELOAD FACTORS	MOMENT					SHEAR					LIVELOAD FACTORS	MOMENT						
							DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)		DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)		
DESIGN LOAD RATING	HL-93(Inv)	N/A	①	1.055	--	1.75	0.275	1.23	55'	EL	27	0.523	1.23	55'	EL	5.4	0.80	0.275	1.05	55'	EL	27		
	HL-93(0pr)	N/A	--	1.591	--	1.35	0.275	1.59	55'	EL	27	0.523	1.59	55'	EL	5.4	N/A	--	--	--	--	--		
	HS-20(Inv)	36.000	②	1.322	47.585	1.75	0.275	1.54	55'	EL	27	0.523	1.47	55'	EL	5.4	0.80	0.275	1.32	55'	EL	27		
	HS-20(0pr)	36.000	--	1.9	68.396	1.35	0.275	1.99	55'	EL	27	0.523	1.9	55'	EL	5.4	N/A	--	--	--	--	--		
LEGAL LOAD RATING	SV	SNSH	13.500	--	2.776	37.476	1.4	0.275	4.04	55'	EL	27	0.523	4.17	55'	EL	5.4	0.80	0.275	2.78	55'	EL	27	
		SNGARBS2	20.000	--	2.155	43.095	1.4	0.275	3.14	55'	EL	27	0.523	3.02	55'	EL	5.4	0.80	0.275	2.15	55'	EL	27	
		SNAGRIS2	22.000	--	2.079	45.734	1.4	0.275	3.03	55'	EL	27	0.523	2.83	55'	EL	5.4	0.80	0.275	2.08	55'	EL	27	
		SNCOTTS3	27.250	--	1.384	37.708	1.4	0.275	2.01	55'	EL	27	0.523	2.09	55'	EL	5.4	0.80	0.275	1.38	55'	EL	27	
		SNAGGRS4	34.925	--	1.189	41.527	1.4	0.275	1.73	55'	EL	27	0.523	1.77	55'	EL	5.4	0.80	0.275	1.19	55'	EL	27	
		SNS5A	35.550	--	1.16	41.255	1.4	0.275	1.69	55'	EL	27	0.523	1.82	55'	EL	5.4	0.80	0.275	1.16	55'	EL	27	
		SNS6A	39.950	--	1.079	43.102	1.4	0.275	1.57	55'	EL	27	0.523	1.68	55'	EL	5.4	0.80	0.275	1.08	55'	EL	27	
		SNS7B	42.000	--	1.028	43.175	1.4	0.275	1.5	55'	EL	27	0.523	1.67	55'	EL	5.4	0.80	0.275	1.03	55'	EL	27	
	TTST	TNAGRIT3	33.000	--	1.32	43.556	1.4	0.275	1.92	55'	EL	27	0.523	1.98	55'	EL	5.4	0.80	0.275	1.32	55'	EL	27	
		TNT4A	33.075	--	1.33	43.979	1.4	0.275	1.94	55'	EL	27	0.523	1.91	55'	EL	5.4	0.80	0.275	1.33	55'	EL	27	
		TNT6A	41.600	--	1.101	45.811	1.4	0.275	1.6	55'	EL	27	0.523	1.83	55'	EL	5.4	0.80	0.275	1.10	55'	EL	27	
		TNT7A	42.000	--	1.114	46.804	1.4	0.275	1.62	55'	EL	27	0.523	1.71	55'	EL	5.4	0.80	0.275	1.11	55'	EL	27	
		TNT7B	42.000	--	1.163	48.848	1.4	0.275	1.69	55'	EL	27	0.523	1.62	55'	EL	5.4	0.80	0.275	1.16	55'	EL	27	
		TNAGRIT4	43.000	--	1.101	47.33	1.4	0.275	1.6	55'	EL	27	0.523	1.56	55'	EL	5.4	0.80	0.275	1.10	55'	EL	27	
		TNAGT5A	45.000	--	1.031	46.405	1.4	0.275	1.5	55'	EL	27	0.523	1.58	55'	EL	5.4	0.80	0.275	1.03	55'	EL	27	
		TNAGT5B	45.000	③	1.013	45.582	1.4	0.275	1.47	55'	EL	27	0.523	1.48	55'	EL	5.4	0.80	0.275	1.01	55'	EL	27	

LOAD FACTORS:

DESIGN LOAD RATING FACTORS	LIMIT STATE	γ _{DC}	γ _{DW}
	STRENGTH I	1.25	1.50
	SERVICE III	1.00	1.00

NOTES:

MINIMUM RATING FACTORS ARE BASED ON THE STRENGTH I AND SERVICE III LIMIT STATES.
ALLOWABLE STRESSES FOR SERVICE III LIMIT STATE ARE AS REQUIRED FOR DESIGN.

Ⓝ CONTROLLING LOAD RATING

① DESIGN LOAD RATING (HL-93)


② DESIGN LOAD RATING (HS-20)

③ LEGAL LOAD RATING **

** SEE CHART FOR VEHICLE TYPE

GIRDER LOCATION

I - INTERIOR GIRDER
EL - EXTERIOR LEFT GIRDER
ER - EXTERIOR RIGHT GIRDER



LRFR SUMMARY
FOR SPAN 'A'

PROJECT NO. 17BP.4.R.85
WAYNE COUNTY
STATION: 15+05.50 -L-




ASSEMBLED BY :	TBE	DATE :	3/18
CHECKED BY :	MGC	DATE :	3/18
DRAWN BY :	CVC 6/10		.
CHECKED BY :	DNS 6/10		.

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
804-C N. LAFAYETTE ST
SHELBY, NC 28150
PH (704) 476-0003
CORP. LICENSE NO.: C-0275

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
STANDARD
LRFR SUMMARY FOR
55' CORED SLAB UNIT
90° SKEW
(NON-INTERSTATE TRAFFIC)

REVISIONS						SHEET NO. S-4
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 15
2			4			




HALF SECTION
AT INTERMEDIATE DIAPHRAGMS

HALF SECTION
THROUGH VOIDS


TYPICAL SECTION

* - THE MAXIMUM BARRIER RAIL HEIGHT AND ASPHALT THICKNESS IS SHOWN. THE HEIGHT OF THE BARRIER RAIL AND ASPHALT THICKNESS VARIES WHILE THE TOP OF THE BARRIER RAIL FOLLOWS THE PROFILE OF THE GUTTERLINE. FOR RAIL HEIGHT DETAILS AND ASPHALT THICKNESS SEE THE "VERTICAL CONCRETE BARRIER RAIL DETAILS", SHEET 3 OF 3.

FIXED END




SECTION AT END BENT




END ELEVATION


SHOWING PLACEMENT OF DOUBLE STIRRUPS AND LOCATION OF DOWEL HOLES. (STRAND LAYOUT NOT SHOWN.)
INTERIOR SLAB UNIT SHOWN-EXTERIOR SLAB UNIT SIMILAR EXCEPT SHEAR KEY LOCATION.




THREADED INSERT DETAIL



ELEVATION VIEW



SECTION B-B



SHEAR KEY DETAIL

NOTE: OMIT SHEAR KEY ON OUTSIDE FACE OF EXTERIOR CORED SLABS.


0.6" Ø LOW RELAXATION STRAND LAYOUT

BOND SHALL BE BROKEN ON THESE STRANDS FOR A DISTANCE OF 6'-0" FROM END OF CORED SLAB UNIT. SEE STANDARD SPECIFICATIONS, ARTICLE 1078-7.

DEBONDING LEGEND

PROJECT NO. 17BP.4.R.85
WAYNE COUNTY
STATION: 15+05.50 -L-

SHEET 1 OF 3





DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
804-C N. LAFAYETTE ST
SHELBY, NC 28150
PH (704) 476-0003
CORP. LICENSE NO.: C-0275

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH
STANDARD
3'-0" X 1'-9"
PRESTRESSED CONCRETE
CORED SLAB UNIT
90° SKEW

REVISIONS						SHEET NO.
NO.	BY	DATE	NO.	BY	DATE	
1			3			S-5
2			4			TOTAL SHEETS 15

DRAWN BY : TBE
CHECKED BY : MGC
DATE : 3/18
DATE : 3/18



DETAIL "A"

(TYPICAL EACH END OF UNIT)
NOTE: EXTERIOR UNIT SHOWN - INTERIOR UNIT SIMILAR EXCEPT OMIT #5 S3 BARS.



PROJECT NO. 17BP.4.R.85

WAYNE COUNTY

STATION: 15+05.50 -L-

SHEET 2 OF 3


STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

PLAN OF 55' UNIT
30'-10" CLEAR ROADWAY
90° SKEW

DRAWN BY : TBE
CHECKED BY : MGC
DATE : 3/18
DATE : 3/18

PLAN OF UNIT

REVISIONS						SHEET NO.
NO.	BY	DATE	NO.	BY	DATE	
1			3			S-6
2			4			TOTAL SHEETS 15




FIXED END
(TYPE I - 22 REQ'D)

ELASTOMERIC BEARING DETAILS


ELASTOMER IN ALL BEARINGS SHALL BE 50 DUROMETER HARDNESS.

DEAD LOAD DEFLECTION AND CAMBER	
	3'-0" x 1'-9"
55' CORED SLAB UNIT	0.6" Ø L.R. STRAND
CAMBER (SLAB ALONE IN PLACE)	1 1/2" ↑
DEFLECTION DUE TO SUPERIMPOSED DEAD LOAD**	3/8" ↓
FINAL CAMBER	1 1/8" ↑

** INCLUDES FUTURE WEARING SURFACE




VERTICAL CONCRETE BARRIER RAIL SECTION




SECTION S-S
AT DAM IN OPEN JOINT
(THIS IS TO BE USED ONLY
WHEN SLIP FORM IS USED)

Ø 1/2" EXP. JT. MAT'L HELD IN
PLACE WITH GALVANIZED NAILS.
(NOTE: OMIT EXP. JT. MAT'L
WHEN SLIP FORM IS USED)



ELEVATION AT EXPANSION JOINTS



END VIEW

SIDE VIEW

END OF RAIL DETAILS

BILL OF MATERIAL FOR ONE 55' CORED SLAB UNIT							
BAR	NUMBER	SIZE	TYPE	EXTERIOR UNIT		INTERIOR UNIT	
B7	4	#4	STR	LENGTH	WEIGHT	LENGTH	WEIGHT
				28'-3"	75	28'-3"	75
S1	8	#5	3	4'-3"	35	4'-3"	35
S2	114	#4	3	5'-4"	406	5'-4"	406
* S3	64	#5	1	5'-8"	378		
REINFORCING STEEL				LBS.	516	LBS.	516
* EPOXY COATED REINFORCING STEEL				LBS.	378		
6500 P.S.I. CONCRETE				CU. YDS.	7.8	CU. YDS.	7.8
0.6" Ø L.R. STRANDS				No.	19	No.	19

GUTTERLINE ASPHALT THICKNESS & RAIL HEIGHT		
	ASPHALT OVERLAY THICKNESS	RAIL HEIGHT
55' UNITS	1 5/8"	3'-7 5/8"


BILL OF MATERIAL FOR VERTICAL CONCRETE BARRIER RAIL						
BAR	BARS PER PAIR OF EXTERIOR UNITS	TOTAL NO.	SIZE	TYPE	LENGTH	WEIGHT
	55' UNIT					
* B14	40	40	#5	STR	27'-1"	1130
* S4	128	128	#5	2	7'-2"	957
* EPOXY COATED REINFORCING STEEL					LBS.	2087
CLASS AA CONCRETE					CU. YDS.	14.1
TOTAL VERTICAL CONCRETE BARRIER RAIL					LIN. FT.	110.00

GRADE 270 STRANDS	
	0.6" Ø L.R.
AREA (SQUARE INCHES)	0.217
ULTIMATE STRENGTH (LBS. PER STRAND)	58,600
APPLIED PRESTRESS (LBS. PER STRAND)	43,950

CORED SLABS REQUIRED			
	NUMBER	LENGTH	TOTAL LENGTH
55' UNIT			
EXTERIOR C.S.	2	55'-0"	110'-0"
INTERIOR C.S.	9	55'-0"	495'-0"
TOTAL	11		605'-0"

CONCRETE RELEASE STRENGTH	
UNIT	PSI
55' UNITS	4900

BAR TYPES



ALL BAR DIMENSIONS ARE OUT TO OUT

NOTES

ALL PRESTRESSING STRANDS SHALL BE 7-WIRE LOW RELAXATION GRADE 270 STRANDS AND SHALL CONFORM TO AASHTO M203 EXCEPT FOR SAMPLING REQUIREMENTS WHICH SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.

ALL REINFORCING STEEL CAST WITH THE CORED SLAB SECTIONS SHALL BE GRADE 60 AND SHALL BE INCLUDED IN THE UNIT PRICE BID FOR PRESTRESSED CONCRETE CORED SLABS.

RECESSES FOR TRANSVERSE STRANDS SHALL BE GROUTED AFTER THE TENSIONING OF THE STRANDS.

THE 2 1/2" Ø DOWEL HOLES AT FIXED ENDS OF SLAB SECTIONS SHALL BE FILLED WITH NON-SHRINK GROUT.

THE BACKER RODS SHALL CONFORM TO THE REQUIREMENTS OF TYPE M BOND BREAKER. SEE SECTION 1028 OF THE STANDARD SPECIFICATIONS.

WHEN CORED SLABS ARE CAST, AN INTERNAL HOLD-DOWN SYSTEM SHALL BE EMPLOYED TO PREVENT VOIDS FROM RISING OR MOVING SIDEWAYS. AT LEAST SIX WEEKS PRIOR TO CASTING CORED SLABS, THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER FOR REVIEW AND COMMENT, DETAILED DRAWINGS OF THE PROPOSED HOLD-DOWN SYSTEM. IN ADDITION TO STRUCTURAL DETAILS, LOCATION AND SPACING OF THE HOLD-DOWNS SHALL BE INDICATED.

ALL REINFORCING STEEL IN THE VERTICAL CONCRETE BARRIER RAIL SHALL BE EPOXY COATED.

PRESTRESSING STRANDS SHALL BE CUT FLUSH WITH THE CORED SLAB UNIT ENDS.

APPLY EPOXY PROTECTIVE COATING TO CORED SLAB UNIT ENDS.

GROOVED CONTRACTION JOINTS, 1/2" IN DEPTH, SHALL BE TOOLED IN ALL EXPOSED FACES OF THE BARRIER RAIL AND IN ACCORDANCE WITH ARTICLE 825-10(B) OF THE STANDARD SPECIFICATIONS. A CONTRACTION JOINT SHALL BE LOCATED AT EACH THIRD POINT BETWEEN BARRIER RAIL EXPANSION JOINTS. ONLY ONE CONTRACTION JOINT IS REQUIRED AT MIDPOINT OF BARRIER RAIL SEGMENTS LESS THAN 20 FEET IN LENGTH AND NO CONTRACTION JOINTS ARE REQUIRED FOR THOSE SEGMENTS LESS THAN 10 FEET IN LENGTH.

FLAME CUTTING OF THE TRANSVERSE POST-TENSIONING STRAND IS NOT ALLOWED.

THE TRANSFER OF LOAD FROM THE ANCHORAGES TO THE CORED SLAB UNIT SHALL BE DONE WHEN THE CONCRETE HAS REACHED A COMPRESSIVE STRENGTH OF NOT LESS THAN THE REQUIRED STRENGTH SHOWN IN THE "CONCRETE RELEASE STRENGTH" TABLE.

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.

THE PERMITTED THREADED INSERTS ARE DETAILED AS AN OPTION FOR THE CONTRACTOR TO ATTACH FALSEWORK AND FORMWORK DURING CONSTRUCTION.

THE PERMITTED THREADED INSERTS IN THE EXTERIOR UNITS SHALL BE SIZED BY THE CONTRACTOR, SPACED AT 4'-0" CENTERS AND GALVANIZED IN ACCORDANCE WITH SECTION 1076 OF THE STANDARD SPECIFICATIONS. STAINLESS STEEL THREADED INSERTS MAY BE USED AS AN ALTERNATE.

THE PERMITTED THREADED INSERTS SHALL BE GROUTED BY THE CONTRACTOR IMMEDIATELY FOLLOWING REMOVAL OF THE FALSEWORK.


THE COST OF THE PERMITTED THREADED INSERTS SHALL BE INCLUDED IN THE PRICE BID FOR THE PRECAST UNITS.

PROJECT NO. 17BP.4.R.85

WAYNE COUNTY

STATION: 15+05.50 -L-

SHEET 3 OF 3



DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
804-C N. LAFAYETTE ST
SHELBY, NC 28150
PH (704) 476-0003
CORP. LICENSE NO.: C-0275

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

STANDARD
3'-0" X 1'-9"
PRESTRESSED CONCRETE
CORED SLAB UNIT
90° SKEW


REVISIONS

NO.	BY:	DATE:	NO.	BY:	DATE:
1			3		
2			4		




SHEET NO.

S-7
TOTAL
SHEETS
15

DRAWN BY : TBE
CHECKED BY : MGC
DATE : 3/18
DATE : 3/18



FOR LOCATION OF GUARDRAIL ANCHOR ASSEMBLY, SEE "PLAN" BELOW



LOCATION OF ANCHORS FOR GUARDRAIL

END BENT #1 SHOWN, END BENT #2 SIMILAR.

NOTES

THE GUARDRAIL ANCHOR ASSEMBLY SHALL CONSIST OF A 1/4" HOLD DOWN PLATE AND 7 - 7/8" Ø BOLTS WITH NUTS AND WASHERS.

THE HOLD-DOWN PLATE SHALL CONFORM TO AASHTO M270 GRADE 36. AFTER FABRICATION, THE HOLD-DOWN PLATE SHALL BE HOT-DIP GALVANIZED IN ACCORDANCE WITH AASHTO M111.

BOLTS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A307 AND NUTS SHALL CONFORM TO THE REQUIREMENTS OF AASHTO M291. BOLTS, NUTS AND WASHERS SHALL BE GALVANIZED. (AT THE CONTRACTOR'S OPTION, STAINLESS STEEL BOLTS, NUTS AND WASHERS MAY BE USED AS AN ALTERNATE FOR THE 7/8" Ø GALVANIZED BOLTS, NUTS AND WASHERS. THEY SHALL CONFORM TO OR EXCEED THE MECHANICAL REQUIREMENTS OF ASTM A307. THE USE OF THIS ALTERNATE SHALL BE APPROVED BY THE ENGINEER.)

THE GUARDRAIL ANCHOR ASSEMBLY IS REQUIRED AT ALL POINTS WHERE APPROACH GUARDRAIL IS TO BE ATTACHED TO THE END OF BARRIER RAIL. FOR POINTS OF ATTACHMENT, SEE SKETCH.

AFTER INSTALLATION, THE EXPOSED THREAD OF THE BOLT SHALL BE BURRED WITH A SHARP POINTED TOOL.

THE COST OF THE GUARDRAIL ANCHOR ASSEMBLY SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR VERTICAL CONCRETE BARRIER RAIL.

THE VERTICAL REINFORCING BARS MAY BE SHIFTED SLIGHTLY IN THE VERTICAL CONCRETE BARRIER RAIL TO CLEAR ASSEMBLY BOLTS.

THE 1 1/4" Ø HOLES SHALL BE FORMED OR DRILLED WITH A CORE BIT. IMPACT TOOLS WILL NOT BE PERMITTED. ANY CONCRETE DAMAGED BY THIS WORK SHALL BE REPAIRED TO THE SATISFACTION OF THE ENGINEER.



SKETCH SHOWING POINTS OF ATTACHMENT

* DENOTES GUARDRAIL ANCHOR ASSEMBLY

PROJECT NO. 17BP.4.R.85

WAYNE COUNTY

STATION: 15+05.50 -L-



DocuSigned by
Marshall G. Cheek, Jr.
4/2/2018

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
804-C N. LAFAYETTE ST
SHELBY, NC 28150
PH (704) 476-0003
CORP. LICENSE NO.: C-0275

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

STANDARD GUARDRAIL ANCHORAGE DETAILS FOR VERTICAL CONCRETE BARRIER RAIL

REVISIONS						SHEET NO.
NO.	BY	DATE	NO.	BY	DATE	
1			3			S-8
2			4			TOTAL SHEETS 15

DRAWN BY : TBE
CHECKED BY : MGC
DATE : 3/18
DATE : 3/18


NOTES

STIRRUPS IN CAP MAY BE SHIFTED AS NECESSARY TO CLEAR DOWELS.


THE CONCRETE IN THE SHADED AREA OF THE WING SHALL BE POURED AFTER THE VERTICAL CONCRETE BARRIER RAIL IS CAST IF SLIP FORMING IS USED.

FOR PILE SPLICE DETAILS, SEE SHEET 4 OF 4.

FOR WING DETAILS, SEE SHEET 3 OF 4.



PLAN



ELEVATION

WINGS NOT SHOWN FOR CLARITY.
FOR SECTION A-A, SEE SHEET 4 OF 4.
CONCRETE COLLARS FOR STEEL PILES NOT SHOWN IN PLAN AND ELEVATION VIEWS FOR CLARITY.
SEE "CORROSION PROTECTION FOR STEEL PILES DETAIL", SHEET 4 OF 4.

DRAWN BY : TBE
CHECKED BY : MGC
DATE : 3/18
DATE : 3/18

PROJECT NO. 17BP.4.R.85

WAYNE COUNTY

STATION: 15+05.50 -L-

SHEET 1 OF 4



DocuSigned by
Marshall G. Cheek, Jr. 4/2/2018

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED
TGS ENGINEERS
804-C N. LAFAYETTE ST
SHELBY, NC 28150
PH (704) 476-0003
CORP. LICENSE NO.: C-0275

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

SUBSTRUCTURE
END BENT No. 1


REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			S-9
2			4			TOTAL SHEETS 15

STD. NO. EB_33_90S4


FOR WING DETAILS, SEE SHEET 3 OF 4.




STD. NO. EB_33_90S4




PLAN OF WING (W1)




PLAN OF WING (W2)




ELEVATION OF WING (W1)



ELEVATION OF WING (W2)



SECTION X-X




SECTION Y-Y

PROJECT NO. 17BP.4.R.85

WAYNE COUNTY

STATION: 15+05.50 -L-

SHEET 3 OF 4



Marshall G. Cheek, Jr. 4/2/2018

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
804-C N. LAFAYETTE ST
SHELBY, NC 28150
PH (704) 476-0003
CORP. LICENSE NO.: C-0275

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH


SUBSTRUCTURE
END BENT
WING DETAILS

REVISIONS						SHEET NO.
NO.	BY	DATE	NO.	BY	DATE	
1			3			S-11
2			4			TOTAL SHEETS 15

DRAWN BY : TBE DATE : 3/18
CHECKED BY : MGC DATE : 3/18

WING DETAILS

STD. NO. EB_33_90S4




BAGGED STONE AND PIPE SHALL BE PLACED IMMEDIATELY AFTER COMPLETION OF END BENT EXCAVATION. PIPE MAY BE EITHER CONCRETE, CORRUGATED STEEL, CORRUGATED ALUMINUM ALLOY, OR CORRUGATED PLASTIC. PERFORATED PIPE WILL NOT BE ALLOWED.

BAGGED STONE SHALL REMAIN IN PLACE UNTIL THE ENGINEER DIRECTS THAT IT BE REMOVED. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF SILT ACCUMULATIONS AT BAGGED STONE WHEN SO DIRECTED BY THE ENGINEER. BAGS SHALL BE REMOVED AND REPLACED WHENEVER THE ENGINEER DETERMINES THAT THEY HAVE DETERIORATED AND LOST THEIR EFFECTIVENESS.


NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK AND THE ENTIRE COST OF THIS WORK SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR THE SEVERAL PAY ITEMS.

TEMPORARY DRAINAGE AT END BENT



DETAIL "A"


(END BENT No. 1 SHOWN, END BENT No. 2 SIMILAR BY ROTATION)



PLAN


CORROSION PROTECTION FOR STEEL PILES DETAIL

(END BENT No. 1 SHOWN, END BENT No. 2 SIMILAR BY ROTATION)




POSITION OF PILE DURING WELDING.

PILE SPLICE DETAILS




ELEVATION



SECTION A-A

(CONCRETE COLLAR NOT SHOWN FOR CLARITY. SEE "CORROSION PROTECTION FOR STEEL PILES DETAIL.")

BAR TYPES



ALL BAR DIMENSIONS ARE OUT TO OUT.

END BENT No. 1	END BENT No. 2
HP 12 X 53 STEEL PILES NO: 7 LIN. FT.= 350	HP 12 X 53 STEEL PILES NO: 7 LIN. FT.= 350
PILE DRIVING EQUIPMENT SETUP FOR HP 12 X 53 STEEL PILES EACH 7	PILE DRIVING EQUIPMENT SETUP FOR HP 12 X 53 STEEL PILES EACH 7
PILE REDRIVES EACH 4	PILE REDRIVES EACH 4

BILL OF MATERIAL

FOR ONE END BENT

BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
B1	8	#9		41'-0"	1115
B2	28	#4	STR	20'-7"	385
B3	10	#4	STR	2'-5"	16
D1	22	#6	STR	1'-6"	50
H1	40	#4	2	9'-4"	249
K1	16	#4	STR	2'-11"	31
S1	50	#4	3	10'-5"	348
S2	50	#4	4	3'-2"	106
S3	28	#4	5	6'-6"	122
V1	52	#4	STR	6'-2"	214

REINFORCING STEEL (FOR ONE END BENT) 2636 LBS.

CLASS A CONCRETE BREAKDOWN (FOR ONE END BENT)

POUR #1 CAP, LOWER PART OF WINGS & COLLARS 19.5 C.Y.

POUR #2 UPPER PART OF WINGS 2.1 C.Y.

TOTAL CLASS A CONCRETE 21.6 C.Y.

PROJECT NO. 17BP.4.R.85

WAYNE COUNTY

STATION: 15+05.50 -L-

SHEET 4 OF 4



DocuSigned by Marshall G. Cheek, Jr. 4/2/2018

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED
TGS ENGINEERS
804-C N. LAFAYETTE ST
SHELBY, NC 28150
PH (704) 476-0003
CORP. LICENSE NO.: C-0275

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

SUBSTRUCTURE


END BENT No. 1 & 2
DETAILS

REVISIONS



NO.	BY:	DATE:	NO.	BY:	DATE:	SHEET NO.
1			3			S-12
2			4			TOTAL SHEETS 15

DRAWN BY : TBE
CHECKED BY : MGC
DATE : 3/18
DATE : 3/18

NOTES :
FOR BERM WIDTH DIMENSIONS, SEE GENERAL DRAWING.



ESTIMATED QUANTITIES		
BRIDGE @ STA. 15+05.50 -L-	RIP RAP CLASS II	GEOTEXTILE FOR DRAINAGE
	TONS	SQUARE YARDS
END BENT 1	135	150
END BENT 2	145	160



PROJECT NO. 17BP.4.R.85
WAYNE COUNTY
STATION: 15+05.50 -L-




DocuSigned by
Marshall G. Cheek, Jr.
4/2/2018

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

TCS ENGINEERS
804-C N. LAFAYETTE ST
SHELBY, NC 28150
PH (704) 476-0003
CORP. LICENSE NO.: C-0275

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			S-13
2			4			TOTAL SHEETS 15

DRAWN BY : TBE DATE : 3/18
CHECKED BY : MGC DATE : 3/18



SPlice LENGTHS		
BAR SIZE	EPOXY COATED	UNCOATED
#4	2'-0"	1'-9"
#5	2'-6"	2'-2"
#6	3'-10"	2'-7"

NOTES

FOR BRIDGE APPROACH FILL INCLUDING GEOTEXTILE, 4" Ø DRAINAGE PIPE, AND SELECT MATERIAL BACKFILL, SEE ROADWAY PLANS.

GEOTEXTILE SHALL BE TYPE 1 IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS SECTION 1056.


SELECT MATERIAL BACKFILL (CLASS V OR CLASS VI) SHALL BE IN ACCORDANCE WITH STANDARD SPECIFICATIONS SECTION 1016.

SELECT MATERIAL BACKFILL IS TO BE CONTINUOUS ALONG FILL FACE OF BACKWALL FROM OUTSIDE EDGE TO OUTSIDE EDGE OF APPROACH SLAB.

FOR THE 4" Ø DRAINAGE PIPE OUTLET(S), SEE ROADWAY STANDARD DRAWINGS.


AREA BETWEEN THE WINGWALL AND APPROACH SLAB SHALL BE GRADED TO DRAIN THE WATER AWAY FROM THE FILL FACE OF THE BRIDGE AND SHALL BE PAVED. SEE ROADWAY PLANS.

APPROACH SLAB GROOVING IS NOT REQUIRED.



NOTE: IF THE APPROACH SLAB IS NOT CONSTRUCTED IMMEDIATELY AFTER THE BACKFILLING OF THE END BENT EXCAVATION, GRADE TO DRAIN TO THE BOTTOM OF THE SLOPE AND PROVIDE EROSION RESISTANT MATERIAL, SUCH AS FIBERGLASS ROVING OR AS DIRECTED BY THE ENGINEER TO PREVENT SOIL EROSION AND TO PROTECT THE AREA ADJACENT TO THE STRUCTURE. THE CONTRACTOR WILL BE REQUIRED TO REMOVE THESE MATERIALS PRIOR TO CONSTRUCTION OF THE APPROACH SLAB.

TEMPORARY DRAINAGE DETAIL



NOTE: IMMEDIATELY AFTER THE CONSTRUCTION OF THE APPROACH SLAB, THE CONTRACTOR SHALL PROVIDE TEMPORARY BERM AND SLOPE DRAIN. CONTRACTOR SHALL GRADE TO PIPE INLET AND PROVIDE EROSION RESISTANT MATERIAL AS SHOWN. THE EROSION RESISTANT MATERIAL SHALL BE EITHER 1) ASPHALT PLANT MIX, TYPE 1 OR TYPE 2, MIN. 2" DEPTH, 2) EROSION CONTROL MAT, OR 3) CONCRETE, AS DIRECTED BY THE ENGINEER. THE SLOPE DRAIN SHALL CONSIST OF A NON-PERFORATED TEMPORARY DRAINAGE PIPE, 12 INCHES IN DIAMETER.

PLAN VIEW

TEMPORARY BERM AND SLOPE DRAIN DETAILS

(TO BE USED WHEN SHOULDER BERM GUTTER IS REQUIRED)

PROJECT NO. 17BP.4.R.85

WAYNE COUNTY

STATION: 15+05.50 -L-

ASSEMBLED BY :	TBE	DATE :	3/18
CHECKED BY :	MGC	DATE :	3/18
DRAWN BY :	SHS/MAA 5-09	REV. 12-17	MAA/THC
CHECKED BY :	BCH 5-09		

DocuSigned by
Marshall G. Cheek, Jr.
4/2/2018

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

STANDARD
BRIDGE APPROACH SLAB
FOR PRESTRESSED CONCRETE
CORED SLAB UNIT
(SUB-REGIONAL TIER)
90° SKEW

REVISIONS						SHEET NO.
NO.	BY	DATE	NO.	BY	DATE	TOTAL SHEETS
1			3			S-14
2			4			15

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

TGS ENGINEERS
804-C N. LAFAYETTE ST
SHELBY, NC 28150
PH (704) 476-0003
CORP. LICENSE NO.: C-0275

STANDARD NOTES

DESIGN DATA:

SPECIFICATIONS	- - - - -	A.A.S.H.T.O. (CURRENT)
LIVE LOAD	- - - - -	SEE PLANS
IMPACT ALLOWANCE	- - - - -	SEE A.A.S.H.T.O.
STRESS IN EXTREME FIBER OF		
STRUCTURAL STEEL - AASHTO M270 GRADE 36	-	20,000 LBS. PER SQ. IN.
- AASHTO M270 GRADE 50W	-	27,000 LBS. PER SQ. IN.
- AASHTO M270 GRADE 50	-	27,000 LBS. PER SQ. IN.
REINFORCING STEEL IN TENSION		
GRADE 60	- -	24,000 LBS. PER SQ. IN.
CONCRETE IN COMPRESSION	- - - - -	1,200 LBS. PER SQ. IN.
CONCRETE IN SHEAR	- - - - -	SEE A.A.S.H.T.O.
STRUCTURAL TIMBER - TREATED OR		
UNTREATED - EXTREME FIBER STRESS	- - - - -	1,800 LBS. PER SQ. IN.
COMPRESSION PERPENDICULAR TO GRAIN OF TIMBER	- - - -	375 LBS. PER SQ. IN.
EQUIVALENT FLUID PRESSURE OF EARTH	- - - - -	30 LBS. PER CU. FT. (MINIMUM)

MATERIAL AND WORKMANSHIP:

EXCEPT AS MAY OTHERWISE BE SPECIFIED ON PLANS OR IN THE SPECIAL PROVISIONS, ALL MATERIAL AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE 2018 "STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES" OF THE N. C. DEPARTMENT OF TRANSPORTATION.

STEEL SHEET PILING FOR PERMANENT OR TEMPORARY APPLICATIONS SHALL BE HOT ROLLED.

CONCRETE:

UNLESS OTHERWISE REQUIRED ON PLANS, CLASS A CONCRETE SHALL BE USED FOR ALL PORTIONS OF ALL STRUCTURES WITH THE EXCEPTION THAT: CLASS AA CONCRETE SHALL BE USED IN BRIDGE SUPERSTRUCTURES, ABUTMENT BACKWALLS, AND APPROACH SLABS; AND CLASS B CONCRETE SHALL BE USED FOR SLOPE PROTECTION AND RIP RAP.

CONCRETE CHAMFERS:

UNLESS OTHERWISE NOTED ON THE PLANS, ALL EXPOSED CORNERS ON STRUCTURES SHALL BE CHAMFERED 3/4" WITH THE FOLLOWING EXCEPTIONS: TOP CORNERS OF CURBS MAY BE ROUNDED TO 1-1/2" RADIUS WHICH IS BUILT INTO CURB FORMS; CORNERS OF TRANSVERSE FLOOR EXPANSION JOINTS SHALL BE ROUNDED WITH A 1/4" FINISHING TOOL UNLESS OTHERWISE REQUIRED ON PLANS; AND CORNERS OF EXPANSION JOINTS IN THE ROADWAY FACES AND TOPS OF CURBS AND SIDEWALKS SHALL BE ROUNDED TO A 1/4" RADIUS WITH A FINISHING STONE OR TOOL UNLESS OTHERWISE REQUIRED ON PLANS.

DOWELS:

DOWELS WHEN INDICATED ON PLANS AS FOR CULVERT EXTENSIONS, SHALL BE EMBEDDED AT LEAST 12" INTO THE OLD CONCRETE AND GROUTED INTO PLACE WITH 1:2 CEMENT MORTAR.

DRAWN BY :	TBE	DATE :	3/18
CHECKED BY :	MGC	DATE :	3/18

ALLOWANCE FOR DEAD LOAD DEFLECTION, SETTLEMENT,
ETC. IN CASTING SUPERSTRUCTURES: _____

BRIDGES SHALL BE BUILT ON THE GRADE OR VERTICAL CURVE SHOWN ON PLANS.
SLABS, CURBS AND PARAPETS SHALL CONFORM TO THE GRADE OR CURVE.

ALL DIMENSIONS WHICH ARE GIVEN IN SECTION AND ARE AFFECTED BY DEAD LOAD DEFLECTIONS ARE DIMENSIONS AT CENTER LINE OF BEARING UNLESS OTHERWISE NOTED ON PLANS. IN SETTING FORMS FOR STEEL BEAM BRIDGES AND PRESTRESSED CONCRETE GIRDER BRIDGES, ADJUSTMENTS SHALL BE MADE DUE TO THE DEAD LOAD DEFLECTIONS FOR THE ELEVATIONS SHOWN. WHERE BLOCKS ARE SHOWN OVER BEAMS FOR BUILDING UP TO THE SLAB, THE VERTICAL DIMENSIONS OF THE BLOCKS SHALL BE ADJUSTED BETWEEN BEARINGS TO COMPENSATE FOR DEAD LOAD DEFLECTIONS, VERTICAL CURVE ORDINATE, AND ACTUAL BEAM CAMBER. WHERE BOTTOM OF SLAB IS IN LINE WITH BOTTOM OF TOP FLANGES, DEPTH OF SLAB BETWEEN BEARINGS SHALL BE ADJUSTED TO COMPENSATE FOR DEAD LOAD DEFLECTION, VERTICAL CURVE ORDINATE, AND ACTUAL BEAM CAMBER.

IN SETTING FALSEWORK AND FORMS FOR REINFORCED CONCRETE SPANS, AN ALLOWANCE SHALL BE MADE FOR DEAD LOAD DEFLECTIONS, SETTLEMENT OF FALSEWORK, AND PERMANENT CAMBER WHICH SHALL BE PROVIDED FOR IN ADDITION TO THE ELEVATIONS SHOWN. AFTER REMOVAL OF THE FALSEWORK, THE FINISHED STRUCTURES SHALL CONFORM TO THE PROFILE AND ELEVATIONS SHOWN ON THE PLANS AND CONSTRUCTION ELEVATIONS FURNISHED BY THE ENGINEER.

DETAILED DRAWINGS FOR FALSEWORK OR FORMS FOR BRIDGE SUPERSTRUCTURE AND ANY STRUCTURE OR PARTS OF A STRUCTURE AS NOTED ON THE PLANS SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL BEFORE CONSTRUCTION OF THE FALSEWORK OR FORMS IS STARTED.

REINFORCING STEEL:

ALL REINFORCING STEEL SHALL BE DEFORMED. DIMENSIONS RELATIVE TO PLACEMENT OF REINFORCING ARE TO CENTERS OF BARS UNLESS OTHERWISE INDICATED IN THE PLANS. DIMENSIONS ON BAR DETAILS ARE TO CENTERS OF BARS OR ARE OUT TO OUT AS INDICATED ON PLANS.

WIRE BAR SUPPORTS SHALL BE PROVIDED FOR REINFORCING STEEL WHERE INDICATED ON THE PLANS. WHEN BAR SUPPORT PIECES ARE PLACED IN CONTINUOUS LINES, THEY SHALL BE SO PLACED THAT THE ENDS OF THE SUPPORTING WIRES SHALL BE LAPPED TO LOCK LEGS ON ADJOINING PIECES.

STRUCTURAL STEEL:

AT THE CONTRACTOR'S OPTION, HE MAY SUBSTITUTE 7/8"Ø SHEAR STUDS FOR THE 3/4"Ø STUDS SPECIFIED ON THE PLANS. THIS SUBSTITUTION SHALL BE MADE AT THE RATE OF 3 - 7/8"Ø STUDS FOR 4 - 3/4"Ø STUDS, AND STUD SPACING CHANGES SHALL BE MADE AS NECESSARY TO PROVIDE THE SAME EQUIVALENT NUMBER OF 7/8"Ø STUDS ALONG THE BEAM AS SHOWN FOR 3/4"Ø STUDS BASED ON THE RATIO OF 3 - 7/8"Ø STUDS FOR 4 - 3/4"Ø STUDS. STUDS OF THE LENGTH SPECIFIED ON THE PLANS MUST BE PROVIDED. THE MAXIMUM SPACING SHALL BE 2'-0".

EXCEPT AT THE INTERIOR SUPPORTS OF CONTINUOUS BEAMS WHERE THE COVER PLATE IS IN CONTACT WITH BEARING PLATE, THE CONTRACTOR MAY, AT HIS OPTION, SUBSTITUTE FOR THE COVER PLATES DESIGNATED ON THE PLANS COVER PLATES OF THE EQUIVALENT AREA PROVIDED THESE PLATES ARE AT LEAST 5/16" IN THICKNESS AND DO NOT EXCEED A WIDTH EQUAL TO THE FLANGE WIDTH LESS 2" OR A THICKNESS EQUAL TO 2 TIMES THE FLANGE THICKNESS. THE SIZE OF FILLET WELDS SHALL CONFORM TO THE REQUIREMENTS OF THE CURRENT ANSI/AASHTO/AWS "BRIDGE WELDING CODE". ELECTROSLAG WELDING WILL NOT BE PERMITTED.

WITH THE SOLE EXCEPTION OF EDGES AT SURFACES WHICH BEAR ON OTHER SURFACES, ALL SHARP EDGES AND ENDS OF SHAPES AND PLATES SHALL BE SLIGHTLY ROUNDED BY SUITABLE MEANS TO A RADIUS OF APPROXIMATELY 1/16 INCH OR EQUIVALENT FLAT SURFACE AT A SUITABLE ANGLE PRIOR TO PAINTING, GALVANIZING, OR METALLIZING.

HANDRAILS AND POSTS:

METAL STANDARDS AND FACES OF THE CONCRETE END POSTS FOR THE METAL RAIL SHALL BE SET NORMAL TO THE GRADE OF THE CURB, UNLESS OTHERWISE SHOWN ON PLANS. THE METAL RAIL AND TOPS OF CONCRETE POSTS USED WITH THE ALUMINUM RAIL SHALL BE BUILT PARALLEL TO THE GRADE OF THE CURB.

METAL HANDRAILS SHALL BE IN ACCORDANCE WITH THE PLANS. RAILS SHALL BE AS MANUFACTURED FOR BRIDGE RAILING. CASTINGS SHALL BE OF A UNIFORM APPEARANCE. FINISHES AND OTHER DEFORMATIONS RESULTING FROM CASTING OR OTHERWISE SHALL BE

BE OBTAINED. CASTINGS WITH DISCOLORATIONS OR OF NON-UNIFORM COLORING WILL NOT BE ACCEPTED. CERTIFIED MILL REPORTS ARE REQUIRED FOR METAL RAILS AND POSTS

SPECIAL NOTES:

GENERALLY, IN CASE OF DISCREPANCY, THIS STANDARD SHEET OF NOTES SHALL GOVERN OVER THE SPECIFICATIONS, BUT THE REMAINDER OF THE PLANS SHALL GOVERN OVER NOTES HEREON, AND SPECIAL PROVISIONS SHALL GOVERN OVER ALL. SEE SPECIFICATIONS ARTICLE 105-4.

PROJECT NO. 17BP.4.R.85

WAYNE COUNTY

STATION: 15+05.50 -L-

	STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH																										
SEAL 020125 ENGINEER MARSHALL G. CHEEK, JR. (Decal) Marshall G. Cheek, Jr. 4/2/2018	STANDARD NOTES																										
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="6">REVISIONS</th> <th style="width: 15%;">SHEET NO.</th> </tr> <tr> <th>NO.</th> <th>BY:</th> <th>DATE:</th> <th>NO.</th> <th>BY:</th> <th>DATE:</th> <th rowspan="3" style="text-align: center; vertical-align: middle;"> TOTAL SHEETS 15 </th> </tr> <tr> <td style="text-align: center;">1</td> <td></td> <td></td> <td style="text-align: center;">3</td> <td></td> <td></td> </tr> <tr> <td style="text-align: center;">2</td> <td></td> <td></td> <td style="text-align: center;">4</td> <td></td> <td></td> </tr> </table>	REVISIONS						SHEET NO.	NO.	BY:	DATE:	NO.	BY:	DATE:	TOTAL SHEETS 15	1			3			2			4		
REVISIONS						SHEET NO.																					
NO.	BY:	DATE:	NO.	BY:	DATE:	TOTAL SHEETS 15																					
1			3																								
2			4																								

STD. NO. SM