

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

ROY COOPER J. ERIC BOYETTE GOVERNOR SECRETARY

June 2, 2023

Addendum No. 1

RE: **DD00423 Nash County**

To Whom It May Concern:

Reference is The following made to the above-mentioned project. changes/additions/deletions have been made:

- 1. An error was made on the map number for the DMV Parking Lot in reference to the Intermediate Contract Time Number 3. Please replace ICT 3 on page 8 of the proposal with the revised page attached.
- 2. An error was made on the type of pavement markings that are required for the DMV Parking Lot. 4" Paint Pavement Marking Lines will replace the 4" Hot Spray Thermoplastic Lines. Please replace page 2 of the Summary of Quantities in the proposal and the proposal item sheets with the attached proposal item sheets dated Jun 02, 2023.
- 3. An error was made on the milling items in reference to the depths and quantities. The Summary of Quantities reflects the correct items. The correction has been made on the proposal item sheets attached.

This sheet and attachments shall be made a part of the plans and bid documents and shall be submitted with the bid. Bids submitted without the addenda and attachments will be considered non-responsive.

If there are any questions, please contact me at (252) 640-6433.

Sincerely,

-DocuSigned by: Vickie P. Gardner BD9FE36C1AA642B...

Vickie P. Gardner

Division Four Contract Engineer

VPG/ Attachments

Mailing Address: NC DEPARTMENT OF TRANSPORTATION DIVISION FOUR OFFICE POST OFFICE BOX 3165 WILSON, NC 27895

Telephone: (252) 640-6400 Fax: (252) 234-6174

Customer Service: 1-877-368-4968

Location: 509 WARD BOULEVARD WILSON, NC 27895

Website: www.ncdot.gov

INTERMEDIATE CONTRACT TIME NUMBER 2 AND LIQUIDATED DAMAGES:

The Contractor shall adhere to the time limitations for replacement of pavement markings provided by the Contract and Standard Specifications as applicable for each map given the facility and marking type.

The date of availability for this intermediate contract time for each facility type and pavement marking type will be the date when the Contractor elects to obliterate or overlay the existing markings on any particular map or portion thereof.

The completion date for this intermediate contract time for pavement marking replacement will be the replacement deadline date based on facility type and marking type governed by the Contract and Standard Specifications after the date of availability.

The liquidated damages are **Five Hundred Dollars** (\$500.00) per calendar day.

INTERMEDIATE CONTRACT TIME NUMBER 3 AND LIQUIDATED DAMAGES:

(2-20-07)

108

SP1 G14 A

The Contractor shall complete the required work of installing, maintaining, and removing the traffic control devices for lane closures and restoring traffic to the existing traffic pattern. The Contractor shall not close or narrow a lane of traffic on **the following Maps** during the following time restrictions:

DAY AND TIME RESTRICTIONS

All Maps (Except Map #7) Monday thru Sunday 9:00PM to 6:00AM

Map #7 – DMV Parking Lot (2617 N. Wesleyan Blvd)
Monday Thru Friday
7:00 AM to 6:00 PM

In addition, the Contractor shall not close or narrow a lane of traffic on **Any Map (except Map #5)**, detain and/or alter the traffic flow on or during holidays, holiday weekends, special events, or any other time when traffic is unusually heavy, including the following schedules:

HOLIDAY AND HOLIDAY WEEKEND LANE CLOSURE RESTRICTIONS

- 1. For **unexpected occurrence** that creates unusually high traffic volumes, as directed by the Engineer.
- 2. For New Year's Day, between the hours of 6:00am December 31st and 7:00pm January 2nd. If New Year's Day is on a Friday, Saturday, Sunday or Monday, then until 7:00pm the following Tuesday.

PROJECT NO.	SHEET NO.	TOTAL NO.		
2023CPT.04.21.20641,				
48184.01K	2	2		

THERMOPLASTIC AND PAINT QUANTITIES

										4413000000-E	4457000000-N	4810000000-E	484000000-N	484500	0000-N	48900	00000-E
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE	LENGTH	WIDTH	WORK ZONE	TEMPORARY	PAINT	PAINT	PAINT	PAINT STR	4" WHITE	4" YELLOW
							TYPE			ADVANCE/GE	TRAFFIC	PAVEMENT	"RESERVED"	HANDICAP	ARROW	HOT SPRAY	HOT SPRAY
										NERAL	CONTROL	MARKING	PAVEMENT	PAVEMENT		THERMO	THERMO
										WARNING		LINES (4")	MARKING	MARKING			
										SIGNING			CHARACTER	SYMBOL			
								MI	FT	SF	LS	LF	EA	EA	EA	LF	LF
2023CPT.04.1.20641	Nash	1	SR-1310 / EDWARDS RD	FROM SR-1321 TO NC-58	1	2	2WU	6.59	20	316	0.40					69,590	43,494
	TOTAL F	OR MAP N	0.1					6.59		316	0.40					69,590	43,494
2023CPT.04.21.20641	Nash	2	SR-1310 / TAYLORS GIN RD	FROM NC-58 TO SR-1004	1	2	2WU	3.62	22	174	0.22					38,227	23,892
	TOTAL F	OR MAP N						3.62		174	0.22					38,227	23,892
2023CPT.04.21.20641	Nash	3	SR-1310 / W HILLARDSTON RD	FROM SR-1004 TO START OF C&G	1 & 2	2	2WU	1.75	22	84	0.10					18,480	11,550
	TOTAL F	OR MAP N	0.3					1.75		84	0.10					18,480	11,550
				FROM START OF C&G TO END OF													
2023CPT.04.21.20641	Nash	4	SR-1310 / W HILLARDSTON RD	C&G	3	2		0.23	22	11	0.01					2,429	1,518
	TOTAL F	OR MAP N	0.4					0.23		11	0.01					2,429	1,518
2023CPT.04.21.20641	Nash	5	SR-1310 / W HILLARDSTON RD	FROM END OF C&G TO NC-43	1	2	2WU	1.6	22	77	0.10						
	TOTAL F	OR MAP N	0.5					1.6		77	0.10						
2023CPT.04.21.20641	Nash	6	SR-1310 / E HILLARDSTON RD	FROM NC-43 TO SR-1500	1	2	2WU	1.12	22	54	0.07					11,827	7,392
	TOTAL F	OR MAP N	O. 6					1.12		54	0.07					11,827	7,392
TOTAL FOR PROJ NO. 2023CPT.04.21.20641							14.91		716	0.90					140,553	87,846	
															228	,399	
					1	1		ı						I		1	
				DMV PARKING LOT LOCATED @ 2617													
48184.01K	Nash	7	US-301 @ DMV PARKING LOT	N. WESLEYAN BLVD	4	2	2WU		140		0.10	4,370	96	6	8		
	TOTAL F	OR MAP N	0.7					0.043			0.100	4,370	96	6	8		
TOTAL FOR PROJ NO. 48184.01K							0.043			0.100	4,370	96	6	8			
													14				
								14.953		716	1.000	4,370	96	6	8	140,553	87,846
	GRAND TOTAL							14.933		/10	1.000	4,370	30	-	<u> </u>		37,840
												Ĺ			220	,,,,,,	

Jun 02, 2023 10:45 AM

County: NASH

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount			
ROADWAY ITEMS									
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.				
0002	1220000000-E	545	INCIDENTAL STONE BASE	185 TON					
0003	1297000000-E	607	MILLING ASPHALT PAVEMENT, ***" DEPTH (1.5")	3,945 SY					
0004	1330000000-E	607	INCIDENTAL MILLING	1,500 SY					
0005	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	13,565 TON					
0006	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	916 TON					
0007	1704000000-E	SP	PATCHING EXISTING PAVEMENT	150 TON					
0008	2605000000-N	848	CONCRETE CURB RAMPS	4 EA					
0009	4413000000-E	SP	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	716 SF					
0010	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.				
0011	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	96 EA					
0012	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	14 EA					
0013	489000000-E	SP	GENERIC PAVEMENT MARKING ITEM HOT SPRAY THERMOPLASTIC PM LINES (4", 50 MILS)	228,399 LF					
0014	1297000000-E	607	MILLING ASPHALT PAVEMENT, ***" DEPTH (1.25")	4,000 SY					
0015	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,370 LF					