DRAINAGE SUMMARY TABLE

STATION	LOCATION (LT, RT, OR CL)'	STRUCTURE NO. FROM	STRUCTURE NO. TO	TOP ELEVATION	INVERT ELEVATION	INVERT ELEVATION	R.C. PIPE CLASS III 12"	15"	18"	24"	30"	36"	42"	48"	QUANTITIES FOR DRAINAGE STRUCTURES PER EACH (0' THRU 5.0')	*TOTAL L.F. FOR PAY QUANTITY SHALL BE COL. 'A' + (1.3 X COL. 'B') LIN. FT. A 5.0' THRU 10.0'	B 10.0' AND ABOVE	G.D.I. (N.S.) FR. WITH TWO FLAT GRATES. STD. 840.29	T.B.D.I. STD. 840.35	REMARKS
SHEET 4																				
-L- 13+26.00	LT	0401		112.06											1			1	1	
-L- 13+26.00	LT	0401	0402		106.54	106.45			28											
-L- 13+15.00	RT	0403		112.10											1			1	1	
-L- 13+15.00	RT	0403	0404		106.73	106.64			32											
TOTAL									60						2			2	2	

ABBREVIATIONS

C.B.	CATCH BASIN
N.D.I.	NARROW DROP INLET
D.I.	DROP INLET
G.D.I.	GRATED DROP INLET
G.D.I.(N.S.)	(NARROW SLOT)
J.B.	JUNCTION BOX
M.H.	MANHOLE
T.B.D.I.	TRAFFIC BEARING DROP INLET
T.B.J.B.	TRAFFIC BEARING JUNCTION BOX

8/17/99

4/18/2018
R:\Roadway\Proj\950053_rdg_psh03D-1.dgn
mmaso