



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

July 20, 2021

Addendum No. 2

RE: **DD00355**
Wilson County

To Whom It May Concern:


Reference is made to the above-mentioned project. The following changes/additions/deletions have been made:

1. The line item for Directional Drilling was inadvertently omitted from the Item Sheets. This line item has been added and the 6" Water Line quantity has been changed. Please replace the Proposal Item Sheets in the proposal with the attached sheets dated July 20, 2021.

This sheet and attachments shall be made a part of the plans and bid documents and shall be submitted with the bid. Bids submitted without the addenda and attachments will be considered non-responsive.

If there are any questions, please contact me at (252) 640-6433.

Sincerely,

DocuSigned by:

BD9FE36C1AA642B...

7/20/2021

Vickie P. Gardner
Division Four Contract Engineer

VPG/

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0030000000-N	SP	TYPE II MODIFIED APPROACH FILL, STATION ***** STATION -L- 15+29.00	Lump Sum	L.S.	
0005	0036000000-E	225	UNDERCUT EXCAVATION	300 CY		
0006	0043000000-N	226	GRADING	Lump Sum	L.S.	
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA-TION	300 SY		
0009	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0010	1330000000-E	607	INCIDENTAL MILLING	170 SY		
0011	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	230 TON		
0012	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	210 TON		
0013	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	25 TON		
0014	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY		
0015	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	200 SY		
0016	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	34 CY		
0017	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0018	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0019	2077000000-E	815	6" OUTLET PIPE	6 LF		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	2556000000-E	846	SHOULDER BERM GUTTER	60		LF
0021	2570000000-N	SP	MODIFIED CONCRETE FLUME	1		EA
0022	3030000000-E	862	STEEL BEAM GUARDRAIL	75		LF
0023	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5		EA
0024	3215000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE III	4		EA
0025	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	4		EA
0026	3649000000-E	876	RIP RAP, CLASS B	32		TON
0027	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	430		SY
0028	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	529		SF
0029	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	83		SF
0030	4445000000-E	1145	BARRICADES (TYPE III)	48		LF
0031	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM HOT SPRAY THERMOPLASTIC PM LINES (4", 50 MILS)	1,700		LF
0032	5325600000-E	1510	6" WATER LINE	146		LF
0033	5540000000-E	1515	6" VALVE	2		EA
0034	5800000000-E	1530	ABANDON 6" UTILITY PIPE	318		LF
0035	6000000000-E	1605	TEMPORARY SILT FENCE	1,100		LF
0036	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75		TON
0037	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	5		TON
0038	6012000000-E	1610	SEDIMENT CONTROL STONE	50		TON

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	6015000000-E	1615	TEMPORARY MULCHING	0.5	ACR	
0040	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0041	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5	TON	
0042	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
0043	6029000000-E	SP	SAFETY FENCE	325	LF	
0044	6030000000-E	1630	SILT EXCAVATION	10	CY	
0045	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,550	SY	
0046	6037000000-E	SP	COIR FIBER MAT	100	SY	
0047	6042000000-E	1632	1/4" HARDWARE CLOTH	5	LF	
0048	6070000000-N	1639	SPECIAL STILLING BASINS	2	EA	
0049	6071012000-E	SP	COIR FIBER WATTLE	175	LF	
0050	6071014000-E	SP	COIR FIBER WATTLE BARRIER	250	LF	
0051	6084000000-E	1660	SEEDING & MULCHING	0.5	ACR	
0052	6087000000-E	1660	MOWING	0.5	ACR	
0053	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0054	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.3	TON	
0055	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0056	6108000000-E	1665	FERTILIZER TOPDRESSING	0.3	TON	
0057	6111000000-E	SP	IMPERVIOUS DIKE	375	LF	
0058	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
0059	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25	EA	

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0060	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0061	6123000000-E	1670	REFORESTATION	0.1 ACR		
0077	5872600000-E	1550	DIRECTIONAL DRILLING OF *** (6" FUSIBLE PVC)	208 LF		
STRUCTURE ITEMS						
0062	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** STATION -L- 15+29.00	Lump Sum	L.S.	
0063	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0064	8112730000-N	450	PDA TESTING	1 EA		
0065	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** STATION -L- 15+29.00	Lump Sum	L.S.	
0066	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	44.4 CY		
0067	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** STATION -L- 15+29.00	Lump Sum	L.S.	
0068	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,428 LB		
0069	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES HP 12 X 53	14 EA		
0070	8355000000-E	450	HP ***X*** STEEL PILES 12 X 53	14 LF		
0071	8393000000-N	450	PILE REDRIVES	8 EA		
0072	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	90.25 LF		
0073	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	185 TON		
0074	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	205 SY		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0076	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	495 LF		

1428/Jul20/Q16722.15/D374505656000/E77

Total Amount Of Bid For Entire Project :