



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

JAMES H. TROGDON, III
SECRETARY

August 2, 2017

Addendum No. 2

RE: DATE AND TIME OF BID OPENING: August 8, 2017 AT 2:00 PM
CONTRACT ID: DD00214
WBS ELEMENT NO.: 17BP.4.R.71, 17BP.4.R.72
FEDERAL AID NO.: STATE FUNDED
COUNTY: Johnston County
TIP NO.: B-500232, B-500239
MILES: 0.161 MILES
ROUTE NO.: SR 2110, SR 2129
**LOCATION: BRIDGE NO. 232 ON SR 2110 (GLENDALE ROAD) OVER
LITTLE BUFFALO CREEK & BRIDGE NO. 239 ON SR
2129 (WOODRUFF ROAD) OVER BUFFALO CREEK**
**TYPE OF WORK: GRADING, DRAINAGE, PAVING AND
STRUCTURE**

To Whom It May Concern:

Reference is made to the above-mentioned project. The following changes/additions/deletions have been made:

1. Pay Item 0079 was added to the Proposal Item Sheets. It is for Spiral Column Reinforcing Steel - Item 8238000000-E. Replace the Itemized Proposal Sheets for Contract No. DD00214 dated Jul 17, 2017 with the attached Itemized Proposal Sheets for Contract No. DD00214 dated Aug 2, 2017.

This sheet and attachments shall be made a part of the plans and bid documents and shall be submitted with the bid. Bids submitted without the addenda and attachments will be considered non-responsive.

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION FOUR OFFICE
POST OFFICE BOX 3165
WILSON, NC 27895


Telephone: (252) 640-6400
Fax: (252) 234-6174
Customer Service: 1-877-368-4968

Location:
509 WARD BOULEVARD
WILSON, NC 27895

Website: www.ncdot.gov

If there are any questions, please contact me at (252) 640-6400.

Sincerely,

DocuSigned by:

-BC8FE3BCFE014EA...
8/2/2017

J. Charles Cauley
Division Four Contracts and Proposals Engineer

JCC/
Attachment

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (STA. 13+66.50)	Lump Sum	L.S.	
0004	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (STA. 15+43.50)	Lump Sum	L.S.	
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	2 ACR		
0007	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	20 TON		
0008	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	20 SY		
0009	0335200000-E	305	15" DRAINAGE PIPE	52 LF		
0010	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0011	1330000000-E	607	INCIDENTAL MILLING	535 SY		
0012	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	230 TON		
0013	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	430 TON		
0014	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	45 TON		
0015	2000000000-N	806	RIGHT OF WAY MARKERS	14 EA		
0016	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0017	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0018	2556000000-E	846	SHOULDER BERM GUTTER	48 LF		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	3030000000-E	862	STEEL BM GUARDRAIL	50		LF
0020	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10		EA
0021	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	8		EA
0022	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	4		EA
0023	3288000000-N	SP	GUARDRAIL END UNITS, TYPE TL-2	4		EA
0024	3635000000-E	876	RIP RAP, CLASS II	20		TON
0025	3649000000-E	876	RIP RAP, CLASS B	40		TON
0026	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,560		SY
0027	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	678		SF
0028	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	225		SF
0029	4445000000-E	1145	BARRICADES (TYPE III)	176		LF
0030	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,299		LF
0031	6000000000-E	1605	TEMPORARY SILT FENCE	1,515		LF
0032	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	125		TON
0033	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	70		TON
0034	6012000000-E	1610	SEDIMENT CONTROL STONE	350		TON
0035	6015000000-E	1615	TEMPORARY MULCHING	2		ACR
0036	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200		LB
0037	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1		TON

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6024000000-E	1622	TEMPORARY SLOPE DRAINS	400		
					LF	
0039	6029000000-E	SP	SAFETY FENCE	400		
					LF	
0040	6030000000-E	1630	SILT EXCAVATION	40		
					CY	
0041	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,600		
					SY	
0042	6037000000-E	SP	COIR FIBER MAT	200		
					SY	
0043	6042000000-E	1632	1/4" HARDWARE CLOTH	400		
					LF	
0044	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	550		
					SY	
0045	6070000000-N	1639	SPECIAL STILLING BASINS	14		
					EA	
0046	6071020000-E	SP	POLYACRYLAMIDE (PAM)	15		
					LB	
0047	6084000000-E	1660	SEEDING & MULCHING	6		
					ACR	
0048	6087000000-E	1660	MOWING	1		
					ACR	
0049	6090000000-E	1661	SEED FOR REPAIR SEEDING	100		
					LB	
0050	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5		
					TON	
0051	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100		
					LB	
0052	6108000000-E	1665	FERTILIZER TOPDRESSING	1		
					TON	
0053	6111000000-E	SP	IMPERVIOUS DIKE	260		
					LF	
0054	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	20		
					EA	
0055	6123000000-E	1670	REFORESTATION	0.2		
					ACR	
0056	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (CONCRETE WASHOUT STRUCTURE)	4		
					EA	
0057	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (STA. 13+57)	Lump Sum	L.S.	

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (STA. 13+66.50)	Lump Sum	L.S.	
0059	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (STA. 15+43.50)	Lump Sum	L.S.	
0060	8108000000-E	411	***-*** DIA DRILLED PIERS (3'-0")	200.25 LF		
0061	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	47.96 LF		
0062	8113000000-N	411	SID INSPECTIONS	2 EA		
0063	8114000000-N	411	SPT TESTING	2 EA		
0064	8115000000-N	411	CSL TESTING	2 EA		
0065	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (STA. 13+66.50)	Lump Sum	L.S.	
0066	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (STA. 15+43.50)	Lump Sum	L.S.	
0067	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	109.3 CY		
0068	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (STA. 13+66.50)	Lump Sum	L.S.	
0069	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (STA. 15+43.50)	Lump Sum	L.S.	
0070	8217000000-E	425	REINFORCING STEEL (BRIDGE)	29,915 LB		
0071	8364000000-E	450	HP12X53 STEEL PILES	303 LF		
0072	8391000000-N	450	STEEL PILE POINTS	10 EA		
0073	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	460.77 LF		
0074	8590000000-E	876	RIP RAP, CLASS ** (II, 2'-0" THICK)	270 TON		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0076	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	2,300 LF		
0077	8860000000-N	SP	GENERIC STRUCTURE ITEM (ASBESTOS ASSESSMENT)	Lump Sum	L.S.	
0078	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (STA. 15+50)	Lump Sum	L.S.	
0079	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,939 LB		
1727/Aug02/Q55526.98/D410051920000/E79			Total Amount Of Bid For Entire Project :			