



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

J. ERIC BOYETTE  
SECRETARY

July 28, 2022

**Addendum No. 1**

RE: **DD00375**  
**Halifax County**

To Whom It May Concern:

Reference is made to the above-mentioned project. The following additions have been made:

1. The 8" water line quantity was inadvertently miscalculated. The correct quantity for 8" water line should be 640 LF. Please replace the Proposal Item Sheets in the proposal with the attached sheets dated Jul 28, 2022.

**This sheet and attachments shall be made a part of the plans and bid documents and shall be submitted with the bid. Bids submitted without the addenda and attachments will be considered non-responsive.**

If there are any questions, please contact me at (252) 640-6433.

Sincerely,

DocuSigned by:  
*Vickie P. Gardner*  
BD9FE36C1AA642B...

07/28/2022

Vickie P. Gardner  
Division Four Contract Engineer

VPG/  
Attachment

County: HALIFAX

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	TYPE II MODIFIED APPROACH FILL, STATION ***** (12+07.70 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	100 SY		
0009	1220000000-E	545	INCIDENTAL STONE BASE	40 TON		
0010	1330000000-E	607	INCIDENTAL MILLING	230 SY		
0011	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	275 TON		
0012	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	400 TON		
0013	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	40 TON		
0014	2022000000-E	815	SUBDRAIN EXCAVATION	50 CY		
0015	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	200 SY		
0016	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	35 CY		
0017	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		

County: HALIFAX

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0019	2077000000-E	815	6" OUTLET PIPE	6 LF		
0020	2556000000-E	846	SHOULDER BERM GUTTER	82 LF		
0021	2570000000-N	SP	MODIFIED CONCRETE FLUME	2 EA		
0022	2619000000-E	850	4" CONCRETE PAVED DITCH	20 SY		
0023	3030000000-E	862	STEEL BEAM GUARDRAIL	112.5 LF		
0024	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0025	3215000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0026	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	4 EA		
0027	3635000000-E	876	RIP RAP, CLASS II	125 TON		
0028	3649000000-E	876	RIP RAP, CLASS B	150 TON		
0029	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	520 SY		
0030	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	435 SF		
0031	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0032	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0033	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINES (4", 50 MILS)	1,750 LF		
0034	5325800000-E	1510	8" WATER LINE	640 LF		

County: HALIFAX

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	440 LB		
0036	5546000000-E	1515	8" VALVE	2 EA		
0037	5801000000-E	1530	ABANDON 8" UTILITY PIPE	627 LF		
0038	5872600000-E	1550	DIRECTIONAL DRILLING OF *** (8")	600 LF		
0039	6000000000-E	1605	TEMPORARY SILT FENCE	3,750 LF		
0040	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	65 TON		
0041	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	5 TON		
0042	6012000000-E	1610	SEDIMENT CONTROL STONE	30 TON		
0043	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0044	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0045	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0046	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0047	6029000000-E	SP	SAFETY FENCE	350 LF		
0048	6030000000-E	1630	SILT EXCAVATION	25 CY		
0049	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,300 SY		
0050	6037000000-E	SP	COIR FIBER MAT	100 SY		
0051	6042000000-E	1632	1/4" HARDWARE CLOTH	150 LF		

County: HALIFAX

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	100 SY		
0053	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0054	6087000000-E	1660	MOWING	0.5 ACR		
0055	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0056	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.3 TON		
0057	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0058	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0059	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0060	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
0061	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0062	6123000000-E	1670	REFORESTATION	0.1 ACR		
<b>STRUCTURE ITEMS</b>						
0063	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+07.70 -L-)	Lump Sum	L.S.	
0064	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0065	8112730000-N	450	PDA TESTING	2 EA		
0066	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (12+07.70 -L-)	Lump Sum	L.S.	
0067	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	49.8 CY		

County: HALIFAX

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0068	821000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (11+50.58 -L-, 12+72.82 -L-)	Lump Sum	L.S.	
0069	821700000-E	425	REINFORCING STEEL (BRIDGE)	8,502 LB		
0070	832820000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (HP12X53)	14 EA		
0071	832820000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (HP14X73)	16 EA		
0072	836400000-E	450	HP 12 X 53 STEEL PILES	910 LF		
0073	838400000-E	450	HP 14 X 73 STEEL PILES	1,280 LF		
0074	839300000-N	450	PILE REDRIVES	16 EA		
0075	850300000-E	460	CONCRETE BARRIER RAIL	220.8 LF		
0076	860800000-E	876	RIP RAP CLASS II (2'-0" THICK)	218 TON		
0077	862200000-E	876	GEOTEXTILE FOR DRAINAGE	242 SY		
0078	865700000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0079	876200000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,210 LF		

1405/Jul28/Q26647/D384617030000/E79

Total Amount Of Bid For Entire Project :