



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

J. ERIC BOYETTE  
SECRETARY

October 5, 2022

**Addendum No. 1**

RE: **DD00400**  
**Johnston County**

To Whom It May Concern:


Reference is made to the above-mentioned project. The following additions/changes have been made:

1. The typical sections show 1.5" milling, however only Incidental Milling was included in the itemized proposal. The item for Milling Asphalt Pavement, 1.5" Depth has been added and the quantity for Incidental Milling has been corrected. Please replace the Proposal Item Sheets in the proposal with the attached sheets dated Oct 05, 2022.

***This sheet and attachments shall be made a part of the plans and bid documents and shall be submitted with the bid. Bids submitted without the addenda and attachments will be considered non-responsive.***

If there are any questions, please contact me at (252) 640-6433.

Sincerely,

DocuSigned by:  
  
BD9FE36C1AA642B...

10/05/2022

Vickie P. Gardner  
Division Four Contract Engineer

VPG/  
Attachment

County: JOHNSTON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	55 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	300 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	50 TON		
0009	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	150 SY		
0010	0343000000-E	310	15" SIDE DRAIN PIPE	184 LF		
0011	0448500000-E	310	30" RC PIPE CULVERTS, CLASS IV	184 LF		
0012	0448600000-E	310	36" RC PIPE CULVERTS, CLASS IV	56 LF		
0013	0995000000-E	340	PIPE REMOVAL	179 LF		
0014	1099500000-E	505	SHALLOW UNDERCUT	100 CY		
0015	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	150 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0017	1330000000-E	607	INCIDENTAL MILLING	200 SY		

County: JOHNSTON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	700 TON		
0019	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	700 TON		
0020	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	80 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		
0022	2209000000-E	838	ENDWALLS	4 CY		
0023	2253000000-E	840	PIPE COLLARS	1 CY		
0024	2264000000-E	840	PIPE PLUGS	1 CY		
0025	2612000000-E	848	6" CONCRETE DRIVEWAY	20 SY		
0026	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	5 EA		
0027	3628000000-E	876	RIP RAP, CLASS I	50 TON		
0028	3649000000-E	876	RIP RAP, CLASS B	60 TON		
0029	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	480 SY		
0030	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	42.5 SF		
0031	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	54 LF		
0032	4102000000-N	904	SIGN ERECTION, TYPE E	4 EA		
0033	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	2 EA		
0034	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	

County: JOHNSTON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	6,985 LF		
0036	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	4 EA		
0037	6000000000-E	1605	TEMPORARY SILT FENCE	1,150 LF		
0038	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	90 TON		
0039	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	250 TON		
0040	6012000000-E	1610	SEDIMENT CONTROL STONE	85 TON		
0041	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
0042	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0043	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1 TON		
0044	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0045	6029000000-E	SP	SAFETY FENCE	320 LF		
0046	6030000000-E	1630	SILT EXCAVATION	130 CY		
0047	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,200 SY		
0048	6037000000-E	SP	COIR FIBER MAT	100 SY		
0049	6042000000-E	1632	1/4" HARDWARE CLOTH	20 LF		
0050	6070000000-N	1639	SPECIAL STILLING BASINS	1 EA		
0051	6071020000-E	SP	POLYACRYLAMIDE (PAM)	50 LB		

County: JOHNSTON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0053	6087000000-E	1660	MOWING	1.5 ACR		
0054	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0055	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0056	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0057	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
0058	6111000000-E	SP	IMPERVIOUS DIKE	100 LF		
0059	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0060	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
0061	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0062	6123000000-E	1670	REFORESTATION	0.1 ACR		
0063	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1.5")	1,150 SY		

1119/Oct05/Q18232.1/D226707820000/E63

Total Amount Of Bid For Entire Project :