



County of Wayne
Ivey Drive Extension



Addendum No. 1

Date: May 10, 2023

Project: Ivey Drive Extension

To: All Bidders

The following item(s) may modify, add to, or subtract from the contract documents, plans, specifications, and previous addenda, if any, for the Ivey Drive Extension Project located in Wayne County, NC. This addendum is issued prior to the receipt of bids and does hereby become a part of the specifications and plans and supersedes original specifications and plans in case of conflict. Each contractor shall be responsible for issuing information contained herein to subcontractors.

Acknowledge receipt of this addendum in your bid proposal form.

General Comments from Pre-Bid Meeting

- Overview of current project was discussed along with plan review and emphasis areas of the bid document.
- Pre-bid sign-up sheet attached. Revised Bid form attached which should replace original.
- Owner representative is responsible for sampling and testing of materials incorporated in the project for final acceptance.
- Date of availability of contract will be the NTP date (approximately July 2023).
- Reference points for staking will be provided by owner representative.

Questions from Pre-Bid meeting and email inquiries

- There is no item in bid schedule for undercut and backfill on this project. On the detail sheet 3-C5.1 for asphalt paving there is notes pertaining undercut and backfill and use of fabric and that Geotech engineer will make decision in using? The site of Wayne Industrial park in pass has had serious unsuitable soils issues. Should we have established a pay item made for undercut and backfill? If not, how do you pay for undercut and backfill? **Yes, separate pay items added to revise bid form as a contingency item.**
- Also detail 5-C5.1 shows driveway apron (valley gutter) We do not have a pay item set up for. Should we have an item set up for concrete driveway? **6" Driveway item added to revise bid form.**
- Waterline construction shown by others but no construction for Harry Ivey Drive appears to commence prior to Ivey Drive project. **Items for 8" Waterline has been added to the revised bid form and corrected on the plans.**
- Plans show 18" Sanitary Sewer line but bid form has 12" noted. **Correction to item on revise bid form.**



County of Wayne
Ivey Drive Extension



- Typical section shows curb and gutter on subgrade. Should there be asphalt or ABC stone under curb? **No base material required under the curb and gutter. No change to the typical section**
- For the two encasement pipe runs, are we to install just the encasement or to include the carrier pipes as well? (24" enc for 12" DIP water and 36" enc for 18" DIP sewer)
Encasement pipe only

ITEMIZED PROPOSAL

ITEM NO.	ITEM DESCRIPTION	SPECIFICATION REFERENCE	QUANTITY	UNIT	UNIT BID PRICE	AMOUNT BID
1	Mobilization	SP	1	LS		
2	Construction Surveying	801	1	LS		
3	Grading	226	1	LS		
4	Foundation Conditioning Material, Minor Structures	300	120	Tons		
5	Foundation Conditioning Geotextile	300	350	SY		
6	Aggregate Base Course	520	22	TON		
7	Incidental Stone Base	545	10	TON		
8	Milling Asphalt Pavement, 3.0" Depth	607	1,325	SY		
9	Asphalt Surface Course S9.5B	610	1,290	Tons		
10	Asphalt Base Course B25.0B	610	1,780	Tons		
11	2'-6" Concrete Curb and Gutter	846	4,900	LF		
12	4" Concrete Sidewalk	848	1,390	SY		
13	Concrete Curb Ramps	848	8	EA		
14	15" RC Pipe Culv, Class IV	310	48	LF		
15	18" RC Pipe Culv, Class IV	310	364	LF		
16	24" RC Pipe Culv, Class IV	310	632	LF		
17	18" Pipe End Section	310	3	EA		
18	24" Pipe End Section	310	1	EA		
19	Masonry Drainage Structure	840	22	EA		
20	Catch Basin Detail 4/C5.1	SP	3	EA		
21	Frame with Grate and Hood, Std. 840.03 (E)	840	2	EA		
22	Frame with Grate and Hood, Std. 840.03 (F)	840	8	EA		

ITEM NO.	ITEM DESCRIPTION	SPECIFICATION REFERENCE	QUANTITY	UNIT	UNIT BID PRICE	AMOUNT BID
23	Frame with Grate and Hood, Std. 840.03 (G)	840	6	EA		
24	Frame with Two Grates, 840.16	840	4	EA		
25	Frame with Two Grates, 840.22	840	3	EA		
26	Adjustment of Meter Boxes or Valve Boxes	858	1	EA		
27	Adjustment of Manholes	858	1	EA		
28	Rip Rap, Class B	876	15	Tons		
29	Rip Rap, Class I	876	20	Tons		
30	Geotextile For Drainage	876	255	SY		
31	Contractor Furnished, Type E Sign	901	9	SF		
32	Supports, 3-lb Steel U-Channel	903	42	LF		
33	Sign Erection, Type E (Ground Mounted)	904	3	EA		
34	Sign Erection, Relocate Type E (Ground Mounted)	904	3	EA		
35	18" Sanitary Gravity Sewer	1520	140	LF		
36	Ductile Iron Sewer Pipe Fittings	1520	130	LB		
37	4' Dia. Utility Manhole	1525	1	EA		
38	24" Encasement Pipe	1540	50	LF		
39	36" Encasement Pipe	1540	50	LF		
40	Temporary Silt Fence	1605	6,950	LF		
41	Erosion Control Stone, Class A	1610	70	TON		
42	Erosion Control Stone, Class B	1610	40	TON		
43	Sediment Control Stone	1610	210	TON		
44	Temporary Mulching	1615	12	Acres		
45	Seed For Temporary Seeding	1620	800	LB		

ITEM NO.	ITEM DESCRIPTION	SPECIFICATION REFERENCE	QUANTITY	UNIT	UNIT BID PRICE	AMOUNT BID
46	Fertilizer for Temporary Seeding	1620	4	Tons		
47	Silt Excavation	1630	70	CY		
48	Matting for Erosion Control	1631	1,375	SY		
49	1/4" Hardware Cloth	1632	925	LF		
50	Special Stilling Basin (Silt Bag)	1639	1	EA		
51	Coir Fiber Baffle	1640	105	LF		
52	Mowing	1660	9	Acres		
53	Seeding and Mulching	1660	12	Acres		
54	Seed for Repair Seeding	1661	150	LB		
55	Fertilizer for Repair Seeding	1661	0.25	Tons		
56	Seed for Supplemental Seeding	1662	275	LB		
57	Fertilizer Topdressing	1665	8	Tons		
58	Specialized Hand Mowing	1667	10	MHR		
59	Response for Erosion Control	SP	19	EA		
60	Concrete Washout Structure	SP	2	EA		
61	Fabric Insert Inlet Protection Device (Gutter Buddy)	SP	3	EA		
62	Temporary Traffic Control	SP	1	LS		
63	Paint Pavement Marking Symbols	1205	3	EA		
64	Paint Pavement Marking, 24"	1205	60	LF		
65	Paint Pavement Marking, 4"	1205	330	LF		
66	Shallow Undercut	505	600	CY		
67	Class IV Subgrade Stabilization	505	1,500	Tons		
68	Geotextile for Soil Stabilization	270	5,400	SY		

ITEM NO.	ITEM DESCRIPTION	SPECIFICATION REFERENCE	QUANTITY	UNIT	UNIT BID PRICE	AMOUNT BID
69	6" Concrete Driveway	848	30	SY		
70	8" Water Line	1510	180	LF		
71	Ductile Iron Water Pipe Fittings	1510	500	LB		
72	8" Valve	1510	1	EA		
73	Fire Hydrant	1515	1	EA		
74	Fire Hydrant Leg	1515	20	LF		

TOTAL BID PRICE	
-----------------	--

Bidder _____ (Print)

NOTE: PROPOSAL SIGNATURE REQUIRED ON PAGE 00300-14. ALL PROPOSALS MUST BE PROPERLY EXECUTED TO BE CONSIDERED A VALID BID.

BID SECURITY:

Accompanying this Proposal is a (1) _____ in the amount of (2) _____ Dollars (\$ _____).

NOTE: (1) Insert the words "bank draft," "certified check," "bid bond", or "cashiers check", as the case may be.

(2) Amount must be equal to at least five percent (5%) of the total Bid.

BIDDER'S LICENSE:

The Bidder certifies that (he/she/it) is licensed as a Bidder under the specific North Carolina state law regulating his/her/its particular trade and that the number of the license under which he/she/it now operates is _____. The Bidder has 60 days after bid opening to obtain a NC license.

BIDDER'S CERTIFICATION AS TO ORGANIZATION AND AUTHORITY:

The Bidder certifies that the Affidavit of Organization and Authority, like the other documents attached hereto, form an integral part of the Proposal, and the Bidder acknowledges that the Owner will rely on the information provided therein in reviewing the Proposal and awarding a Contract.

LIQUIDATED DAMAGES:

The Bidder agrees, further, that the Owner may retain those amounts indicated in the Contract from the amount of compensation due the Bidder, under the terms of the Contract, for each and every day that the work remains incomplete and/or unsatisfactory beyond the completion date(s) specified in the Notice to Proceed. This amount is agreed upon as the proper measure of liquidated damages the Owner will sustain, per day, by the failure of the Bidder to complete the work within the stipulated time, and it is not to be construed in any sense as a penalty.

The Bidder shall not have or bring a claim against the Owner, or raise as a defense against the imposition of liquidated damages, other construction purportedly impeding Bidder's progress or timely project completion.